

VOL. 132. PRICE 2s. 6d.


RUDIMENTARY TREATISE
ON THE
ERECTION
OF
DWELLING HOUSES.

*With Specifications, Mode of taking out Quantities,
to Determine Cost, and to make Detail Drawings.*


With Illustrations.

LONDON: JOHN WEALE.

15,8633







RUDIMENTARY TREATISE
ON THE
ERECTION OF DWELLING-HOUSES;

OR, THE
BUILDER'S COMPREHENSIVE DIRECTOR,

EXPLAINED BY
A PERSPECTIVE VIEW, PLANS, ELEVATIONS, AND
SECTIONS OF A PAIR OF SEMI-DETACHED VILLAS,
WITH EVERY REQUISITE DETAIL IN SEQUENCE FOR THEIR
CONSTRUCTION AND FINISHING;

TO WHICH IS ADDED

The Specification, Quantities, and Estimate,

COMBINED WITH NUMEROUS PRACTICAL REMARKS AND OBSERVATIONS
OBTAINED FROM MANY YEARS' EXPERIENCE, AND WHICH IT IS
ASSUMED ARE CALCULATED TO RENDER ASSISTANCE TO
THE YOUNG ARTIZAN IN EVERY DEPARTMENT OF
THE BUILDING ART.

BY

S. H. BROOKS, ARCHITECT,

AUTHOR OF SEVERAL ARCHITECTURAL WORKS.

LONDON:
JOHN WEALE, 59, HIGH HOLBORN.
1860.

PREFACE.

IN our professional practice we have frequently been applied to for a treatise on Building, to which the young student in Architecture, as well as the more mechanical one in Building, might refer and see, in an erection of simplicity or splendour, the necessity of studying all the details essential for such erection. In the office of the Architect, it frequently occurs that Buildings, from the variableness of practice, are only taken in detached parts as the work proceeds; and in the workshop of the Builder (*where they have drawings and specifications to work from*), the workman, or pupil, is seldom allowed to see them, but takes his instructions from the foreman for the portion of work to be executed; consequently he has little opportunity of acquiring the combined information requisite for the artisan in the building department to possess.

Under such considerations the present work was

projected by Mr. Weale, the publisher of the rudimentary works on the Arts and Sciences.

We have, in this sketch of a pair of dwellings, endeavoured to show and describe the manner in which a building, from the commencement of it to its completion, should be dissected and studied in its various mechanical departments, and how they work and combine with each other.

We first submit a set of probationary drawings, all drawn to the same scale; and then show the requisite details, as they would generally occur, for the completion of the carcass, and, lastly, the finishings. We have also divided the specification, quantities, and estimates, into corresponding parts. It may not always be desirable to make such a distinction, but this being a rudimentary work, we have adopted this method in order to make it as intelligible as possible to the student in the Building art. We have also given as much attention to the drainage, supply of water, ventilation, &c., as the importance of such an erection demands.

It may be proper to observe, that we have not strictly conformed to the Metropolitan Building Act, but have endeavoured to show how to erect a substantial building with every attention to the prevention of such casualties as buildings of this class are frequently liable to.

In submitting this as one of a series of designs with their details, allow us to acknowledge the information quoted from the rudimentary series of scientific works before alluded to, as we have freely referred to any of them that would assist us in conveying our views in the theoretical and practical construction of buildings. Perhaps no one is more liable to criticism than the architect for domestic arrangements; consequently there are few who devote their time to it. An architect justly observes: to produce a building fit for its purposes, and substantially beautiful at the same time, is a good step towards perfection. And probably the allusion to street architecture might with benefit be here quoted.

It is stated that, in alluding to the building at the corner of Fleet-street and Chancery-lane:—"It is a good step towards that perfection which the commercial architecture of the metropolis may reach. Fleet-street and the Strand, transformed into a succession of such edifices, might become a worthy Corso for the trading Rome, and make a grand connecting point between the region of docks and warehouses at one end; and of mansions and palaces at the other."

The building referred to is an example of a commercial edifice. It were better, indeed, that the elements of mercantile life were exemplified in its habitations.

We have surely had enough of doubtful objects in stucco, &c.: sober and straightforward, not uncomely, are the operations of upright tradesmen; so let their offices, warehouses, and shops, be truthful, substantial, cheerful, ornamental piles. Thought is not thrown away, lavished upon the improvement of our streets and mercantile edifices. A man will carry on his affairs with a healthier and clearer mind, surrounded by buildings of the class we are now writing about, than in such dens of darkness as some of the buildings in the neighbourhood of Chancery-lane.

There is such correspondence between outward forms and shows, and inner feelings and emotions, in all truthful matters, that it is far from an affair of indifference in what manner of form we transact our commerce, with what impress of form we endow our churches, or in what fashion of apartments we meet our friends and children. Providence has arranged this world upon these considerations (*so to speak*), and surrounded parts of the earth with cheerfulness and healthful beauties.

We, who in our offices and ledgers have often little enough thought of Providence, shall we esteem it indifferent whether we follow *His* precepts here, where, perhaps, we need their healthful influence most?

To architects, at least, this question is not unimportant, in an architectural point of view ; for it is in such we speak. As a sanitary question, these things are happily decided.

The importance of domestic architecture must be held in a very different estimation to what it has been, by any one who hopes to assist in the revival of all architecture, dead since the sixteenth century in our country.

We are a commercial people, and a common sense trading race ; he who can find a brotherhood in architecture with the great republics of mediæval Italy, the commercial communities of Florence, Genoa, Sienna, will perceive nothing but a source for the highest gratulations. We shall have our San Michele, Sansovino, &c. We, too, may become, amid this Kaleidoscope Europe, a stand-point of light for the after-times to reckon from ; but, to achieve this we must recognise and know ourselves. We must develop and not conceal our nationality, in arts as in all things else. From the streets of our cities and manufacturing towns, our wealth and power proceed. Let these become the stepping-stones to our temples ; as they must do, if our temples and our worship are to be sincere. It is not by forgetting, but remembering, our

commercial street-life that we shall become a people great in wisdom as in wealth.

And, indeed, why should words be multiplied about the matter? It is from these things that we are growing a wise, and, so much as there is of it, a holy people. From counting-houses, offices, warehouses, and chambers, come the schemes for baths and wash-houses, and model dwellings, ragged schools, and reformatory asylums. There on one side the genius of the shop-keeping people make them; beyond them burns the glory of future England. What if, on the other side, those who have no work to do, embroider mediæval patterns and multiply Gothic churches over the land? Let us be grateful that they do so much.

But meanwhile the architects have work to do; the public demands its streets and warehouses. Let us bear in mind how great these things are in their destinations—not, truly, all cheating and adulteration—let us remember that we are erecting buildings to-day through which the future contemplate, and the dwellers therein are preparing the paths of truth by their duties and their charities.

Let us then look upon those buildings and streets in their proper light, and build as if building for honourable men: to give our minds tone, let us discipline

them to see in this shop-keeping what promise of greatness it encloses ; and, recognising the nature of the times, perceive that it is in these very streets that the way is opened for us to commence our stone daguerreotype of the nineteenth century.

Architects are the limners for the future ; to them is perhaps entrusted the verdict which remotest times will form. All else will go, as it has gone, of Art and man's production. But Architecture, that substitute for Nature, is nourished by time as the fossil history of mankind ; and, as the shells which the nautilus and ammonite of the primæval world have formed, become to us the sure records and interpreters of their far-departed times ; so these shells under which animal life has dwelt, which religion has formed and inhabited, will become, may-be, to future races the only and fossil records whence the epoch of man shall be clearly read. For us, then, who have to mould these latest medals of creation, there is the responsibility that we rightly represent our race—our age ; it is not surely all untruthful. We forge the long chain of antique history link by link—almost from architectural remains : from these we deduce a people and a history for our edification, instruction, and example. Regarded in this light, study will soon disclose to us what valuable and unique

opportunity domestic architecture affords in our time. There are yet higher views, under whose radiance the architect begins to perceive the great influence and responsibility of his work. But the consideration of what, and how great effect upon the mind, external objects exert, may be explained on another occasion.

After thus adverting to street and mercantile architecture, we would solicit some little attention to that style suitable and applicable for domestic purposes or dwellings, that may be proposed to be erected in the suburbs or environs of such as Cities, Towns, or Boroughs, before alluded to. For wherever our places of business assume a different and more healthy character for their various purposes, and in their erection a more permanent and architectural feature, the dwellings, cottages, villas, mansions, &c., of the surrounding country approximate, in a corresponding extent, with such improvements, and, consequently, the buildings for domestic purposes become equally, combined with other classes of architecture, a reflection and monument of the people, and a key to the date of their erection. It was by witnessing this laudable improvement that is daily taking place in this City and other parts of the country, and in acquiescence with numerous applications for a series of designs suitable for the

domestic arrangement and social comfort of all grades of society, the present works were projected. It is admitted that much ignorance exists as to the necessary knowledge in the erection of an edifice, however simple : and this is a powerful drawback to the execution of such undertakings. It is also proverbial that false estimates, which are frequently tendered, dishearten many from the prosecution of their plans, in the well-founded suspicion that the expenditure will exceed the means appropriated for that purpose.

In the erection of an edifice, much depends on the choice of materials, whether for fitness or durability ; and a correct guide in the selection of them, on the most cheap and economical principles, cannot therefore but be regarded as a desideratum by every one connected with or concerned in building, whether for profit or private purposes. An elaborate and explanatory specification, with the quantities of the various materials required in each department, their prices, the amount of labour and price required for working them, with accompanying design, so that any one about to build may arrive at the total expense before commencing ; the most approved and efficient methods of water supply, drainage, warming, ventilating, according with the magnitude of the design,

will form an important feature of *the work*. We have commenced our *series* with a design for a pair of semi-detached dwellings, the estimated expense of each of which would be about £400, or £800 the pair; thereby giving a selection for the retired tradesman, or the gentleman of moderate wealth who may wish to build over his own demesne, fully detailing the most approved and efficient methods of construction, as well as finishings, as a guide to the various trades employed in the building art.

Each design is exemplified with a perspective view of the building, accompanied with all requisite plans, elevations, sections, and details, drawn to a large scale; thereby making this Volume a work of instruction to the student and builder, and one of reference to the professional practitioner in all his requirements.

CONTENTS.

	PAGE
<u>EXPENDITURE, choice of situation, drainage, and general</u>	
healthiness	1
Locality, prospect, and adjoining grounds	2
The aspect and roads	3
Sewerage, drainage, &c.	4
Traps, siphons, &c.	5
Supply of water	6
Rain water tanks, and filters	10

BRICKLAYING.

<u>Materials and tools used by the bricklayers</u>	11
<u>Weight of different kinds of earths with other tables suitable</u>	
and in reference to bricklaying	14
<u>Table for paving</u>	15
„ for tiling	16
„ of the sizes and weights of various articles	16
<u>The necessity of the bricklayer having some knowledge of</u>	
scale and geometrical drawing	17

CARPENTRY.

<u>The principal tools used in carpentry, with their application,</u>	
and general occupation of the carpenter, with a description	
of wood and iron bond	18
<u>Floors with single and double joisting, &c.</u>	19
<u>Various partitions explained</u>	20
<u>Roofing</u>	21
<u>Classification of ditto</u>	22
<u>Scarfing and joining timbers</u>	23
<u>Wall-plates, &c.</u>	24

	PAGE
The usual method of measuring carpenter's work, with the tables of lineal, superficial, and cubic measure	25
A table explaining the quantities of timber making one load	26
" " " " on average weighing one ton	26
The number of cubic feet in every square of flooring, roofing, or quarter partitions of different dimensions	27
" " of naked floors without girder	27

MASON.

The trade of the mason explained; stone cutting, ditto.	28
The application of steam power to the same	29
The various tools used by the mason	29
The construction of scaffolds	30
The moveable derrick crane explained	31
The lewis, ditto, ditto	32
The method of working stones generally	33
Terms generally used by quarry men; joggle, joints, and dowels explained	34
Iron cramps and their uses	35
The usual custom of measuring mason's work	35
A table of the weights of the different kinds of stone	36

PLUMBING.

The work of the plumber with his necessary tools explained	36
The manufacture of milled and sheet lead-pipes, &c., and the laying of sheet-lead	37
The fitting-up of cisterns, water-closets, pumps, &c.	38
A table of the weight of lead pipes per yard	38

ZINC-WORKER.

The applicability of sheet zinc for building purposes	39
---	----

SMITH AND IRONFOUNDER.

The various uses of wrought and cast iron as applied to builder's purposes	39
The methods adopted for smelting iron	39
Steam power as applied to the blast furnaces for working the forge hammers and rolling mills	40
The method of casting iron	40
The hot-blast furnace explained	41

	PAGE
<u>A description of various castings applied for different purposes</u>	<u>42</u>
<u>The conversion of forge-pig into bar iron</u>	<u>43</u>
<u>A table of the weight of metal; coppersmith and warming apparatus</u>	<u>44</u>

SLATER.

<u>The operations which pertain to building</u>	<u>45</u>
<u>Table of the sizes of roof, slating, &c.</u>	<u>47</u>

PLASTERER.

<u>Description of tools used</u>	<u>48</u>
<u>Materials, &c.</u>	<u>48</u>
<u>Operations for plastering</u>	<u>50</u>
<u>Setting, stucco, rough cast, puzzolan, &c.</u>	<u>51</u>
<u>Memoranda applicable to plasterer's work</u>	<u>53</u>

JOINERY.

An endeavour to explain joiner's work, with the application of their tools, &c.	54
The mechanical operations of the joiner, &c.	58
Glue. Its component parts	60
Tables for joiners	61
Sawing	62

IRONMONGERY.

Description of hinges	63
Locks, bolts, &c.	64

GLAZIER.

The tools used, the material required, and the glazier's business	65
A table applicable to glazing	66

PAINTER, PAPER-HANGER, AND DECORATOR 67

Painting	68
Graining	69

	PAGE
<u>THE APPLICATION OF SCALES AND THE ELEMENTARY</u>	
<u>PRINCIPLES OF GEOMETRY</u>	72
Its uses, &c.	73
<u>DIMENSIONS OF DRAWING-PAPER</u>	74
Hints on the management of drawing-paper	75
Mounting paper on canvas	76
In choice of pencils	77
<u>DRAWING INSTRUMENTS.</u>	
The use of the compasses or divider	78
Hair compasses	79
Compasses with moveable points	80
Bow compasses	81
Tubular compasses	83
Portable or turning compasses	85
Large screw dividers	87
Spring dividers	88
Wholes and halves	89
Proportional compasses	91
Triangular compasses	94
Beam compasses	96
Knife-file, screw-driver	98
Drawing pens	99
Road pens	100
Dotting pens	101
Pricking or tracing point	102
Drawing pins	103
<u>SPECIFICATIONS OF CARCASS OF BUILDING</u>	104
" Excavator	104
" Bricklayer	105
" Carpentry	109
" Smith and Iron-founder	116
" Stone Mason	118
" Plumber	119
" Slater and Zinc-worker	120
" Finishings, joinery	121—130
" Plasterers	130
" Mason's work	133
" Furnishing ironmonger	134

	PAGE
<u>SPECIFICATIONS.</u>	
Bell-hanger, Plumber	137
Glazier, Painter, Paper-hanger, . . .	139
General conditions	140
<u>QUANTITIES OF THE VARIOUS MATERIALS REQUIRED .</u>	<u>141</u>
Excavator, Bricklayer	141
Carpenter, Smith and Iron-founder, and Plumber	142
Mason, Slater	143
Zinc-worker	143
Requisite materials for the finishings .	144
Joiner's work	144—148
Plasterer's work	149
Mason, Furnishing ironmonger	150
Bell-hanger and Plumber	151
Glazier, Painter, and Paper-hanger . .	152
<u>ENGRAVINGS.</u> See List of Plates	<u>153—172</u>
<u>DESCRIPTION OF INSTRUMENTS</u>	<u>181—206</u>

DESCRIPTION OF PLATES.

	PAGE
Perspective view of the proposed pair of semi-detached cottages or dwellings	153
Block-plan of ground, showing position of rain-water tank, drains, traps, siphons, &c., with a section describing their fall, current, &c., to and from the said tank to principal sewers	154
Block-plan, showing position of buildings, gardens, yard, &c., and the situation of the gully-traps, siphons, &c.	155
Basement-plan, comprising breakfast-room, kitchen, back kitchen, cellars, store-closets, water ditto, coal-cellars, pantries, with the position of their sinks, dressers, &c.	156
Plans of ground-floor, comprising porticos, entrance halls, dining-rooms, parlors, lobbies, &c., with stairs to front and back entrances, and roofs over offices	157
Plans of chamber-floor, arranged for front and back, bed-rooms, front dressing-rooms, water-closets, roofs over offices, &c., &c.	158
Plan of attics, consisting of two front and two back bed-rooms, with a portion of principal roof, gutters, &c.	159
Plan of roofs, showing chimney flues, roof of dormer lights, ridge, flashings, hips, gutters, &c., &c.	160, 161
Entrance elevation	162
Back elevation	163
Longitudinal section of carcass, showing flues, &c., with elevation of kitchen, offices, &c., and ground line of front and back of building	164
Transverse section of carcass, showing flues and position of stairs, with the height of story figured thereon, and the ground lines of back and front of building	165
<p>Traps for drain, &c., exemplified in six figures. Fig. 1. The section of drain that can be easily cleaned without the necessity of</p>	

removing any portion of the earth, &c. Fig. 2. A simple sort of trap applicable to this form of drain. Fig. 3. A section and plan of a drain trap to be formed of iron or earthen ware. Figs. 4, 5, 6. A similar description exemplified for various purposes. See *Description*, page 51 166

Plan and section of rain-water tank, with slate filtering machine, so applied as to be taken out for cleaning, &c. 167

Plan of brick piers, sleepers, and joists, consisting of six figures, viz. Fig. 1. Plan of pier. Fig. 2. Section of pier sleepers and joists. Fig. 3. Transverse section of the same. Fig. 4. Plan of pier, sleepers, and floor-joists. Fig. 5. Method of notching sleepers for receiving floor-joists, &c. Fig. 6. Floor joists, bridged for fixing upon sleepers 168

Details of brickwork, exemplified in six figures. Fig. 1. Footings of external and party walls. Fig. 2. Footings, showing projections for sleepers, &c. Fig. 3. Chimney breast, brick and wood trimmers, with herring-bone trussing. Fig. 4. Floor joists, with ditto. Fig. 5. The elliptical arch, with its radii for brickwork. Fig. 6. The segment of a circle for the same 169

Details of brickwork for chimneys. Fig. 1. Plan of foundation. Fig. 2. Shows a different method with fenders. Fig. 3. Elevation of chimney breast, with chimney bars. Fig. 4. Section of the same and back. Fig. 5. Brick corbels 170

Plan and section of chimney breast and trimmers. Fig. 1. Plan. Fig. 2. Section of the same 171

Details of floor-joists for first, second, and third floors, &c., with the application of their tension rods. Fig. 1. Plan of walls, wall-plates, floor-joists, tension-rods, &c. Section of end of the same. Fig. 3. A perspective sketch, showing their combination. Fig. 4. Transverse trusses to floor-joists. Fig. 5. Floor-joists, with sound boarding applied 172

Plan and section of a portion of roof. Fig. 1. Section showing the whole principal rafters at each hip. Fig. 2. Plan of the same, showing the position of whole and half principles, &c. 173

Details of roof. Fig. 1. Part of principal rafter, with all auxiliaries, &c. Fig. 2. Elevation of bracket. Fig. 3. Head and foot of queen-posts, &c., with their clips and ties. Fig. 4. Side elevation of the same. Fig. 5. King-posts, tie-beams, rafters, &c. 174

Plan and elevation of portion of bay window, showing external finishing 175

Details of entrance porch. Fig. 1. Plan of side and pilaster. Fig. 2. Plan of spandrel. Fig. 3. Elevation of the same, with steps,

&c. Fig. 4. Section of cornice, frieze, &c. Fig. 5. Elevation of the same. Fig. 6. Ditto of the base	PAGE 176
Transverse section, showing partitions. Fig. 1. Partition for ground and chamber floors. Fig. 2. Heads and sills of the same. Fig. 3. Struts and braces. Fig. 4. Plan of a portion of cistern in roof. Fig. 5. Section of the same, &c.	177
Longitudinal section, showing partitions. Fig. 1. Partition for ground and chamber floors. Fig. 2. Head and braces. Fig. 3. Door heads	178
Details of finishing for the various floors. Fig. 1. For doors, windows, &c., attic floor. Fig. 2. Grounds and skirting chamber floor. Fig. 3. Windows, doors, &c., chamber floor. Fig. 4. Windows and doors, back parlor and breakfast room	179
Finishings for bay windows. Fig. 1. Portion of plan, showing sash frame; angular metal bar groove for revolving shutters, &c. Fig. 2. Section of the same, showing box for machinery of revolving shutters, &c.	180

ON THE
ERECTION OF DWELLING-HOUSES.

CHAPTER I.

WHEN it is determined to erect an edifice of any description, the first and primary consideration should be the money intended to be expended; the next, when possible, the choice of situation, not only as respects its efficient drainages, dryness, and general healthiness, but also as regards its relative position with other buildings, and, when a number are proposed to be erected on a new site, to their being so placed as not to interfere with or injure the effect of the surrounding scenery. Consequently, it is desirable, after a space of ground has been appropriated for building purposes, surveyed, levelled, plotted, &c., that a perspective bird's-eye view should accompany the plans, not so much that the design there exhibited should be carried into execution, but that they shall not interfere with the principal prospect, and as little as possible intercept the view or prospect of each other.*

* Mr. Bruce Allen, 20th volume of this series.

The "lamentable way in which the beauty and loveliness of the finest landscape may be injured or destroyed by buildings and grounds is exemplified by the far-famed view from the top of Richmond Hill. What it was when Thomson wrote it would perhaps be difficult to say; but now—instead of the houses and villas, and the gardens about them, harmonising with and forming a part of the general view to be examined in detail—after the eye is satiated with the whole, it is first struck with the glaring newness (*for they all seem as if they were painted and pointed regularly once every year*) of first one and then another of these regularly built boxes placed in the middle of a large square garden or lawn, and surrounded by a high fence, and the country round being thickly wooded close up to the wall, the formality of the grounds is rendered truly distressing."

A landscape made up of a collection of square fields, surrounded by regular hedge-rows, and dotted here and there with cubical, newly-painted boxes and straight roads, may satisfy, as it commonly does, the owners of the several lots, but can never be otherwise than painful to the eye of an artist. But what is called landscape scenery in England is mostly of this description, and appears to be admired on the ground of its cultivation and plenty, qualities perfectly distinct from it, considered as a beautiful object.

If any general rule could be given for the laying out of building grounds, it would be to avoid everything considered essential—long rows of houses all of the

same height, semi-circular rows with a tall house in the centre, &c. The unsightliness of the common plan will be seen by contrasting the picturesque cities of York or Lincoln with the formal and uninteresting appearance of Bath or Cheltenham, or they may be seen side by side in the old town of Hastings and the modern triumphal-arched town of St. Leonards. From this cause, London, though the largest, is probably the least picturesque city in Europe. Mr. Disraeli, in his "Tancred," has ably contrasted the old part of London with the new, and has pointed out the absence of all interest of character in the modern portions. Strange that he should have been able to see so clearly that which professors of the art have not only been blind to, but are continually helping to increase.

If the building is proposed to be placed by the side of a public road, it would be desirable to erect the principal front in direction of as near south-east or south-west as possible. The principal front, therefore, can only in certain situations be parallel to the public road, but the preference should be given to the south-east. The complete drainage of a house is a point of the utmost importance, as upon it mainly depends the health and comfort of its inmates—and not only is it requisite that the drainage be perfect; but it must be as little liable as possible to get out of order, and when disturbed for the purpose of cleaning, should be capable of reinstatement with the materials at first used. The most essential points to be attended to in the drainage of buildings generally, where main sewers

are formed, are the following :—Assuming in this plate that the main sewer is constructed in the front or principal road—and we desire to convey all our soil, waste water, &c., into it. On the block plan in Plate III., upon which are shown the grounds, buildings, &c., mark the most accessible places for fixing the tank, gulleys, traps, siphons, &c. ; and then upon a skeleton block-plan and section, Plate II. ; show the principal pipes for the conveyance of water to the tank, and the waste and soil drains, into the principal sewer, with the necessary falls, traps, and gulleys required.

Soilage-drains are found to be of sufficient dimensions, and the soil and water find ample room to pass along in a tube, equal in capacity to a cylinder of 6 inches diameter. They should have a fall of not less than 6 inches in every 100 feet, and more where possible.

They should be made water-tight, that the portions of the soilage may not escape and leave the solid matters in the drain.

They should have as much waste water pass through as possible, to carry the soilage onward, and to prevent any solid matters from being deposited within them. To prevent the foul air generated in, or returning by the drains, the waste-ways should be double-trapped by a bell-trap at the sink where the waste water enters, and by a well-trap short of the inlet to the drain.

All drains should be so constructed as to admit of being opened for the purpose of cleansing without

breaking them, and of the displaced portion being afterwards replaced. A great defect in the common soilage drains, whether built in brickwork or of earthenware pipes, is, that they have to be broken up whenever they require cleansing; this might be obviated by using drains of the form represented on Plate XIII., fig. 1.

The upper tile *a*, in the diagram, could at any time be lifted off, and the drain cleansed, without the necessity of breaking the drain, or of removing any portion of the earth, except that immediately covering it. Fig. 1.

A simple kind of trap, applicable to this form of drain (*its transverse section being the same*), and equally effective as regards its capability of being readily cleansed, is shown in fig. 2.

A section and plan of a drain-trap, to be formed of iron or earthenware, is shown in the same plate, figure 3. the tile *a* should not be fixed down, but be left loose, so as to allow of its ready removal, and the cleansing of the trap. It would, perhaps, be as well to leave the whole of the trap loose, which would allow of its being lifted out, and any obstruction removed. This form of drain-trap is suitable for yards, areas, &c., and, slightly modified, for streets. Figs. 4 and 5.

The waste water from sinks does not seem to be sufficient to cleanse thoroughly these drains; but this may be effected, and at little expense, by simply shortening by one or two inches or more the waste-pipes of the cistern in each case. For as the water runs off by the waste-pipe, the cistern would continue to fill from

the main faster than it runs off, till the rate of its coming in (which is *always regulated* by the ball-cock, and becomes gradually less as the ball rises), became exactly equal to the quantity running off; and this it would continue to do until stopped at the main, the quantity of water running off being regulated by the length of the waste-pipe.

By this plan every house-drain might be daily cleansed with water, and kept at a low temperature at a trifling expense, that is, at merely the cost of water from each cistern; *though small*, it would in each street amount to a considerable body; it would serve to cleanse the main sewers themselves without the necessity of any separate apparatus as proposed above. As before remarked, the air of a house can never be kept pure unless the bell and water-traps act perfectly, which they seldom or ever do as at present constructed; for the bells of the traps in common use for sinks and other places are usually left loose for the convenience of cleansing them, as various matters find their way into the trap, and the escape becomes choked; and unless the bell is immediately replaced after the foreign matter is removed, the trap becomes, of course, useless. To remedy this defect, the bell is sometimes soldered down, when the trap, after a time, becomes filled up, and the bell is forcibly moved and laid aside. A simple apparatus for cleansing the traps when the bells are soldered down has been contrived* which would be perfectly effective if its careful preservation and

* By Mr. Hosking.

use by servants and others could be relied on. But the bell-traps in common use may be much improved, and made to answer all the uses required of them; be always certain of action, and yet admit of occasional cleaning, by fixing the bell to the trap by a hinge, as shown at Plate XIII., fig. 5, with a projecting piece of metal to prevent its being but partially raised; so that the bell, being held up while the trap is cleaned by the knob *b*, as indicated by the dotted lines, falls into its place by its own weight, and can consequently never fail. The use of the metal top *a*, is to prevent the bell being thrown back and left so; it is on this plate shown in section, fig. 5. The sink may be of wood, lined with lead, of stone, or slate; or, perhaps, better than those, of earthenware, which, among other advantages, would allow of the trap being made with it, and forming a part of itself, as shown in fig. 6.

Supply of Water.

The arrangements for distributing a supply of water over the different parts of a building will depend very materially on the nature of the supply, whether constant or intermittent. The most common method of supply is from water-works, by pipes which communicate with private cisterns, into which the water is turned at stated intervals.

A cistern in a dwelling-house is always more or less an evil, it takes up a great deal of space, costs a great deal of money in the first instance, and often causes

inconvenience from leakage, from the bursting of the service pipes in frosty weather, and from the liability of self-acting cocks to get out of order. The common material for the cistern itself is wood lined with sheet lead ; but slate cisterns have been much used of late. The service or feed-pipe for a cistern, in the case of an intermittent supply, must be sufficiently large to allow of its filling during the time the water is turned on from the main. The flow of water into the cistern is regulated by a ball-cock, so called from its being opened and shut by a lever with a copper or zinc ball which floats on the surface of the water. The service pipes to the different parts of the building are laid into the bottom of the cistern, but should not come within an inch of the actual bottom, in order that the sediment, which is always deposited in a greater or less degree, may not be disturbed ; the mouth of each pipe should be covered by a rose, to prevent any foreign substance being washed into the pipes and choking the taps. To afford a ready means of clearing out the cistern, a waste-pipe is inserted quite at the bottom, sufficiently large to draw off the whole contents in a short time when required, into this waste-pipe is fitted a standing waste which reaches nearly to the top of the cistern and carries off the waste water, when from any disarrangement in the working of the ball-cock the water continues running after the cistern is full. To prevent any leakage at the bottom of the standing waste, the latter terminates in a brass plug which is ground to fit a washer inserted at the top of the waste-pipe.

Where the supply of water is constant, instead of being intermittent, private cisterns may be altogether dispensed with, the main pipes not being required to discharge a large quantity of water in a short time may be of smaller bore, and consequently cheaper, and a considerable length of pipe is saved, as the water can be laid on directly to the several taps, instead of having to be taken up to the cistern and then brought back again. The constant flow of water through the pipes also much diminishes the risk of their bursting in frosty weather from freezing of their contents, when there is not a regular supply of water from the mains of water works, if any, as it frequently occurs. In new localities, wells are sunk, and the water raised by means of pumps, and conveyed by pipes to its required destination; and as rain-water is considered the purest of all water, it may be considered desirable to construct a filtering tank for its reception; and where there is a want of wholesome water, a tank might be constructed large enough to receive the rain-water from the roofs of a number of houses. This would insure a constant supply of soft and pure water for all domestic purposes.

The same would apply where there is no complete system of sewerage; a large manure tank might be constructed.

It is calculated that the average quantity of water which falls on a square yard of surface in Britain, in a year, amounts to about 120 gallons, which, for a building containing 100 square yards of roof, gives 12,000

gallons, an ample quantity for all purposes. Rain-water tanks are generally constructed in the following manner: The ground being excavated, the bottom is laid with one or two courses of bricks, upon which two or three courses of tiles are laid in cement, and the sides and ends are formed with brickwork in cement, and the whole is then rendered with cement about an inch in thickness. The top is either domed or covered with a flat stone. To filter water into a tank of this kind a small well or cistern is constructed, the bottom of which is perforated to admit the water upon which the charcoal is laid, and then covered over with another perforated plate, as shown and described on Plate XIV.; a pump is then applied to the smaller cistern or filter for the supply. This, as will be perceived on inspection, would admit of ready cleaning, as the filter could at any time be lifted out. Plate XIV., fig. 1, is a section of the rain-water tank; H the cistern; A the stone cover to the same; E E the portion for the filtered water; F filtering medium; c c the perforated portion for allowing the water to force itself through the filtering medium F; J rod for lifting the filters out of cistern when it requires cleaning; c the supply pipe; D waste ditto. Fig. 2 is a plan of the same tank; A cistern; B slate or earthenware filter. A modification of this arrangement may be adopted for smaller buildings, and a bucket may be applied for dipping the water from the filter.

CHAPTER II.

BRICKLAYER.

Our drainage, water supply, &c., having been considered as far as relates to our design, perhaps the next consideration would be for the erection of the carcass of the building, and probably we cannot do better than commence with the bricklayer.* The business of a bricklayer consists in the execution of all kinds of work in which brick is the principal material; and in London it always includes tiling, and paving with bricks or tiles. Where undressed stone is much used as a building material, the bricklayer executes this kind of work also; and in the country the business of the plasterer is sometimes connected with the above-named branches. And here, perhaps, we cannot do better for the instruction of the young bricklayer than state the list of tools required by him, and the classification of them, necessary for their various purposes.

The tools of the bricklayer are the *trowel*, to take up and spread the mortar, and to cut bricks to the requisite size; the *brick-axe* for shaping them to the required bevel; the *tin-saw* for making incisions in them to be cut with the *axe*; and a *rubbing-stone* to rub the bricks

* Mr. E. Dobson, 22nd volume of this series.

smooth after being roughly axed into shape. The *jointer* and the *jointing-rule* are used for running the centers of the mortar joints; the *raker* for raking out the joints of old brickwork, previous to repointing; the *hammer* for cutting chases and splays; the *banker*, which is a piece of timber about six feet long, raised on supports to a convenient height, to form a table on which to cut the bricks to any gauge for which moulds and bevels are required. The *crow-bar*, *pick-axe*, and shovel are used in digging out the foundation; and the rammer in punning the ground round the footings, and in rendering the foundation firm where it is soft, by beating or ramming.

To set out the work and keep it true, the bricklayer uses the *square*, the *level*, and the *plumb-rule*. For circular work he uses templets and *battering-rules*; *lines*, and *pins* are used to lay the courses by, and *measuring-rods* to take dimensions when brickwork has to be carried up in conjunction with stonework; the height of each course must be marked on a *gauge-rod*, that the joints of each may coincide.

The bricklayer is supplied with bricks and mortar by a labourer, who carries them in a hod; the labourer also makes the mortar, and builds and strikes the scaffolding.

The bricklayer's scaffold is constructed with *standards*, *ledgers*, and *putlogs*.

The standards are fir poles, from forty to fifty feet long, and six or seven inches in diameter at the butt ends, which are firmly bedded in the ground. When

one pole is not sufficiently long, two are lashed together, top and butt, the lashings being tightened with wedges. The ledgers are horizontal poles, placed parallel to the walls and lashed to the standard for the support of the putlogs. The putlogs are cross pieces, usually made of birch, and about six feet long, one end resting in the wall, the other on a ledger. On the putlogs are placed the scaffold-boards, which are stout boards hooped with iron at the ends, to prevent them from splitting.

A bricklayer and his labourer will lay in a day about 1000 bricks, or about two cubic yards.

The tools required for tiling are the *lathing-hammer*, with two gauge marks on it, one at 7 and the other at $7\frac{1}{2}$ inches; the iron *lathing-staff*, to clinch the nails; the *trowel*, which is longer and narrower than that used for brick-work; the *bosse*, for holding mortar and tiles, with an iron hook to hang it to the tiles or to a ladder; and the *striker*, a piece of lath about 10 inches long, for clearing off the superfluous mortar at the foot of the tiles.

Brickwork is measured and valued by the rod or by the cubic yard, the price including the erection and use of scaffolding, but not centering to arches, which is an extra charge.

Bricknogging pavings and facings by the superficial yard.

Digging and steining of wells and cesspools by the foot in depth according to size, the price increasing with the depth.

Plain tiling and pantiling are valued per square of 100 feet superficial.

A journeyman bricklayer receives from 4*s.* to 5*s.* 6*d.* and a labourer from 2*s.* 6*d.* to 3*s.* 6*d.* per day.

The following memoranda may be useful:—

WEIGHTS OF DIFFERENT KINDS OF EARTH.

13	cubic feet of chalk	weigh	.	.	one ton.
17	" clay	"	.	.	} one ton each.
18	" night soil	"	.	.	
21½	" gravel	"	.	.	
23½	" sand	"	.	.	

Night soil is removed in carts containing 45 cubic feet or 2½ tons.

Twenty-seven cubic feet, or 1 cubic yard, is called a single load, and 2 cubic yards a double load.

A measure of lime is 27 cubic feet, and contains 21 strike bushels.

A bricklayer's hod measures 1 ft. 4 in. × 9 × 9, and contains 20 bricks.

A rod of brickwork measures 16½ square, 1½ brick thick (*which is called the reduced or standard thickness*) or 272 ft. 3 in. superficial or 306 cubic feet, or 11½ cubic yards.

A rod of brickwork, laid four courses to a foot in height, requires 4353 stock bricks.

Ditto 11½ inches to 4 courses, 4533 stock bricks.

These calculations are made without allowing for waste, which is necessary, because the space occupied by flues, bond-timber, &c., and for which no deduction is made, more than compensates for any waste; and in building dwelling-houses, 4540 stocks to a rod is sufficient.

If laid dry, 5370 to the rod.

4900 ditto in wells and circular cesspools.

A rod of brickwork, laid 4 courses to gauge 12 in., contains 235 cubic feet of bricks and 71 cubic feet of mortar, and weighs about 15 tons.

A rod of brickwork requires $1\frac{1}{2}$ cubic yards of chalk lime, and 3 single loads of sand, or 1 cubic yard of stone lime, and $3\frac{1}{2}$ loads of sand or 36 bushels of cement, and an equal quantity of sharp sand.

A cubic yard of mortar requires 9 bushels of lime and 1 load of sand.

Lime and sand, and likewise cement and sand, lose one-third of their bulk when made into mortar.

The proportion of mortar or cement, when made up, to the lime or cement and sand before made up is as 2 to 3.

Lime or cement and sand to make mortar require as much water as is equal to one-third of their bulk.

A cubic yard of concrete requires 34 cubic feet of material; or if the gravel is to the lime as 6 to 1, a concrete will require 1.1 cubic yard of gravel and sand, and 3 bushels of lime.

Facing requires 7 bricks per foot superficial.

Gauged arches 10 ditto, ditto.

Bricknogging, per yard superficial, requires 30 bricks on edge, or 45 laid flat.

PAVING.

Stock bricks laid flat require	36	per yard superficial.
Paving ditto on edge	52	„
Paving ditto laid flat	36	„
Ditto on edge	82	„

Dutch clinkers	require 140 per yard superficial.
12-inch paving tiles	" 9 "
10-inch ditto	" 13 "

TILING.

Description.	Gauge in Inches.	No. required per Square.
With pantiles	12	150
Ditto	11	164
Ditto	10	180
Ditto	4	600
Ditto	3½	700
Ditto	3	800

N.B.—A square of pantiling requires one bundle of laths, and one cwt. and a quarter of sixpenny nails.

A TABLE

Of the Sizes and Weights of various Articles it may be considered useful to refer to.

Description.	Length.	Breadth.	Thickness.	Weight.
	ft. in.	ft. in.	ft. in.	lbs. ozs.
Stock-bricks . . . each	0 8¾	0 4½	0 2½	5 0
Paving ditto . . . "	0 9	0 4½	0 1¾	4 0
Dutch clinkers . . . "	0 6½	0 3	0 1½	1 8
12-inch paving-tiles . . . "	0 11¾	0 11¾	0 1½	13 0
10-inch ditto . . . "	0 9¾	0 9¾	0 1	8 9
Pantiles	0 10½	0 6½	0 0¾	2 5
Pantile laths, per 10-feet bundle	120 0	0 1½	0 1	4 6
Ditto, 12-feet ditto . . .	144 0	0 1½	0 1	5 0
N.B. A bundle contains twelve laths.				
Plain tiles, per bundle . .	500 0	0 1	0 0½	3 0
Thirty bundles of laths make a load.				

To ascertain the quantity of brickwork contained in a well, take the diameter, allowing the thickness on one side, three times of which, and one-seventh, will be the circumference. This should be multiplied by the depth, and the contents brought into brick and half work.

To find what quantity of water a well will hold, multiply half the circumference by half the diameter; this should be multiplied by the depth, and will give the number of cube feet which will contain 6 gallons and 1 pint each.

We so far have endeavoured to explain the various tools and principal materials used in the trade of a bricklayer, and at the same time would impress upon the young artisan to give some attention to geometrical drawing; for, unless he has some knowledge of this useful auxiliary, he will never be enabled to read or comprehend the design he may be entrusted with to execute. For, even in the simple turning of an arch over a centre already fixed for him, unless he knows that every brick should radiate to a centre and knows how to find that centre, he will never be certain of making sound work to his arch. We have endeavoured to show this in two diagrams shown on Plate XVI., figs. 4 and 5. Let 1—2 be the opening or span of the segment of an arch; *E F* the rise; stretch a line, or apply a straight edge, from 2 to *F*, and mark the centre *c*; apply the square, and where it intersects the centre of your rise, *B F* will be centre for the arch; consequently, *B* will be the converging point for all the bricks on that arch. Fig. 5 merely exemplifies the same principle applied to the ellipsis, as it should to every other description of arch.

CHAPTER III.

CARPENTER.

THE business of the carpenter consists in framing timber together for the construction of *floors, partitions, roofs, &c.*

The carpenter's principal tools are the axe, the saw, and the chisel, to which may be added, the chalk-line, plumb-rule, level, and square. The work of the carpenter does not require the use of the plane, which is one of the principal tools of the joiner; and this forms the principal distinction between these two trades, the carpenter being engaged in the rough frame-work, and the joiner on the finishings and decorations of buildings.

Probably the first occupation a carpenter will have in a building is the preparation and laying of bond-timber, making and fixing of centers, &c. Bond-timber and wood-bricks were formerly used as the only means for providing against irregular settlement in the brick-work. There is, however, a great objection to the use of timber in the construction of a wall, as it shrinks away from the rest of the work, and often endangers its stability by rotting. Instead of bond-timbers, hoop-iron bond is now very generally used. This is formed

of iron-hooping tarred, to protect the iron from contact with the mortar, and laid in the thickness of the mortar joint. This forms a very permanent longitudinal tie, and has all the advantages, with none of the disadvantages, of the bond-timbers.

Floors.

The assemblage of timbers forming any naked flooring may be either single or double. Single flooring is formed with joists reaching from wall to wall, where they rest on plates of timber, built into the brickwork, and called wall-plates. The floor-boards are nailed over the upper edges of the joists, whose lower edges receive the lathing and plastering of the ceilings. Double floors are constructed with stout binding joists, a few feet apart, reaching from wall to wall, and supporting ceiling joists, which carry the ceiling, and bridging joists, on which are nailed the floor-boards. In double framed flooring, the binders, instead of resting on the walls, are supported on *girders*. Single flooring is in many respects inferior to double flooring, being liable to sag or deflect, so as to make the floors concave; and the situation of the joists occasions injury to the ceilings, and likewise shakes the walls. This may be prevented in single floors by herring-bone, trussing them, and introducing an iron rod from wall-plate to wall-plate, as shown and described on Plate XIX., figs. 1, 2, 3, and 4. Fig. 5 shows the method of applying sound boarding puggings, &c., to prevent any sound passing between the upper and lower floors. In double floors, the

stiffness of the binders and girders prevents both deflection and vibration, and the floors and ceilings hold their lines, that is, retain their intended form much better than in single flooring.

If it were not for the increased expense it would be much better for all the joists of a single floor to be laid on a plate supported by projecting corbels, which prevents the wall being crippled in any way by the insertion of the joists. The plates of basement floors are best supported on small piers carried up from the footings. This is an important point to be attended to, as the introduction of timbers into a wall is nowhere likely to be productive of such injurious effects as at the foundations, where from damp and imperfect ventilation all woodwork is liable to speedy decay.

Partitions.

The partitions forming the interior divisions of a building, may be either solid walling of brick or stone, or they may be constructed entirely of timber, or they may be frames of timber, filled in with masonry or brickwork. It would always be best for durability, and security against fire, to make the partitions of solid walling; but this is not always practicable; and in the erection of houses they are generally made of timber.

The principles to be kept in view, in the construction of framed partitions, are very simple. Care must be taken to avoid any cross strain, and they should not in any way depend for support upon subordinate parts

of the construction, but should form a portion of the main carcass of the building, and quite independent of the floors which should not support, but be supported by them.

When a partition extends through two or more storeys of a building, it should be as much as possible a continuous piece of framing, with strong sills, at proper heights, to support the floor-joists.

Where openings occur as for folding-doors, or where a partition rests on the ends of the sill only, it should be strongly trussed, so that it is as incapable of settlement as the walls themselves.

From want of attention to these points, we frequently see in dwelling-houses, floors which have sunk into curved lines, doors out of square, cracked ceilings and broken cornices, and gutters that only serve to conduct the roof-water to the interior of the building, to the injury of ceilings and walls, and the great discomfort of the inmates.

Roofing.

In roofs of the ordinary construction, the roof-covering is laid upon rafters, supported by horizontal purlins, which rest on upright trusses, or frames of timber, placed on the walls at regular distances from each other. Upon the framing of the trusses depends the stability of the roof. The arrangement of the rafters and purlins being subordinate matters of detail. The timbering of a roof may be compared to that of a double-framed floor; the trusses of the former corre-

sponding to the girders of the latter, the purlins to the binders, and the rafters to the joists.

Timber roofs may be divided into two heads :—

First. Those which exert merely a vertical pressure on the walls on which they rest.

Secondly. Those in which advantage is taken of the strength of the walls to resist a side thrust, as in many of the gothic open-timbered roofs.

Trussed roofs exerting no side thrust on the walls, consist essentially of a pair of principals, or principal rafters, and a horizontal tie-beam, and in large roofs these are connected and strengthened by king and queen posts and struts.

The collar beam roof is the most simple truss, in which the tie is above the bottom of the feet of the principal, which is often done in small roofs for the sake of obtaining height. In this roof the feet of both common and principal rest on a wall-plate, and the tie is called a collar. The purlins rest on the collar, and the common rafters butt against a ridge running along the top of the roof. This kind of truss is only suited for very small spans, as there is a cross strain on that part of the principal below the collar which is rendered harmless in a small space by the extra strength of the principal ; but which, in a larger one, would be very likely to thrust out the walls.

In roofs of larger spans the tie-beams are placed below the feet of the principals, which are tenoned into and bolted or strapped to them. To keep the beam from sagging, or bending by its own weight, it is suspended

from the head of the principal by a king-post of wood or iron. The lower part of the king-post affords abutments for struts, supporting the principals immediately under the purlins, so that no cross-strain is exerted on any of the timbers in the truss, but they all act in the direction of their length, the principals and struts being subjected to compression, and the king-post and tie-beams to tension. The common rafters butt on a pole plate, the tie-beams resting either on a continuous wall-plate, or on short templets of wood or stone. Where the span is considerable, the tie-beam is supported at additional points by suspension pieces called queen-posts, from the bottom of which spring additional struts, and by extending this principle *ad infinitum* we might construct a roof of any span, were it not that a practical limit is imposed by the nature of the materials.

Having in a cursory manner described the principles of framing, we will now endeavour to describe some of the principal joints made use of in framing. Timbers that have to be joined in the direction of their length, are what is termed scarfed together, that is, an oblique cut is made across the width of one piece at the end proposed to be joined, and a corresponding one to the piece proposed to be added to it, with bird's-mouth bevels at each end, and notches in the middle to admit of oak or iron wedges; these are then placed together and secured either by iron bolts or straps. The king-post is connected with the tie-beam by a tenon and mortice, and the post should be cut somewhat short, to give the power of screwing up the framing after the timber has

become fully seasoned. The tie-beam may be suspended from the king-post either by a bolt or by a strap passed round the tie-beam, and secured by iron wedges or cotters passing through a hole in the king-post; this last is the more perfect, but at the same time the more expensive of the two methods.

The king-post is generally cut with joggles for the principal rafters and struts to abutt against and frame into. The ends of the principal rafters and struts should be cut off as nearly square as possible, and tenoned into the joggles—otherwise when the timber shrinks, which it will more or less, the thrust is thrown upon the edge only, which splits or crushes under the pressure and causes settlement.

The wall-plates are halved and dove-tailed together, and the tie-beams coggled upon them, the purlins bridged upon the principal rafters, and the common rafters notched upon the purlins. And it should be observed, as a general rule, all timbers should be notched down to those on which they rest, so as to prevent their being moved either lengthways or sideways. Where an upright post has to be fixed between two horizontal sills, as in the case of the uprights of a common framed partition, it is simply tenoned into them, and the tenons secured with oak pins driven through the cheeks of the mortice.

The carpenter requires considerable bodily strength for the handling of the timbers on which he has to work; he should have a knowledge of mechanics, that he may understand the nature of the strains and thrusts

to which his work is exposed, and the best method of preventing or resisting them ; and he should have such a knowledge of working drawings as will enable him, from the sketches of the architect, to set out the lines for every description of work for centering, framing, &c., that may be entrusted to him for execution.

In measuring carpenter's work, the tenons are included in the length of the timber. This is not the case in joiner's, in which they are allowed for in the price. Carpenter's work is generally measured by the square of 100 feet, and the cubical contents of every square taken out ; and not anything is to be deducted for chimneys, as the extra thickness of the trimmers will make good for the deficiency, and in a quarter partition the braces and extra thickness of the door posts will make good for the opening, but the head and sill must be taken separate ; and if the joists or quarterings in roofs or partitions are 13 inches asunder, one-twentieth of the quantity found is to be taken off—that if placed within 11 inches, one-twentieth must be added. And in measuring the work for labour, only take the extreme verge, including the bearings, one way, and make no deductions for well-holes, chimney-breasts, door-ways, &c. The timber to be collected the full length and size, and charged as cube fir without labour. The following tables should be constantly borne in mind by the young carpenter :—

Lineal or running measure contains 12 inches in 1 foot, 3 feet in 1 yard, 2 yards 1 fathom and 1760 yards or 5280 feet in one mile.

Superficial measure contains 144 square inches in 1 foot, 9 feet in 1 yard, and 100 feet in 1 square of flooring, roofing, partitioning, &c.; 272½ feet in 1 rod or pole, and 160 poles in 4840 yards, or 43560 feet in 1 acre.

Cubical measure comprises the length, breadth, and thickness, and contains 1728 inches in 1 cubic foot, 27 cubic feet in one cubic yard, 282 cubic inches in 1 gallon, and 6 gallons and 1 pint in each cubic foot.

To measure round timber, multiply the mean or quarter girt by itself, and that product by the length by cross multiplication, and the cubical quantity will be ascertained. For instance: suppose a piece of timber to girt 6 feet, one-quarter of this will be 1 foot 6 inches, which, multiplied by 1 foot 6 inches, will give 2 feet 3 inches superficial, which, multiplied by the length (say 20 feet), will give the contents—45 feet cube; and in the same way for any other size.

A TABLE

Of quantities of Timber each making One Load.

50 feet cube of square timber.	600 feet of 1-inch planking.
40 feet ditto of round or rough.	30 12-feet 3-inch deals.
150 feet of 4-inch planking.	26 14-feet ditto ditto.
170 feet of 3½-inch ditto.	18 20-feet ditto ditto.
200 feet of 3-inch ditto.	25 12-feet 3-inch plank.
240 feet of 2½-inch ditto.	21 14-feet ditto ditto.
300 feet of 2-inch ditto.	18 16-feet ditto ditto.
400 feet of 1½-inch ditto.	15 20-feet ditto ditto.

The following quantities of Material will each, on an average, weigh One Ton:—

30 feet cube of oak timber.	48 feet of ash timber.
50 ditto of fir „	35 12-feet 2½-inch deals.
60 ditto of elm „	30 ditto 3-inch ditto.
45 feet of ash „	46 12-feet 2½-inch battens.
60 feet of beech „	33 ditto 3-inch ditto.

The number of Cube Feet in every Square of Flooring, Roofing, or Quarter Partitions of the following different dimensions, the timbers whereof are one foot apart, which should not be more in either.

ROOFS AND QUARTER PARTITIONS.

inches.		cube	ft.	in.	inches.		cube	ft.	in.
2 by 2½	.	.	2	10½	3 by 4½	.	.	6	10
2 „ 3	.	.	3	4	4 „ 2½	.	.	5	8
3 „ 2½	.	.	4	3½	4 „ 4	.	.	8	4
3 „ 3	.	.	5	0	4 „ 4½	.	.	9	1
3 „ 3½	.	.	5	7	4 „ 5	.	.	9	9½
3 „ 4	.	.	6	8					

NAKED FLOOR WITHOUT GIRDER.

inches.		cube	ft.	in.	inches.		cube	ft.	in.
5 by 2½	.	.	7	2½	9 by 2½	.	.	12	11½
5 „ 3	.	.	8	4	9 „ 3	.	.	15	0
6 „ 2½	.	.	8	7½	10 „ 2½	.	.	14	4½
6 „ 3	.	.	10	0	10 „ 3	.	.	16	3
7 „ 2½	.	.	10	4½	11 „ 2½	.	.	15	9½
7 „ 3	.	.	11	8	11 „ 3	.	.	18	4
8 „ 2½	.	.	11	6	12 „ 2½	.	.	17	3
8 „ 3	.	.	13	4	12 „ 3	.	.	20	0

The above tables of different scantlings will be found very useful to those who are unacquainted with taking and squaring and cubing dimensions; as also to such as have to make an estimate in a hurry, as they are the common dimensions of fir scantling for joists, rafters, and quarters for roofs and partitions, of second third, and fourth-rate houses: but we would advise the young carpenter to take the dimensions of the timber required for any stated work, and square and cube them himself.

CHAPTER IV.



MASON.

THE business of the mason consists in working the stones to be used in a building to their shape and setting them in their places. The works connected with the trade of the mason are those of the stone-cutter, who hews and cuts large stones roughly into shape preparatory to their being worked by the mason, and of the carver, who executes the ornamental portions of the stone-work of a building, as enriched cornices, capitals, &c. Where the value of stone is considerable it is sent from the quarry to the building in large blocks, and cut into slabs and scantlings of the required size with a stone-mason's saw, which differs from that used in any other trade in having no teeth. It is a long thin plate of steel, slightly jagged on the bottom edge and fixed in a frame, and, being drawn backwards and forwards in a horizontal position, cuts the stone by its own weight.

To facilitate the operation a heap of sharp sand is placed on an inclined plane over the stone, and water allowed to trickle through it so as to wash the sand into the saw cut. Of late years machinery worked by

steam-power has been used for sawing marble into slabs as well as stone to a very great extent, and has almost entirely superseded manual labour in this part of the manufacturing of chimney-pieces.

Some freestones, as Bath stone, are so soft as to be easily cut with a toothed saw worked backwards and forwards by two persons. The harder kinds of stones, as granites and gritstones, are brought roughly into shape at the quarry, with an axe or scalping hammer, and are then said to be scalped. The tools used by the mason for cutting stone, consist of the *mallet* and *chisel* of various sizes. The mason's mallet differs from that used by any other artisan, being similar to a dome in *contour*, excepting a portion of the broadest part, which is rather cylindrical; the handle is short, being only sufficiently long to enable it to be firmly grasped. In London the tools used to break the faces of the stone are the *point*, which is the smallest description of *chisel*, being never more than a quarter of an inch broad on the cutting edge; the *inch tool*; the *boaster*, which is two inches wide, and the *broad tool*, of which the cutting edge is three and a-half in. wide. The tools used in working mouldings, and in carving, are of various sizes according to the nature of the work. Besides the above cutting tools, the mason uses the banker or bench, in which he places his stone for convenience of working, and straight-edges, squares, levels, and templets, for marking the shapes of the blocks, and for trying the surfaces as the work proceeds. Any angle greater or less than a right angle is called a

bevel angle, and a bevel is formed by nailing two straight-edges together at the required angle; a bevel square is a *square* with a shifting back, which can be set to any required bevels. A templet is called a mould, moulds are commonly made of sheet zinc carefully cut to the profile of the mouldings with shears and files. For setting his work in place the mason uses the trowel, lines, and pins, the square and level, and plumb, and battering rules for adjusting the faces of upright and battering walls.

The mason's scaffold is double, that is, formed with two rows of standards, so as to be totally independent of the walls for support, as putlog holes are inadmissible in masonry.

During the last fifteen years the construction of scaffolds with round poles lashed together with cords, has been superseded in large works by a system of scaffolding of square timbers connected together by bolts and dog-irons. The hoisting of the materials is performed from these scaffolds by means of a travelling crane, which consists of a double travelling carriage running on a tramway formed on straight sills laid on the top of two parallel rows of standards. The crab winch is placed on the upper carriage, and by means of the double motion of the two carriages can be brought with great ease and precision over any part of the work lying between the two rows of standards.

The facilities which are afforded by these scaffolds and travelling cranes for moving heavy weights over large areas, have led to their extensive adoption, not

only in the erection of buildings, but on landing wharfs, masons' and iron-founders' yards, and similar situations, where a great saving of time and labour is effected by their use. Scaffolding of square timbers appears to have been little used in England before A.D. 1837, when Messrs. Cubitt, of Gray's Inn Road, applied it to the erection of the entrance gateway of the Euston station of the North Western Railway. Since then it has been very generally used in large works, amongst which may be mentioned the Reform Club House, and the Nelson Column,—where it was carried up in perfect safety to the height of 180 feet; and it has been used on a very large scale at the new Houses of Parliament, now in progress of being finished.

The moveable derrick crane is also much used in setting mason's work. It consists of a vertical post supported by two timber back-stays, and a long moveable jib or derrick hinged against the post below the gearing. By means of a chain passing from a barrel over a pulley at the top of the post, the derrick can be hoisted to an almost vertical, or lowered to near a horizontal position, thus enabling it to command every part of the area of a circle of a radius nearly equal to the length of the derrick. This gives it a great advantage over the old gibbet-crane, which only commands a circle of a fixed radius, and the use of which entails great loss of time from its constantly requiring to be shifted as the work proceeds.

Derrick cranes appear to have been first introduced at Glasgow, in 1831, by Mr. York, since which time

their original construction has been greatly improved upon, and they are now very extensively used.

In hoisting blocks of stone they are attached to the tackle by means of a simple contrivance called a *lewis*, which consists of a tapering hole being cut in the upper surface of the stone to be raised, the two side pieces of the lewis are inserted and placed against the sides of the holes (*which being made in the form of a dovetail, and the aperture in the stone made to correspond*), a centre parallel piece is then dropped in and secured in its place by a strong pin passing through all three pieces, and the stone may then be safely hoisted, as it is impossible for the lewis to draw out of the holes. By means of the lewis, in a slightly altered form to this described, stone can be lowered and set under water without difficulty, the lewis being disengaged by means of a line attached to the parallel piece, the removal of which allows the other to be drawn out of the mortice.

In stone-cutting the workman forms as many plane faces as may be necessary for bringing the stone into the required shape with the least waste of material and labour, and on the plane surface, so formed, applies the moulds to which the stone is to be worked.

To form a plane surface the mason first knocks off the superfluous stone along one edge of the block until it coincides with a straight-edge throughout its whole length—this is called a *chisel draught*. Another chisel draught is then made along one of the adjacent edges, and the ends of the two are connected by another draught, a fourth draught is then sunk across the last,

which gives another angle point in the same plane with the other draughts, and the stone is then knocked off between the outside draughts until a straight-edge coincides with its surface in every part.

To form cylindrical or moulded surfaces, curved in one direction only, the workman sinks two parallel draughts at the opposite ends of the stone, to be worked until they coincide with a mould cut to the required shape, and afterwards work off the stone between these draughts by a straight-edge applied at right angles to them.

The formation of conical or spherical surfaces is much less simple, and requires a knowledge of the scientific operations of stone-cutting, a description of which would be unsuited to the elementary character of these pages. The reader who wishes to pursue the subject, is therefore referred to the volume of this series on masonry and stone-cutting, where he will find the required information.

The finely grained stones are usually brought to a smooth surface, and rubbed with sand to produce a perfectly even surface.

In working soft stones the surface is brought to a smooth face with a drag, which is a plate of steel indented on the edge like the teeth of a saw, to take off the marks of the tools employed in shaping it. The harder and more coarsely grained stones are generally tooled, that is, the marks of the chisel are left on their face. If the furrows left by the chisel are dispersed in regular order, the work is said to be *fair-tooled*; but if

otherwise, it may be *random tooled*, or chiselled, or boasted, or *pointed*. If the stones project beyond the points, the work is said to be *rusticated* or reticulated.

Granite and gritstone are chiefly worked with the scalping hammer. In massive erections, where the stones are large and effect is required, the fronts of the blocks are left quite rough, as they come out of the quarry, and the work is then said to be quarry pitched.

Many technical terms are used by quarry-men, and others engaged in working stone; but they need not be inserted here, as they are mostly confined to particular localities, beyond which they are little known, or perhaps bear a different signification. When the mason requires to give the joints of his work greater security than is afforded by the weight of the stone and the adhesion of the mortar, he makes use of joggles, dowels, and cramps. Stones are said to be joggled when a projection is worked out on one stone to fit in a corresponding hole or grove in the other; but this occasions great labour and waste of stone. Dowels are chiefly made use of, which are hard pieces of stone cut to the required size, and let into corresponding mortices in the two stones to be joined together.

Dowels may be pins of wood, metal, or stone, used to secure the joints of stone-work in exposed situations, as copings, pinnacles, &c. The best material is copper; but the expense of this metal causes it seldom to be used. If iron be made use of it should be thoroughly tarred, to prevent oxidation, or it will sooner or later burst or

split the work it is intended to protect. Dowels are often secured in their places with lead poured in from above, through a small channel cut in the side of the joint for that purpose; but a good workman will eschew lead, which too often finds its way into bad work, and will prefer trusting to very close and workmanlike joints, carefully-fitted dowels, and fine mortar: dowels should be made tapering at one end, which ensures a better fit, and renders the setting of the stone more easy for the workman.

Iron cramps are used as fastenings on the tops of copings, and in similar situations; but they are not to be recommended, as they are very unsightly, and if they once become exposed to the action of the atmosphere, are powerfully destructive agents; cast-iron is, however, less objectionable than wrought for this purpose.

In measuring mason's work, the cubic contents of the stone is taken as it comes to the banker, without deduction for subsequent waste. If the scantlings are large, an extra price is allowed for hoisting. The labour in working the stone is charged by the superficial foot, according to the kind of work, as *plain work*, *sunk work*, moulded work, &c. Pavings, landings, &c., and all stones less than three inches, are charged by the superficial foot. Copings, curbs, window-sills, &c., are charged per lineal foot. Cramps, dowels, mortice holes, &c., are always charged separately.

A journey-man mason will receive from 4*s.* to 5*s.* 6*d.* per day, and the labourer from 2*s.* 6*d.* to 3*s.* per day;

but masons working piece-work, or at any work requiring particular skill, will often earn much more. The remuneration of a stone carver is dependent on his talent, and the kind of work he is engaged upon.

The following table of the weights of the different kinds of stone, will convey an idea of their relative hardness, and of the labour required to work them :—

TABLE

Of the Weights of different kinds of Stone.

13	cubic feet of marble	weigh one ton.
13½	„ of granite	„ „
14	„ of Purbeck stone	„ „
14½	„ of Yorkshire stone	„ „
16	„ of Derbyshire grit	„ „
17	„ of Portland stone	„ „
18	„ of Bath ditto	„ „
58	feet superficial of 3-inch York paving	„ „
70	„ of 2½-inch „	„ „

PLUMBER.

The work of the plumber chiefly consists in laying sheet lead on roofs, lining cisterns, laying on water to the different parts of a building, and fixing up pumps and water-closets. The plumber uses but few tools, and those are of a simple character, the greater number of them being similar to those used by other artificers, *hammers, mallets, planes, chisels, gouges, files, &c.* The principal tool peculiar to the trade of the plumber is the bat, which is made of beech, about eighteen inches long, and is used for dressing and flattening sheet lead; for soldering also, the plumber uses iron ladles of various sizes for melting solder, as well as lead and grozing

irons for smoothing down the joints. The sheet-lead used by the plumber is either *cast* or milled, the former being generally cast by the plumber himself out of old lead taken in exchange, whilst the latter, which is cast lead, flattened out between two rollers in a flattening mill, is purchased from the manufacturer. Sheet-lead is described, according to the weight per superficial foot, as 5lb. lead, 6lb. lead, &c.

Lead-pipes, if of large dimensions, are made of sheet-lead dressed round a wooden core and soldered up.

Smaller pipes are cast in short lengths, of a thickness three or four times that of the intended pipe, and either drawn or rolled out to the proper thickness.

Soft-solder is used for uniting the joints of lead-work; it is made of equal parts of lead and tin, and is purchased of the manufacturer, by the plumber, at a price per lb., according to the state of the market.

Laying of Sheet-lead.

In order to secure lead-work from the injurious effect of contraction and expansion where exposed to the heat of the sun, the plumber is careful not to confine the metal by soldered joints, or otherwise. All sheet-lead should be laid with a sufficient current to keep it dry; a fall of one inch in ten feet is sufficient for this purpose, if the boarding on which the lead is laid be perfectly even. Joints in the length of the current are made by dressing the edges of the lead over a wooden roll, and joints in the length are made with drips.

Flashings are pieces of lead turned down over the edges of other lead-work, which is turned up against a wall, and serve to keep the wet from finding its way between the wall and the lead. The most secure way of fixing them is to build them into the joints of the brick-work, but the common method is to insert them about an inch into the mortar joint, and to secure them with wall hooks and cement.

A very important part of the business of the plumber, consists in fitting up cisterns, pumps, and water-closet apparatus, and in laying the different services and wastes connected with the same.

Plumber's work is paid for by the cwt. weight, milled-lead being rather more expensive. Mere cast-lead pipes are charged per foot, lined according to size.

Pumps and water-closet apparatus are charged at so much each, according to description, as also basins, air-traps, washers and plugs, spindle, valves, stop-cocks, ball-cocks, &c.

TABLE

Of the Weight of Lead Pipes per Yard.

Bore.		lbs.	ozs.	Bore.		lbs.	ozs.
$\frac{1}{2}$ -inch	. . .	3	3	$1\frac{1}{2}$ -inch	. . .	11	0
$\frac{3}{4}$ -inch	. . .	5	7	$1\frac{1}{2}$ -inch	. . .	14	0
1-inch	. . .	8	0	2-inch	. . .	21	0

The wages of a journeyman plumber are from 5*s.* to 6*s.* per day, and the plumber's labourer receives from 3*s.* to 3*s.* 6*d.* per day.

ZINC WORKER.

The use of sheet-lead has been to a certain extent

superseded by the use of sheet-zinc, which, from its cheapness and lightness, is very extensively used for almost all purposes to which sheet-lead is applied. It is, however, a very inferior material, and not to be depended on. The laying of it is generally executed by the plumber, but the working of zinc, and manufacturing of it into gutters, rain water-pipes, chimney-cowls, and other articles, is practised as a distinct business.

SMITH AND IRON-FOUNDER.

The smith furnishes the various articles of wrought-iron work used in a building, as pileshoes, straps, screw-balls, dog-irons, chimney-bars, gratings, wrought-iron railways, and iron ballustrades for staircases. Wrought-iron was formerly much used for many purposes, for which cast-iron is almost exclusively employed; the improvements effected in casting during the present century having made a great alteration in this respect. The operations of the iron-founder have been much improved since the middle of the last century, when the smelting of iron was carried on with wood charcoal, and the ores used were chiefly from the secondary strata, although the clay iron-stones of the coal-measures were occasionally used. The weald of Kent and Sussex contained many iron-works during the seventeenth century, that at Lamberhurst, near Tunbridge Wells, Sussex, is noted as having furnished the cast-iron railway round St. Paul's Cathedral. The tilt hammers used in forging bar-iron were chiefly worked by water power.

A large pool in Beeding Forest, near Horsham, Sussex, still retains the name of the hammer pond, and the former sites of many old forges in the Wealden district, may still be traced by the heaps of cinders which yet remain here and there, and by the local name to which the works gave rise.

The introduction of smelting with pit-coal coke during the last century, caused a complete revolution in the iron trade. The ores now chiefly used are the clay-iron stones of the coal measures, and the fuel pit-coal or coke.

Steam power is almost exclusively used for the production of the blast-furnaces and for working the forge hammers and rolling mills. For the production of wrought-iron in the ordinary manner, two distinct sets of processes are required: 1st, the extraction of the metal from the ore in the shape of cast-iron; 2nd, the conversion of cast-iron into malleable or bar-iron by remelting, puddling, and forging. The conversion of bar-iron into sheet is effected by placing it in contact with powdered charcoal in a furnace of concentration.

Cast-iron is produced by smelting the previously calcined ore in a blast furnace by its greater specific gravity. The lime-stone and other impurities float on the top of the melted mass, and are allowed to run off, forming slag or cinder. The melted metal is run off from the bottom of the furnace into moulds where castings are required, and into furrows made in a level bed of sand, where the metal is required for conversion into malleable iron; the bars thus produced being called pigs.

In the year 1827, it was discovered that by the use of heated air for the blasts a great saving of fuel could be effected as compared with the cold heat process. The hot blast is now very extensively used, and has the double advantage of requiring less fuel to bring down an equal quantity of metal, and of enabling the manufacturer to use raw pit-coal instead of coke; so that a saving is effected both in the quantity and cost of the fuel.

For a considerable time after its introduction it was held in great disrepute; which, however, may be chiefly attributed to the inferior quality of metals used, the power of the hot blast in reducing the most refractory ores offering a great temptation to obtain a much larger product from the furnaces than was compatible with the good quality of the metal.

The use of the hot blast by firms of acknowledged character has greatly tended to remove the prejudice against it, and in many iron-works of high character nothing but the hot blast with pit coal is used in the smelting furnaces, the use of coke being confined to the subsequent processes.

Perhaps it may be laid down as a general principle, that where the pig-iron is remelted with coke in the cupola furnace for the purposes of the iron founder, or refined with coke in the conversion of forge-pig into bar-iron, it is of little consequence whether the reduction of the ore has been effected with the hot or cold blast; but where castings have to be run directly from the smelting furnace the quality of the metal will, no doubt, suffer from the use of the former.

Cast-iron is divided by the iron-founder into three qualities: No. 1, or blank cast-iron, is coarse-grained, soft, and not very tenacious. When remelted it passes into No. 2, or grey cast-iron. This is the best quality for castings requiring strength. When repeatedly remelted it becomes excessively hard and brittle and passes into No. 3, or white cast-iron, which is only used for the commonest castings, as sash weights, cannon balls, and similar articles.

White cast-iron if produced direct from the ore, is an indication of derangement in the working of the furnace, and is unfit for the ordinary purposes of the founder, except to mix with other qualities.

Girders and similar solid articles are cast in sand moulds enclosed in iron frames or boxes, each mould requiring upper and lower boxes. A mould is formed by pressing sand firmly round a wooden pattern, which is afterwards removed, and the melted metal poured into the spaces thus left through apertures made for that purpose.

The moulds for ornamental work and for hollow castings are of a more complicated construction, which will be better understood from actual inspection at a foundry than from any written description. Almost all irons are improved by admixture with others, and therefore where superior castings are required they should not be run direct from the smelting furnace, but the metal should be remelted in a cupola furnace, which gives the opportunity of suiting the quality of the iron to its intended use. Thus for delicate ornamental work

a soft and very fluid iron will be required, whilst for girders and castings exposed to cross strain the metal will require to be harder and more tenacious. For bed-plates and castings which have merely to sustain a compressing force, the chief point to be attended to is the hardness of the metal.

Castings should be allowed to remain in sand until cool, as the quality of the metal is greatly injured by the rapid and irregular cooling which takes place from exposure to air if removed from the moulds in a red-hot state, which is sometimes done in small foundries to economise room.

Staffordshire, Shropshire, and Derbyshire afford the best iron for castings. The Scotch iron is much esteemed for hollow wares, and has a beautifully smooth surface, which may be noticed in the stoves and other articles cast by the Carron Company. The Welsh iron is principally used for conversion into bar-iron.

The conversion of forge pig into bar iron is effected by a variety of processes, which have for their object the freeing of the metal from the carbon and other impurities combined with it, so as to produce as nearly as possible the pure metal. We do not propose to enter in these pages into any of the details of the manufacture of bar-iron, or of its conversion into steel, as our business is rather with the iron-founder than the manufacturer; it may, however, be proper to state that new processes have lately been patented, by which malleable iron and steel may be produced directly from the ore without the use of the smelting furnace, a plan

which is likely to be attended with beneficial results, both as regards economy and quality of metal.

Besides cast-iron columns, girders, and similar articles which are cast to order, the founder supplies a great variety of articles which are kept in store for immediate use, as cast-iron palings, balconies, rain water-pipes, and guttering, air-traps, coal-plates, stoves, stable-fittings, iron sashes, &c., &c.

Both wrought and cast-iron work are paid for by weight, except small articles kept in store for immediate use, which are valued per piece :—

One cubic foot of cast-iron . . .	weighs about 450 lbs.
Ditto ditto of wrought . . .	„ 475 „
Ditto ditto of closely-hammered .	„ 485 „

The coppersmith provides and buys sheet copper for covering roofs, copper-gutters, and rain water-pipes, washing, brewing coppers, copper cramps, and dowels, for stone-mason's work, and all other copper work in a building; but the cost of the material in which he works prevents its general use, and the washing-copper is frequently the only part of a building which requires the aid of this artificer. Sheet copper is paid for by the superficial foot, copper in dowels, bolts, &c., at per pound.

Warming apparatus, steam and gas-fittings, and similar kinds of work are put up by the mechanical engineer, who also manufactures a great variety of articles which are purchased in parts, and put together and fixed by the plumber, as pumps, taps, water-closet apparatus.

SLATER.

The business of the slater chiefly consists in covering the roofs of houses with slates ; but has of late years been very much extended by the general introduction of sawn slates as a material for shelves, cisterns, baths, chimney-pieces, and even for ornamental purposes.

We propose here to describe only those operations of the slater which have reference to the covering of roofs. Besides the tools which are in common use among other artificers, the slater uses one peculiar to his trade called the *zax*, which is a kind of hatchet with sharp point at the back. It is used for trimming slates and making the holes by which they are nailed in their places.

Slates are laid either on boarding or on narrow battens from two to three inches wide, the latter being the more common method on account of its being less expensive than the other. The nails used should be either copper or zinc ; iron nails, though sometimes used, being objectionable from their liability to rust. Every slate should be fastened with two nails, except in the most inferior work. The upper surface of a slate is called its back, the under surface the bed, the lower edge the tail, the upper edge the head, the part of each course of slate exposed to view is called the margin of the course, and the width of the margin is called the gauge.

The bond or lap is the distance which the lower edge of any course overlaps the slates of the second course below, measuring from the nail-hole.

In preparing slates for use, the sides and bottom-edges are trimmed, and the nail-holes punched as near the head as can be done without risk of breaking the slate, and at a uniform distance from the tail.

The lap having been decided on, the gauge will be equal to half the distance from the tail to the nail-hole, less the lap ; thus a countess slate measuring nineteen inches from tail to nail, if laid with a three inch lap, would show a margin of eight inches. The battens are of course nailed on to the rafters at the gauge to which the slates will work. If the slates are of different lengths, they must be sorted into sizes and gauged accordingly, the smallest size being placed nearest the ridge. The lap should not be less than two inches, and need not exceed three inches.

It is essential to the soundness, as well as the appearance of slater's work, that the slates should all be of the same width, and the edges perfectly true. The Welsh slates are considered the best, and are of a light sky-blue colour ; the Westmoreland slates are of a dull greenish hue.

Slater's work is measured by the square of 100 superficial feet, allowance being made for the trouble of cutting the slates at the hips, eaves, round chimneys, &c.

Slabs for cisterns, baths, shelves, and other sawn work, are charged per foot, superficial, according to the thickness of the slab, and the labour bestowed on the work. Rubbed edges, grooves, &c., are charged per lineal foot.

A journeyman slater receives about 5*s.* per day, and his labourer about 2*s.* per day.

TABLE
Of the Sizes of Roofing Slates.

Description.	Size.		Average Gauge in Inches.	No. of Squares 1200 will cover.	Weight per 1200 in Tons.	No. required to cover one square.	No. of Nails re- quired to one square.
	Length.	Breadth.					
	ft. in.	ft. in.					
Doubles	1 1	0 6	5½	2	3	480	480
Ladies	1 4	0 8	7	4½	1½	280	280
Countesses	1 8	0 10	9	7	2	176	352
Duchesses	2 0	1 0	10½	10	3	127	254
Imperials	2 6	2 0	} A Ton will cover 2½ to 2½ squares.				
Rags and Queens	3 0	2 0					
Westmoreland of various sizes							

Inch slab per foot superficial weighs 14 lbs.

We have now endeavoured to explain the various trades employed, and the materials required for the carcass of a building, and will commence with the finishing.

Finishings.

The work of the plasterer consists in covering the brickwork and naked timbers of walls, ceilings, and partitions with plaster, to prepare them for painting, papering, or distempering, and in forming cornices, and such decorative portions of the furnishings of buildings as may be required to be executed in plaster or cement.

The plasterer uses a variety of tools, of which the following are the principal ones :—

The *drag* is a three-pronged rake, used to mix the hair with the mortar in preparing coarse stuff.

The *hawk* is a small square board for holding stuff on, with a short handle on the under side.

Trowels are of two kinds, the *laying and smoothing tool*, with which the first and the last are laid, and the *gauging trowel* used for gauging fine stuff for cornices, &c., &c.: these are made of various sizes, from three to seven inches long.

Of *floats*, which are used in floating ceilings and other work. There are three kinds, viz., the *Derby*, which is a rule of such a length as to require two men to use it. The *hand-float*, which is used in furnishing stucco, and the *quirk-float*, which is used in floating angles.

Moulds, for raising cornices, are made of sheet copper cut to the profile of the moulding, to be formed and fixed in a wooden frame.

Stopping and picking out tools are made of steel, seven or eight inches long, and of various sizes. They are used for modelling, and for finishing mitres, and returns to cornice.

Materials.

Coarse stuff, or lime and hair, as it is usually called, is similar to common mortar, with the addition of hair from the tanner's yard, which is thoroughly mixed with the mortar by means of the drag.

Fine stuff is made of pure lime, slaked with a small quantity of water; after which sufficient water is added to bring it to the consistence of cream. It is then allowed to settle, and the superfluous water being poured off, it is left in a bin or tub to remain in a semi-fluid state, until the evaporation of the water has brought it to a proper thickness for use. In using fine stuff for setting ceilings, a small portion of white hair is mixed with it.

Stucco is made with fine stuff and clean washed river sand. This is used for finishing work intended to be painted.

Gauged stuff is formed of fine stuff mixed with plaster of paris, the proportion of plaster varying according to the rapidity with which the work is required to set.

Gauged stuff is used for running cornices and mouldings.

Enrichments, such as pateras, centre flowers for ceilings, &c., are first modelled in clay, and afterwards cast of plaster of paris in wax or plaster moulds.

Papier maché ornaments also are much used, and have the advantage of being very light, and being easily and securely fixed with screws.

The variety of composition and cements made use of by the plasterer is very great. *Roman cement*, *Portland cement*, and *lias cement*, are the principal ones used for coating buildings externally. Martin and Keene's cements are well adapted for all internal plastering where sharpness, hardness, and delicate finish are required.

Operations for Plastering.

When brickwork is plastered, the first coat is called rendering.

In plastering ceilings and partitions, the first operation is *lathing*. This is done with *single, one-and-a-half*, or *double* laths, these names denoting their respective thicknesses. Laths are either of oak or fir; if of the former, wrought-iron nails are used, but cast-iron nails may be employed with the latter. The thickest laths are used for ceilings, as the strain on the laths is greater in a horizontal than in an upright position.

Pricking-up is the first coat of plastering of coarse stuff upon laths; when completed, it is well scratched over with the end of a lath, to form a key for the next coat.

Laid work consists of a simple coat of coarse stuff over a wall or ceiling.

Two-coat work is only roughed over with a broom, and afterwards set with fine stuff, or with gauged stuff in the better description of work.

The laying on of the second coat of plastering is called floating, from its being floated or brought to a plain surface with the float.

The operation of floating is performed by surrounding the surface to be floated with narrow strips of plastering, called screeds, brought perfectly upright, or level, as the case may be, with the level or plumb rule; thus, in preparing for floating a ceiling, nails are driven in at the angles, and along the sides, about ten feet apart,

and carefully adjusted to a horizontal plane, by means of the level. Other nails are then adjusted opposite to the first, at a distance of seven or eight inches from them. The space between each pair of nails is filled up with coarse stuff, and floated perfectly true with a floating rule; this operation forms a screed, perfectly level throughout. Other screeds are then formed, to divide the work into bays about eight feet wide, which are successively filled up flush, and floated level with the screeds.

The screeds for floating walls are formed in exactly the same manner, except that they are adjusted with the plumb rule instead of the level. After the work has been brought to an even surface with the floating rule, it is gone over with the hand-float and a little soft stuff, to make good any deficiencies that may appear. The operation of forming screeds and floating work, which is not either vertical or horizontal, as a plaster floor laid with a fall, is analogous to that of taking the face of a stone out of winding, with chisel, drafts, and straight edges in stone-cutting, the principle being in each case to find three points in the same plane, from which to extend operations over the whole surface.

Setting.

When the floating is about half dry, the setting or finishing coat of fine stuff is laid on with the smoothing trowel, which is alternately wetted with a brush, and worked over with the smoothing tools, until a fine surface is obtained.

Stucco is laid on with the largest trowel and worked over with the hand-float, the work being alternately sprinkled with water and floated until it becomes hard and compact, after which it is finished by rubbing it over with a dry stock brush. The water has the effect of hardening the face of the stucco, so that after repeated sprinklings and trowelling, it becomes very hard, and smooth as glass.

The above remarks may be briefly summed up as follows. The commonest kind of work consists of only one coat, and is called rendering, on brickwork, and laying, if on laths. If a second coat be added, it becomes two-coat work, as *render set*, or lath lay and set. Where the work is floated it becomes three-coat work, and is *render float* and set for ceilings and partitions, ceilings being set with fine with a little white hair, and walls intended for paper with fine stuff and sand : stucco is used where the work is to be painted.

Rough stucco is a mode of finishing staircases, passages, &c., in imitation of stone. It is mixed with a large proportion of sand, to give the appearance of stone.

Rough-cast is a mode of finishing outside work, by dashing over the second coat of plastering, whilst quite wet, a layer of rough cast, composed of well-washed gravel mixed up with pure lime and water till the whole is in a semi-fluid state.

Pugging is lining the spaces between floor joists with coarse stuff, to prevent the passage of sound, or between two stones, and is done on laths or rough boarding.

In the midland districts of England reeds are much used instead of laths, not only for ceilings and partitions, but for floors, which are formed with a thick layer of coarse gauged stuff upon reeds. Floors of this kind are extensively used about Nottingham, and, from security against fire afforded by the absence of wooden floors, Nottingham homes are proverbially fire-proof.

Plasterer's work is measured by the superficial yard cornices by the superficial foot, enrichments to cornices by the lineal foot, and centre flowers and other decorations at per piece.

Memoranda.

The wages of a journeyman plasterer are from 4*s.* 6*d.* to 5*s.* 6*d.* per day; those engaged on modelling and ornamental work will earn much more. A labourer receives from 2*s.* 6*d.* to 3*s.* per day; and a plasterer's boy about 1*s.*

Lathing.—One bundle of laths and 384 nails will cover 5 yards superficial measure.

Rendering.—187½ yards require 1½ hundred of lime, 2 double loads of sand, and 5 bushels of hair.

Floating requires more labour, but only half as much material as rendering.

Setting.—375 superficial yards require 1½ hundred of lime and 5 bushels of hair.

Render Set.—100 yards superficial require 1½ cwt. of lime, 1 double load of sand, and 4 bushels of hair. *Plasterer, labourer, and boy*, 3 days each.

Lath Lay and Set.—130 yards superficial of lath lay and set require 1 load of laths, 10,000 nails, $2\frac{1}{2}$ cwt. of lime, $1\frac{1}{2}$ double load of sand, and 7 bushels of hair. Plasterer, labourer, and boy, 6 days each.

Twenty per cent. profit is allowed upon all materials.

JOINER.

The work of the joiner consists in framing and joining together the wooden finishings and decorations of buildings, both internal and external; such as floors, staircases, framed partitions, skirtings, solid door and window frames, hollow or cased window frames, sashes and shutters, doors, columns and entablatures, chimney-pieces, &c.

The *joiner's* work requires much greater accuracy and finish than that of the carpenter, and differs materially from it in being brought to a 'smooth surface with the plane wherever exposed to view, whilst with the carpenter's work the timber is left rough as it comes from the saw.

The *joiner* uses a great variety of tools: the principal cutting tools are saws, planes, and chisels.

Of saws there are a great variety, distinguished from each by their shape and by the size of their teeth. The *ripper* has 8 teeth in 3 inches; the *half ripper* 3 teeth to the inch; the *hand-saw*, 15 teeth in 4 inches; the *panel-saw*, 6 teeth to the inch. The *tenon-saw*, used for cutting tenons, has about 8 teeth to the inch, and is strengthened at the back by a thick piece of iron to keep the blade from buckling. The *sash-saw* is similar

to the tenon-saw, but is backed with brass instead of iron, and has 13 teeth to the inch; the *dovetail-saw* is still smaller, and has 15 teeth to the inch. Besides the above named, other saws are used for particular purposes—as the *compass-saw* for cutting circular work, and the *keyhole-saw* for cutting small holes. The *car-case-saw* is a large kind of *dovetail-saw*, having about 11 teeth to an inch.

Planes are also of many kinds: those called bench planes—as the *jack-plane*, the *trying-plane*, the *long plane*, the *jointer*, and the *smoothing-plane*—are used for bringing the stuff to a plane surface. The jack-plane is about 18 inches long, and is used for the roughest work. The trying-plane is about 22 inches long, and used after the jack-plane for *trying-up*—that is, taking off shavings the whole length of the stuff. Whilst using the *jack-plane*, the workman stops at every arm's length. The *long plane* is about 2 feet 3 inches long, and used when a piece of stuff is to be tried-up very straight. The *jointer* is about 2 feet 6 inches long, and is used for trying-up or *shooting* the *joints*, in the same way as the *trying-plane* is used for trying up the face of the stuff. The *smoothing-plane* is small, being only about $7\frac{1}{2}$ inches long, and is used on almost all occasions for cleaning or smoothing-off finished work. *Rebate-planes* are used for sinking rebates, and vary in their size and shape according to their respective uses. *Rebate-planes* differ from *bench-planes* in having no handle rising out of the stock, and in discharging their shavings at the side. Amongst the

rebate-planes may be mentioned the *moving fillister* and the *sash fillister*, the uses of which will be better understood from inspection than description. *Moulding-planes* are used for *sticking mouldings*, as the operation of forming mouldings with the plane is called. When mouldings are worked with chisels instead of with planes, they are said to be worked by *hand*. Of the class of moulding-planes, although kept separate in the tool chest, are hollow and rounds, beads, &c., of various sizes.

There are other kinds of planes besides the above-named, as the *plough*, for sinking a groove to receive a projecting tongue; the *bead*, for sticking beads; the *snipe's-bill*, for forming and cleaning out quirks; the *com-plass-plane* and the *forkstaff-plane*, for forming concave and convex cylindrical surfaces. The shape and use of these and many other tools used by the joiner will be better understood by inspection than description.

Chisels are also varied in their form and use: some are used merely with the pressure of the hand, as the *paring chisel*; others by the aid of a mallet, as the *socket chisel* (so named from the iron at the top forming a socket to receive an iron handle), for cutting away superfluous stuff; and the *mortice chisel*, for cutting mortices: the gouges are curved chisels.

The joiners use a great variety of boring tools, as the *brad-awl*, *gimlet*, and *stock and bit*. The last form but one tool, the *stock* being the *handle*, to the hollow of which may be fitted a variety of steel bits of different bores and shapes, for boring and widening out holes in

wood and metal, as countersinks, rimers, and taper shell-bits.

The *screw-driver*, *pincers*, *hammer*, *mallet*, *hatchet*, and *adze* are too well known to require description.

The *gauge* is used for drawing lines on a piece of stuff parallel to its edges.

The *bench* is one of the most important of the joiner's implements. It is furnished with a vertical *sideboard*, perforated with diagonal ranges of holes, which receive the *bench-pin*, on which to rest the lower end of a piece of stuff to be planed, whilst the upper end is firmly clamped by the bench-screw.

The *mitre-box* is used for cutting a piece of stuff to a mitre, or an angle of forty-five degrees, with one of its sides.

The joiner uses for setting out and fixing his work, the straight edge, the square, the level or square with a shifting blade, the mitre square, the level, and plumb rule.

In addition to the tools and implements above enumerated, the execution of particular kinds of work requires other articles, as cylinders, templets, cramps, &c., the description of which would unnecessarily extend the limits of our present object.

The principal operations of the joiner are sawing, planing, dovetailing, morticing, and scribing.

The manner of forming a dovetail is by projecting a part, called the tenon, gradually tapering from the outer edge to the inner, and a corresponding hole made to receive it, which is called a socket.

Morticing is executed by forming a hole in a piece of timber to receive the end of another piece, called the tenon. The tenon is sometimes *pinned* in its place with oak pins driven through the cheeks of the mortice. But in forming doors, shutters, &c., the tenon is secured with tapering wedges driven into the mortice, which is cut slightly wider at the top than the bottom, the adhesion of the glue with which the tenon and wedges are first rubbed over, making it impossible for the tenon afterwards to draw out of its place.

Joints in the length of the stuff may be either *square*, *rebated*, or *grooved and tongued*, which is executed by a groove made with a plough and iron on each edge of the two pieces of stuff, and then a slip of wood, which is called the tongue, being inserted before the joint is glued up.

Scribing is the drawing on of a piece of stuff the exact profile of some irregular surface to which it is to be made to fit; this is done with a pair of compasses, one leg of which is made to traverse the irregular surface, the other to *describe* a line *parallel* thereto along the edge of the stuff to be cut.

In the execution of *circular work*, or as it is frequently termed *sweep work*, there are four different methods by which the stuff can be brought to the required curve:—

Firstly. It may be stamped and bent into shape.

Secondly. It may be glued up in thicknesses which must, when thoroughly dry, be planed true, and, if not to be painted, covered with a thin veneer, bent round.

Thirdly. It may be formed in thin thicknesses bent round and glued up on a mould. This may be considered the most perfect of all the methods in use.

Lastly. It may be formed by sawing a number of notches on one side, by which means it becomes easily bent in that direction, but the curve produced by this means is very irregular, and it is an inferior mode of execution compared to others.

When a number of boards are secured together by cross pieces or ledges nailed or screwed at the back, the work is said to be *ledged*; *ledged work* is for common purposes, as cellar-doors, outside shutters, &c.

Framed work consists of *styles* and *rails* morticed and tenoned together, and filled in with panels, the edges of which fit in grooves cut for the purpose in the *styles* and *rails*.

Work is said to be *clamped* when it is prevented from warping or splitting by a rail at each end. If the ends of the rail are cut off it is said to be *mitre-clamped*.

There are several ways of laying floors practised by joiners. In laying what is called a *straight-joint floor*, from the joints between the boards running in an unbroken line from wall to wall, each board is laid down and nailed in succession, being first forced firmly against the one last laid with a flooring cramp.

Folding floors are laid by nailing down first every fifth board, rather closer together than the united widths of four boards, and forcing the intermediate ones into the space left for them by jumping on them.

This method of laying floors is resorted to when the stuff is imperfectly seasoned and is expected to shrink, but it should never be executed in good work.

The narrower the stuff with which a floor is laid the less will the joints open, on account of the shrinkage being distributed over a greater number of joints.

The floor boards may be nailed at their edges, and grooved and tongued or dowed, if it is desired to make a very perfect floor. Dowelling is superior to grooving and tonguing, because the cutting away the stuff to receive the tongue, greatly weakens the edges of the joint, which are apt to curl.

Glue is an article of great importance to the joiner, the strength of his work depending much upon its adhesive properties.

The best glue is made from the skin of animals, that from the sinewy or horny parts being of inferior quality. The strength of the glue increases with the age of the animals from which the skins are taken.

Joiner's work is measured by the superficial foot, according to its description. Floors by the square of 100 feet superficial. Hand-rails, small mouldings, water-trunks, and similar articles, per lineal foot. Cantilevers, trusses, cut-brackets, scrolls to handrails, &c., are valued per piece.

The wages of a joiner are from 5s. to 6s. per day.

The following memoranda relative to joiner's work may be found useful :—

One Square of Flooring will take—

24	10-foot boards at	. .	5-inch gauge.
20	„ „ at	. .	6-inch ditto.
17	„ „ at	. .	7-inch ditto—10 in. wanted.
15	„ „ at	. .	8-inch ditto.
13	„ „ at	. .	9-inch ditto—2 ft. 6 in. wanted.
12	„ „ at	. .	10-inch ditto.
20	12-foot boards at	. .	5-inch gauge.
14	„ „ at	. .	6-inch ditto—4 ft. wanted.
12	„ „ at	. .	7-inch ditto—2 ft. wanted.
12	„ „ at	. .	8-inch ditto—4 ft. wanted.
12	„ „ at	. .	9-inch ditto—1 ft. wanted.
10	„ „ at	. .	10-inch ditto.

N.B. One square of flooring will take 200 nails. To make them tough they should be heated in a fire-shovel or the like, with a bit of tallow or grease in them,

120 twelve feet deals make one hundred; and the readiest way of calculating the price of a single one, is to consider every pound per hundred as two-pence per deal: thus if deals are 40*l.* per hundred, they are 40 times two-pence each, or 80 pence, which is 6*s.* 8*d.* for each deal; or if 36*l.* 10*s.* per hundred they would be 36½ times two-pence each, double of which, for pence, would be 73, or 6*s.* 1*d.* each deal, and in the same way for any other given price.

TABLE

Of the Relative Weight of Timber.

24	cubic feet of mahogany	. .	weigh 1 ton.
39	„ of oak	. .	„ „
45	„ of ash	. .	„ „
60	„ of elm	. .	„ „
65	„ of fir	. .	„ „
50	„ of fir timber	. .	„ 1 load.

120 12-feet 3-inch deals . . equal $5\frac{1}{2}$ loads of timber.

400 superficial feet $1\frac{1}{2}$ -inch deals weigh 1 load.

Planks are reckoned to 11 inches wide.

Deals " " 9 "

Battens " " 7 "

A reduced deal is $1\frac{1}{2}$ in. thick, 11 in. wide, and 12 feet long.

A square of flooring laid rough requires $12\frac{1}{4}$ floor-board. Ditto, edges shot, $12\frac{1}{2}$. Ditto wrought and laid folding, 13. Laid straight joint, $13\frac{1}{2}$.

Wrought and laid straight joint, and ploughed and tongued, 14. If laid with 12 feet battens, wrought and laid folding, 17, and with straight joint, 18.

Sawing.

The *sawer* is to the carpenter and joiner what the stone-cutter is to the mason.

The pit saw is a large two-handed saw fixed in a frame, and moved up and down in a vertical direction by two men called the top-man and the pit-man, the first of whom stands on the timber that is to be cut, the other at the bottom of the saw-pit. The timber is *lined out* with a chalk line on its upper surface, and the accuracy of the work depends mainly on the top-man keeping the saw to the line, whence the proverbial expression *top-sawyer*, meaning one who directs any undertaking.

In sawing of deals and battens into thicknesses for the joiner's use, the parallelism of the cut is of the utmost importance, as the operation of *taking out of*

winding a piece of uneven stuff, causes a considerable waste of material, and much loss of time.

Circular-saws, moved by steam-power, are now much used in large establishments, timber-yards, &c., and effect a considerable saving of labour over the use of the pit-saw, where the timbers to be cut are not too heavy to be easily handled.

The saw is mounted in the middle of a stout bench furnished with guides, by means of which the stuff to be cut is kept in the required direction, whilst it is pushed against the saw, which is the whole manual labour required in the operation.

IRONMONGERY

Is charged for, generally, with the work to which it is attached; the joiner being allowed 20 per cent. profit upon the prime cost.

The principal articles of ironmongery used in a building, consist of *nails, screws, sash-pulleys, bolts, hinges, locks, latches*, and *sash and shutter-furniture*, besides a great variety of miscellaneous articles which we have not space to enumerate.

Of the different kinds of hinges may be mentioned *hook-and-eye hinges* for gates, coach-house doors, &c.; *butts* and *back-flaps* for doors and shutters; *cross garnets*, which are used for hanging ledged doors and other inferior work; *H and H hinges*, whose name is derived from their shape; and *parliament hinges*.

Besides these, are used *rising-butts* for hanging doors to rise over a carpet or other impediment, *projecting-*

butts, used when some projection has to be cleared, and *spring-hinges* and swing centres for self-shutting doors.

The variety of locks now manufactured is almost infinite. We may mention the *stock-lock*, cased in wood for common work, and *rim-locks*, which have a metal case or rim, and are attached to one side of a door; they should not be used when a door has sufficient thickness to allow of a mortice-lock, as they often catch the dresses of persons passing through the doorway. *Mortice-locks*; as the name implies, are those which are morticed into the thickness of the door.

The handles and escutcheons are called the *furniture* of a lock, and are made of a great variety of materials, as brass, bronze, ebony, ivory, and glass, &c.

Of latches, there are the common *thumb-latch*, the *bow-latch* with brass knobs, the brass *pulpit-latch*, and the *mortice-latch*.

There are also a great variety of other articles, both useful and ornamental, kept in stock and supplied by the furnishing ironmonger.

GLAZIER.

The business of the glazier consists in cutting glass, and fixing it into *lead-work*, *wood-work*, or wood sashes. The former is the oldest method of glazing, and is still used, not only for cottage windows and inferior work, but for church windows and glazing with stained glass, which is cut into pieces of the required size, and set in a leaden framework; this kind of glazing is called *fretwork*. Glazing in sashes is of

comparatively modern introduction. The sash bars are formed with a rebate on the outside for the reception of the glass, which is *cut into* the rebate, and firmly *beaded* and *back-puttied* to keep it in its place. Large squares are also *sprigged* or secured with small brads driven into the sash bars.

Glazing in *lead-work* is fixed in leaden rows called *comes*, prepared for the use of the glazier by being passed through a glazier's vice, in which they receive the grooves for the insertion of the glass. The sides or cheeks of the grooves are sufficiently soft to allow of their being turned down to admit the glass, and again raised up and firmly pressed against it after its insertion. For common lead-work, the bars are soldered together so as to form squares or diamonds. In fret-work, the bars, instead of being used straight, are bent round to the shapes of the different pieces of glass forming the device. Lead-work is strengthened by being attached to *saddle-bars* of iron, by leaden bars soldered to the lead-work and twisted round the iron.

Putty is made of pounded whiting beaten up with linseed oil into a tough tenacious cement.

The principal tool of the glazier is the *diamond*, which is used for cutting glass. This tool consists of an unpolished diamond fixed in lead, and fastened to a handle of hard wood.

The glazier uses a *hacking-knife* for cutting out old putty from broken squares, and the *stopping-knife* for laying and smoothing the putty when *stopping-in* glass

into sashes. For setting glass into lead-work, the *setting-knife* is used.

Besides the above, the glazier requires a square and straight edge, and a pair of compasses, for dividing the tables of glass to the required sizes. Also, a hammer for springing large squares, and brushes for cleaning off the work.

The *glazier's* vice has already been mentioned. The *luter-kin* is a pointed piece of hard wood, with which grooves of the *comes* are cleared out and widened for receiving the glass.

Cleaning windows is an important branch of the glazier's business in most large towns: the glazier taking upon himself the cost of all glass broken in the operation.

Glazier's work is valued by the superficial foot, the price increasing with the size of the square. Irregular panes are taken of the extreme dimensions each way.

Crown glass is *blown* in circular *tables*, from 3 feet 6 inches to 5 feet diameter, and is sold in *crates*, the number of tables in a crate varying according to the quality of the glass.

A crate contains 12 tables of best quality.

Ditto ditto 15 „ second ditto.

Ditto ditto 18 „ third ditto.

Plate glass is cast in large plates on horizontal tables, and afterwards polished.

The manufacture of sheet or spread glass, which was formerly considered a very inferior article, has of late

years been much improved. Much is now sold, after being polished, under the name of patent plate.

PAINTER, PAPER-HANGER, AND DECORATOR.

The business of the house-painter consists in covering with a preparation of white lead and oil, such portions of the joiner's, smith's, and plasterer's work as require to be protected from the action of the atmosphere. Decorative painting is a higher branch, requiring a knowledge of the harmony of colours, and more or less of artistic skill, according to the nature of the work to be executed.

The introduction of fresco painting into this country, as a mode of internal decoration, has led to the employment of some of the first artists of the day in the embellishment of the mansions of the nobility, and the example thus set will no doubt be extensively followed.

The principal materials used by the painter are—*white lead*, which forms the basis of all the colours used in house-painting; *linseed oil* and *spirits of turpentine*, used for mixing and diluting the colours; and *dryers*, as *litharge*, *sugar of lead*, and white vitriol, which are mixed with the colours to facilitate their drying. *Putty*, made of whiting and linseed oil, is used for *stopping* or filling up nail holes and other vacuities, in order to bring the work to a smooth face.

The painter's tools are few and simple: they consist of the *grinding-stone* and *muller*, for grinding colours; *earthen pots*, to hold colours; *cans* for oil and turps; *pallet knife*, and brushes of various sizes and

descriptions. In painting wood, the first operation consists in killing the *knots*, from which the turpentine would otherwise exude and spoil the work. To effect this, the knots are covered with fresh slaked lime, which dries up and burns out the turpentine; when this has been on twenty-four hours, it is scraped off, and the knots painted over with a mixture of red and white lead mixed with glue size. After this, they are gone over a second time with red and white lead mixed with linseed oil; when dry, they must be rubbed perfectly smooth with pumice stone, and the work is then ready to receive the priming coat.

This is composed of red and white lead, well diluted with linseed oil.

The nail holes and other imperfections are then stopped with putty, and the succeeding coats are then laid on, the work being rubbed down between each coat with pumice stone, to bring it to an even surface. The first after the priming is mixed with linseed oil and a little turpentine. The second coat with equal quantities of linseed oil and turpentine.

In laying on the second coat where the work is not to be finished white, an approach must be made to the required colour. The third coat is usually the last, and is made with a base of white lead, mixed with the requisite colours, and diluted with one-third of linseed oil to two-thirds of turpentine.

Painting on stucco, and all other work in which the surface is required to be without gloss, has an additional coat mixed with turpentine only, which from its

drying of one uniform *flat* tint is called a flatting coat.

If the knots show through a second coat they must be carefully covered with silver leaf.

Work finished as above described would be technically specified as knotted, primed, painted three oils, and flatted.

Flatting is almost indispensable in all delicate interior work, but it is not suited to outside work, as it will not bear exposure to the weather.

Painting on stucco is primed with boiled linseed oil, and then should receive at least three coats of white lead and oil, and be finished in a flat tint.

The great secret of success in painting stucco is, that the surface should be perfectly dry, and as this can hardly be the case in less than two years after the erection of a building, it will always be desirable to finish new work in distemper, which can be washed off whenever the walls are sufficiently dry to receive the permanent decorations.

Graining is the imitation of the grain of various kinds of wood, by means of *graining tools*, and, when well executed and properly varnished, has a handsome appearance, and lasts many years. The term graining is also applied to the imitation of marble.

Clear coling is a substitution of size for oil, in the preparation of the priming coat. It is much resorted to by painters on account of the ease with which a good face can be put on the work with fewer coats than when oil is used, but it will not stand damp,

which causes it to scale off, and it should never be used except in painting old work, which is greasy or smoky, and cannot be made to look well by any other means.

Distempering is a kind of painting in which whiting is used as the basis of the colours, the liquid medium being size ; it is much used for ceilings and walls, and will require two, and sometimes three coats, to give it a uniform appearance.

Painter's work is valued per superficial yard, according to the number of coats, and the description of work, as *common colours*, *fancy colours*, *party colours*, &c.

Where work is cut on both edges, it is taken by the lineal foot. In measuring railings, the two sides are measured as flat work.

Sash panes are valued per piece, and sashes per dozen squares.

The manufacture of scagliola, or imitation marble, is a branch of the decorator's business which is carried to very great perfection.

Scagliola is made of plaster of paris and different earthy colours, which are mixed in a trough in a moist state, and blended together until the required effect is produced, when the composition is taken from the trough, laid on the plaster ground, and well worked together with a wooden beater and a small gauging trowel. When quite hard, it is smoothed, scraped, and polished, until it assumes the appearance of marble.

Scagliola is valued at per foot *superficial*, according to the description of marble imitated and the execution of the work.

Gilding is executed with leaf-gold, which is furnished by the gold-beater in books of twenty-five leaves, each leaf measuring $3\frac{1}{2}$ by 3 inches.

The parts to be gilded are first prepared with a coat of gold-size, which is made of Oxford ochre and fat oil.

The operations of the paper-hanger are so simple as to require little description. There are as great a variety of patterns as there are of prices, and the expense of hanging them is generally regulated by the value of the paper, as the most expensive papers require more time and attention than the plainer sorts.

A piece of paper is twelve yards long, and is twenty inches wide when hung, and covers six feet superficial, hence the number of superficial feet that have to be covered divided by sixty, will give the number of pieces required for any description of work.

CHAPTER V.

GEOMETRY.

HAVING in a cursory manner endeavoured to describe the principal tools and materials used in the erection of dwelling-houses, in which we have alluded to the necessity of the young artisan giving some attention to lineal drawing, we are now desirous of conveying our opinion (*founded upon many years' experience, both theoretically and practically,*) of its utility and importance; and in doing so, we may not probably assume too much, by stating that not any mechanic in the building department, or in fact in any other, can ever be efficient in his business unless he fully comprehends the application of scales and the elementary principles of geometry.

Until late years there was not that attention paid to this art its general application and usefulness demanded, it being considered more an acquisition for the mathematician, artist, or amateur, than the mechanician, but the progress that has been made within the last half century in every branch of mechanical art has caused such praiseworthy and meritorious emulation to excel, and the inability to do so without an elementary knowledge of theoretical information combined with practical experience, not only stimulated the artisans and

students who possessed such laudable ambition to apply themselves for the required information, but also the Government, under whose auspices there is now a number of schools opened, at merely *a nominal expense*, for the instruction of this important auxiliary to the various branchical arts of design and ornamentation.

That geometrical drawing to the young mechanic may at first be considered a dry and useless study is admitted, but he must recollect that no one ever rose to eminence in any of the arts or sciences without perseverance and intense application, and although the study here particularly alluded to may be considered dry and disinteresting at first, it will be rewarded by the pleasure and confidence it gives to its possessor hereafter.

It is a well-known fact that without a knowledge of scales and their application, and an elementary acquaintance with the principles of geometry, no one, however well-informed on other subjects, can convey the emanation of his mind for any practical mechanical purpose. He certainly may be enabled in a cursory manner to sketch out his ideas, but they cannot with any certainty be carried into practical execution, without they are geometrically delineated to a scale. Having thus expressed our views upon the usefulness and application of drawing, we will now endeavour to explain the paper in general use for drawing, and the particular use of such scale and mathematical instruments, as are essential for him to possess in the practice of his profession.

A TABLE OF THE DIMENSIONS OF DRAWING-PAPER.*

	Inches.	Inches.
Demy	20	by 15½
Medium	22½	„ 17½
Royal	24	„ 19½
Super Royal	27½	„ 19½
Imperial	30	„ 22
Elephant	28	„ 23
Columbier	35	„ 23½
Atlas	34	„ 26
Double Elephant	40	„ 27
Antiquarian	53	„ 31
Emperor	68	„ 48

HINTS ON THE MANAGEMENT OF DRAWING PAPER.

The first thing to be done preparatory to the commencement of a drawing is the preparation of the paper, that is, the stretching it evenly upon a drawing-board, the edges of the paper should first be cut straight, and as near as possible at right angles with each other. Also the sheet should be so much larger than the intended drawing and its margin, as to admit of being afterwards cut from the board, leaving the border by which it is attached thereto, by glue or paste, as we shall next explain. The paper must be thoroughly and equally damped with a sponge and clean water on the opposite side from that on which the drawing is to be made. When the paper absorbs the water, which may be seen by the wetted side becoming dried, as its surface is viewed slant-ways against the light, it is to be laid on the drawing-board with the wetted side downwards

* It is assumed that the student is fully acquainted with the use of the drawing-boards, T squares, set squares, and parallel rulers.

and placed so that the edges may be nearly parallel with those of the board, otherwise in using a T square an inconvenience may be experienced. This done, lay a straight-edge on the paper with edge parallel to and about half an inch from one of its edges. The straight-edge or ruler must now be held firm while the said projecting half-inch of paper is turned up along its edges, then a piece of glue, having it partially dissolved by holding it over boiling water for a few seconds, must be passed once or twice along the turned up edge of the paper, after which, by sliding the ruler over the glued border, it will again be laid flat, and the ruler or straight-edge being pressed down upon it that edge of the paper will adhere to the board. If sufficient glue has been applied the ruler may be removed directly, and the edge finally rubbed down by an ivory book-knife, or any clean polished substance at hand, which will then firmly cement the paper to the board. This done, another but adjoining edge of the paper must be acted upon in a like manner, and then the remaining edges in succession: we say the adjoining edges, because we have occasionally observed that when the opposite and parallel edges have been laid first, without continuing the process progressively round the board, a greater degree of care is required to prevent undulations in the paper as it dries.

Sometimes strong paste is used instead of glue; but as this takes a longer time to set, it is usual to wet the paper also on the upper surface to within an inch of the paste mark, care being taken not to rule or injure

the surface in the process; the wetting of the paper in either case is done for the purpose of expanding it, and the edges being fixed to the board in its enlarged state acts as stretcher upon the paper while it contracts in drying, which it should be allowed to do gradually. All creases or undulations by this means disappear from the surface of the paper, and it is a smooth plane to receive the drawing.

In mounting paper upon canvas, the latter should be well stretched upon a smooth flat surface being damped for that purpose, and its edges glued down as was recommended in stretching drawing paper, then with a brush spread strong paste upon the canvas, beating it in until the grain of the canvas be all filled up; for this, when dry, will prevent the canvas from shrinking when subsequently removed. Then, having cut the edges of the paper straight, paste one side of every sheet and lay them upon the canvas, sheet by sheet, overlapping each other a small quantity. If the drawing is strong it is best to let every sheet lie five or six minutes after the paste is put on it, for as the paste soaks in, the paper will stretch and may be better spread smooth upon the canvas, whereas, if it be laid on before the paste has moistened the paper, it will stretch afterwards and raise blisters when laid upon the canvas. The paper should not be cut off from its extended position till thoroughly dry, which should not be hastened, but left in a dry room to do so gradually if time permit, if not, it may be exposed to the rays of the sun, unless in the winter season, when the assistance

of a fire is necessary, provided it is not placed too near a scorching heat. In joining two or more sheets of paper together by overlapping, it is necessary, in order to make a neat joint, to feather-edge each sheet, this is done by carefully cutting with a knife half-way through the paper near the edge and on the sides which are to overlap each other, then strip off a feather edge or slip from each, which, if done dexterously, will form a very neat and efficient joint when put together. The following method of mounting and varnishing drawings or prints may be considered useful. Stretch a piece of linen on a frame, to which give a coat of isinglass or common size, paste the back of the drawing or print, which leave to soak and then lay it on the linen. When dry give it at least four coats of well-made isinglass size, allowing it to dry between each coat. Take Canada balsam diluted with the best oil of turpentine, and with a clean brush give it a full flowing coat.

Pencils.

In selecting black pencils for use, it may be remarked, that they ought not to be very soft nor so hard that their traces cannot be easily erased by the India rubber. Great care should be taken in the pencilling, that an accurate outline be drawn, the pencil marks should be distinct, yet not heavy, and the use of the rubber should be avoided as much as possible, for its frequent application ruffles the surface of the paper and will destroy the good effect of shading or colouring, if any is afterwards to be applied.

DRAWING INSTRUMENTS.

The Compasses.

The compasses or dividers are instruments so well known; that it would be superfluous to enter into an accurate description of them, or of the various uses to which they may be applied. The best are constructed with joints of two different metals, as steel and brass, whereby the wear is more equal, and the motion of the legs uniform and steady, and not subject to sudden jerks in opening or shutting; this motion will occasionally require some adjustment to render it uniformly smooth, and to move stiffer or easier at pleasure; but so that they may keep steadily any position that may be given to them, the adjustment is performed by the application of a turn-screw to this axis of the joint. In the common compasses a simple screw forms the axis upon which the legs move, and may be turned with a screw driver of the ordinary construction; but in the best made instruments a steel pin passes through the joints, having at one end a head of brass riveted fast upon it, and on the other end a similar plate is screwed, which is therefore a nut, on a diameter of which is drilled two renall holes for the application of a lever of a particular description.

The points of a well-made instrument should be of steel, so tempered as neither to be easily bent or blunted; not too fine and tapering, and yet meeting closely when the compasses are shut. As some of the

numerous uses to which this instrument may be applied, the following may be mentioned:—To take any extent or length between the points of the compasses, and to set it off or to apply it successively upon any line. To take any proposed line between the points, and by applying it to the proper scale, to find its length. To set off equal distances upon a given line, to describe circles, intersecting arcs, &c. To make an angle equal to any given angle; to lay off an angle of a given quantity upon an arc of circle from the line of cords, &c.; to construct any proposal in plotting, or drawing plans, &c., &c.

The Hair Compasses.

This instrument is represented in the adjoining engraving, and is constructed in the same manner as those above described. The only difference consists in a contrivance *b*, whereby the lower point or half one shank, can be moved a very small quantity, either towards or from the other point which is useful when a distance is required to be taken with the utmost possible exactness. This contrivance consists of a fine spring and screw, by which, when the compasses are opened nearly to the required extent by the help of the screw *b*, the points may be set to the greatest precision, which cannot be done so well by the motion of the joints *alone*.




Compasses with moveable points.

In the smaller and more portable cases of drawing instruments, it is customary to insert a larger sized pair of compasses, of which the point of half of one of the legs is never moveable, to admit of adapting singly a pen or pencil, or dotting points. The pen point is used for drawing circles or arcs with ink, and is constructed like the drawing-pen which will be hereafter described; the pencil point is alike adapted to hold a piece of black lead pencil or crayon for describing circles or arcs that are not to be permanent, and the dotting point consists of two blades similar to those of the drawing pen, but rounded at the points, between which revolves a small wheel with numerous points round its circumference resembling the rowel of a spur. The space between the blades being supplied with Indian ink, and the wheels rolled upon paper, as the compasses describe a circle or arc, each point as the wheel revolves will pass through the ink and transfer it to the paper beneath, making equi-distant dots in the circle which the compasses describe.

The moveable points have a joint in them just under that part which locks into the shank of the compasses, by which the part below the joint may be set perpendicular to the plane on which the lines are described when the compasses are open. An additional piece called a lengthening bar is frequently applied to these compasses, which by lengthening the moveable leg

enables them to strike larger circles, or measure greater extents than they otherwise would perform. When this is applied, the moveable part has a joint similar to those on the pen and pencil points, and for a similar purpose the annexed diagram represents this instrument and its appendages.

A. The compasses with a moveable point at B; c and D, the joints to set each point perpendicular to the paper; E the pencil point; F the pen point (this is represented with a dotting wheel, the pen point, and the dotting point are similar in shape to each other); G the lengthening bar.



Bow Compasses.

These are a small pair having a point either for ink or pencil. They are used to describe small arcs or circles, which they do more conveniently than large compasses, not only on account of the size, but also from the shape of their head, which rolls easily between the fingers and can be turned round as delicately as they require to be moved for drawing very minute circles.

The adjoining figures represent the pencil bow as suited for describing arcs of different radii.




Fig. I. is a construction adapted for describing arcs of a radius intermediate between those described by the above-named compasses, and those capable of being produced by the bows represented by Fig. II.

In Fig. I. the pencil point *B*, and the centre point *F*, can be opened a considerable width by the joint *A*, whilst in the other construction, Fig. II., the corresponding points *E* and *G* are limited in their opening, the two blades carrying the points, being formed out of one solid piece of steel, and tempered so as to form a spring at the upper part corresponding with the joint *A* in Fig. I. The spring of the two blades is then kept in obedience by an adjusting screw *D*, by which the two points may be set to any required degree of minuteness, and very small circles may be described with a precision that could not be expected or scarcely attempted by the construction of Fig. I.


The pen bows are represented in the annexed engraving; their construction is similar to the pencil bows last described. In the pen point of Fig. I. there is a second joint just below letter *A*, by which, when the instrument is open for use, the pen may be set per-

pendicular, or nearly so, to the paper, which is essential in the use of the drawing pen. This is a corresponding contrivance with that before, as applicable to the compasses, with moveable points. In Fig. II. *B* shows the spring blades carrying the points *G* and *D*, and *C*, the adjusting screw, to set these points to the required radius.


Tubular Compasses.

The engraving on the other side represents this admirable instrument. It may be used as an ordinary pair of compasses, either with two fine points, a pen point, or a pencil point, and is capable of describing circles to any extent of radius from an eighth of an inch to fourteen inches and a-half, and with the advantage of reversing points which may be changed from pen to pencil, &c., without deranging the setting of the instrument when opened to any definite extent.

A and *B* are the two principal legs of the instrument, consisting of tubes moveable about a very nicely constructed joint at *C*. Within these are two sliding tubes *E* and *D*, which draw out their whole length, and are accurately fitted to the principal tubes *A* and *B*, so that they may be drawn out to their required extent with a smooth and steady motion, not subject to sudden stoppages, or to move with equally sudden jerks, a proof of bad workmanship, but uniformly, and not too easy.



To assist in this, their inner extremities are made to act as springs within tubes, wherein they slide, thus increasing their friction.



The outward extremity of each of the sliding tubes *E* and *D*, terminates in a square headed joint, *a* and *b*; upon these move the pieces *c* and *d*, which carry the point limbs of the compasses. The joints *a* and *b* in this instrument correspond with the joints *c* and *d* of the compasses, with moveable points as before described, and are used for a similar purpose, namely, to set the point limbs perpendicular to the paper, and consequently parallel to each other, at whatever opening the legs of the

compasses may be extended to.


In our engraving, the two point limbs *g*, *h*, and *e*, *g*, to the two carrying pieces which are jointed to the tubes at *a* and *b*, their pivots also give the means of inserting the position of the points; that is to say, the limbs can be turned upon these pivots so as to make the points *e* and *g*, or *f* and *h* change places. By this simple and ingenious contrivance, the draftsman, after having used the two fine points *e* and *f*, for fixing

with precision the opening of the compass to his required radius, may obtain a pencil point to describe a corresponding arc or circle, by simply turning the pencil limbs *h, f*, round on its pivot *d*, which will cause the point of a pencil or crayon placed in the tube *h*, to change places with the fine point *f* of the compasses, and as the pivot is (or ought to be) at right angles to a line connecting the points *f*, and of the pencil at *h*, the latter will exactly take the place of the former, at the same extent or opening, *e, f*. In like manner, by turning the pen limb *e, g*, round its pivot *c*, the pen point may be made to occupy the position of the fine point *e*, or whatever the compasses may have been set to in the first instance. The milled-head screw, represented at *k*, is for the purpose of fixing a pencil firmly in its tube *h*; the screw *i* is for adjusting the blades of the pen-point *g*, between which the ink is inserted to any required degree of fineness, so as to produce a corresponding fine or coarse circular line. The joint *m*, by removing altogether the screw *i*, gives the means of opening the blades for the better cleansing them after use, and is the same as applied to most drawing pens.

Portable or Turn-in Compasses.

This forms in itself a complete portable case of drawing instruments, consisting of a large pair of compasses with moveable points, which are also so contrived that one forms in itself a small pencil bow and the other a pen bow; and when the whole instrument is put toge-

ther and folded up (or the points turned in, from whence is derived the name of *turn-in compasses*) they occupy but a space three inches long, and may be carried in the pocket without being an incumbrance. The annexed engraving represents the instrument when all its parts are together. The principal legs of the



instrument are F and G, moveable, as usual, by a joint at A. The lower joints, B and C, afford the means of setting the front limbs, D and E, perpendicular to the paper, as explained before when describing the last instrument. Each of the point limbs may be removed from the legs F and G, and by means of their joints B and C form perfect instruments—the one a pen bow, represented at H, and the other a pencil bow, shown at J K. The points of these lesser instruments are all


adapted to slide into the principal legs, *r* and *g*, of the larger one, which are made hollow for their reception. A section of the limb *r* is shown at *j*, to convey to the reader a better idea of the arrangement.

It may easily be seen from the engraving, that by reversing either of the points in the principal instrument, as may be, leaving the other fine or plain point, *e* or *d*, to act as a centre. A sheath or case is sometimes applied to insert the instrument for carriage. There are also various forms and arrangements of the parts occasionally given to the instrument to suit the fancies of individuals; but the one we have described above will give the reader a correct notion of the general character of this class of instruments.

Large Screw Dividers.

We have now to describe another class of compasses such as are used for accurately dividing lines, &c., into a definite number of equal parts, or for setting off equal distances. The first of these is the large screw divider represented in the adjoining figure; *a* is the centre, about which the legs *a c* and *a b* open or shut; *b* and *c* are joints by which the point limbs may be set perpendicular as usual. The extent or opening between the points is regulated by a screw passing through a socket, *r*, and terminated at the other extremity by a milled head, by which the screw is turned round. Between this milled head and the nearest point limb is fixed what is called a micrometer head, decimally divided round its outer or cylindrical

edge. One turn of the screw carries the micrometer head completely round; therefore, when part of a turn only is given to the screw, the divisions on the head show what fraction of a turn has been given, and if it be known what number of turns or threads of the screw are equal to one inch, the points of these compasses may be thus set to any small definite measure of length with the utmost precision. The index or zero for reading the fraction of a turn of the screw is marked on the point limb below B: thus this instrument may be considered as a beam compass of small dimensions and minute accuracy.



Spring Dividers.

This instrument, represented in the accompanying diagram, is particularly useful for repeating divisions of a small but equal extent—a practice that has the

name of stepping, for which a small pair of hair compasses would also be found useful when the head is constructed as shown in the adjoining figure, or similar to that of the bow compass before described, and for reasons before stated. The upper part forming the handle is composed of brass or silver, whilst the lower part from *A* towards the points is made of one piece of steel of a spring temper, whereby the two points are always endeavouring to recede from each other, or open by their elasticity, which is counteracted by the adjusting screw *B*, by which it may be set to the required opening. This acts in the same manner as the micrometer screw, described as belonging to instruments before explained, but with this difference—that it has not the means of pointing out the measure of the material, or extent between the fine points of the compasses, which must therefore be taken from a suitable scale.



Wholes and Halves.

Having explained the general construction of the most approved instruments of the smaller kind for describing circles and dividing lines, we come now to allude to those employed in copying and reducing drawings. And first of the instrument represented in the annexed engraving, which is the simplest form of proportional compasses, and capable of reducing or enlarging in one proportion only—namely, one-half, from whence its name of wholes and halves is derived.

The points *A* and *E* are one piece of metal: likewise the points *B* and *D* are at the extremities of another piece of metal, and straight lines connecting these points pass through the centre, *c*. The legs of the instrument are connected together by a joint of the usual form at *c*, placed one-third of the whole length from one extremity: consequently, whatever may be the extent of the opening of the points *A* and *B*, it will always be double the extent of the opening of the other two points, *D* and *E*. Therefore, if the whole length of any line be taken between the opening of the two former points, the interval between the two latter points will be exactly one-half the length of the same line; consequently, this instrument affords the readiest means of

dividing a line into two equal parts, or *vice versa*. Its usefulness in dividing lines does not rest here; for, if the original line has to be divided into any number of parts—2, 4, 6, 8, &c., by constantly taking the half of the half in the same manner as taking the half of the original line in the first instance, the requisite number of subdivisions may be obtained.

Proportional Compasses.

This instrument is a very useful and necessary appendage to a case of drawing instruments, and although rather expensive in its original cost, it very soon repays

its owner in saving both time and trouble. The proportional compasses consist of two equal and similarly formed parts or limbs, *A E* and *B D* (*see the accompanying engraving*), which are represented as opening upon a centre *c*, and forming a double pair of compasses or points, *A B, E D*. When shut up, the two limbs appear as one, and a small stud fixed on one fits into a notch made in the other, and retains the instrument exactly in its closed position, the two points also at each extremity then coincide and become as one point. When thus closed the dove-tailed slits shown in the engraving as made in each limb, both equal and similar, also coincide and appear as one slit, and in this position only can the adjustment be made for any required proportion; that is to say, the instrument must always be closed in order to slide and fix the centre *c* in its proper place, and the opening of the small points *E D* at the other extremity.



The centre consists of pivot or steel pin which passes through dove-tailed pieces of brass, nicely fitted to slide in the before-named slits, and also through a circular nut or collar on each face which answers the double purpose of keeping the dove-tailed pieces of brass in their slits, and also firmly clamping them together by means of the milled head, *c*, when they are moved to the position required for the centre to occupy; on the

dove-tailed pieces a line is drawn for the zero to set the centre by, which in our engraving is represented as coinciding with the division on the limb marked 2, and nearly with the one marked 12. On the face of each limb there are two sets of division, one denominated lines, a second circles, a third planes, and the fourth solids. When the *zero* of the centre on the dove-tailed sliding-piece is set to the division marked 1, on the line of lines, then the proportion between any opening of the large points A B, will be two to one, or twice as great as the opening of the smaller points D E, and consequently any extent taken between the large points may be accurately divided into two parts by the smaller ones. Also when the *zero* is set to the division marked 3, on the same lines, the proportion of any opening will be three to one, or that of the smaller points will be one-third of the extent of the larger points, and the same of the remaining divisions on the line which extend to ten of the line marked "*circles*" on the opposite edge of the same face of the instrument; the divisions are numbered from 6 to 20, and the index of *zero* being set to any number, the points will open in the proportion of the radius of a circle to the side of an inscribed polygon of that number of sides. Thus if it be set to the division marked 8, and the points A B are opened to the radius of any circle, the opening of the smaller points D E, will divide the circumference into eight equal parts.

The other lines of divisions, namely, those marked planes and "*solids*," are on the other face of the instru-

ment, these are in fact lines of square and cube roots. The line of "*planes*" or "*squares*" shows the proportion between the areas of similar plane figures. Thus, set the *zero* to the division marked 3, and measure the side of the square in the large points A B, the opening of the short ones; D E, will then be equal to the side of a square, which will be one-third the area of the other. The same of triangles, circles, or any other regular plane figure.

To find the square root of a given number, shut the compasses and set the *zero* to the number given upon the line of planes, open the instrument, and from any scale of equal parts take the number between the larger points A B, then apply the smaller points D E, to the same scale, and the distance between them will be equal to the square root of the distance between the points of the larger legs A B. The mean proportional between two given numbers is the square root of their product, and may be found by the proportional compasses; thus, required the mean proportional between 2 and $4\frac{1}{2}$:—Open the compasses with the *zero* or index set against 9, the product of two given numbers, till the distance between the larger is equal to 9, taken from some scale of equal parts, then the distance between the smaller points will be equal to 3 of the same scale, and is the mean proportional between 2 and $4\frac{1}{2}$, for as $2 : 3 :: 3 : 4\frac{1}{2}$.

The line of "*solids*" expresses the proportions between cubes or spheres. Thus, set the *zero* to the division marked 2 on the line of solids, then measure


the diameter of any sphere, or the side of a cube which will have one half the solid content of the former. In like manner by setting *zero* to the divisions marked 3, 4, &c., the interval between the larger and smaller points of the instrument will show respectively the diameters, &c., of spheres, of which one shall have three or four times the solid of the other.

Also the cube root of any number may be found by setting *zero* upon the given number upon the line of solids, &c., as described for obtaining square root by means of the line of planes ; proportional compasses of the best construction are sometimes made with a clamp and tangent screw for setting the zero with the utmost precision, this however is seldom used, and the instrument we have described is the kind in general requisition.


Triangular Compasses.

The adjoining figure represents this instrument as it appears when closed up for packing in its case. That which appears in the engraving as one limb, *A*, consists of a pair of compasses precisely of the ordinary construction ; the single point limb *B*, has a compass joint at *a*, by which its points may be opened at right angles to the plane of the pair of compasses *A*, when the three points will form a triangle. The compass point at *a* is firmly attached to the centre of the compasses *A*, which, by means of a nut or screw *b*, may be turned round without moving the limbs, of which it is the centre. The double motion thus given to

the point limb B (both right angles to, and parallel to the plane of the compasses A), partake of the nature of an universal joint, and enables the three points of the instrument to be placed at the angular points of any shaped triangle whatever, be it ever so obtuse. Also, by the same means, the three points may be brought into one straight line. This instrument, it will be obvious from the description, is chiefly useful in transferring points from one paper to another, and is very serviceable in copying mechanical drawings. The two points of the compasses A being set upon such points of the drawing as are already copied; the third point, B, of the instrument may be moved by its universal joint, *a b*, to rest upon any other point, and then by similarly applying the points of A to the corresponding points on the copy, the new point of the original may be correctly transferred to it by means of the limb of the instrument B.




Another form of triangular compasses is represented in the annexed engraving. *a, b, c*, is a solid tripod, having at the extremity of each arm a limb *c, d, and e*, moving freely upon centres by which they may be placed in any position with respect to the tripod and each other. These limbs carry points at right angles to the plane of the instrument, which may be brought to coincide



with any three given points on the original drawing, and then transferred to the copy as above described.

Beam Compasses.



The accompanying diagram represents this instrument which consists of a beam *A A*, of any length required, generally made of well-seasoned mahogany upon its face; is inlaid, throughout its whole length, a slip of holly or box-wood *a, a*, upon which are engraved the divisions or scales, either feet and decimals, or inches and decimals, or whatever particular scale may be required: those made for use of the persons engaged on the ordnance survey of Ireland, were divided to a scale of chains, 80 of which being equal to six inches, which therefore represented one mile, that being the scale to which the survey is being plotted. Two brass boxes *B*, and *C*, are adapted to the beam; the latter may be moved by sliding to any part of its length, and fixed in position by tightening the clamp screw *E*. Connected with the brass boxes are the two points of the instrument *G* and *H*, which may have any extent of opening by sliding the box *C* along the beam, and the other box *B* being firmly fixed at

one extremity. The object to be attained in the use of this instrument is the nice adjustment of the points *G* and *H* to any distance apart; this is accomplished by two verniers or reading plates, *b c*, each fixed at the side of an opening in the brass boxes to which they are attached, and afford the means of minutely-subdividing the principal divisions *a a* on the beam which appear through those openings; *D* is a clamp screw for a similar purpose as the screw *E*, namely, to fix the box *B* and prevent motion in the point it carries after adjustment to position; *F* is a slow-motion screw by which the point *G* may be moved any very minute quantity, for perfecting the setting of the instrument after it has been otherwise set as nearly as possible by the hand alone.

The method of setting the instrument for use may be understood from the above description of its parts, and also by the following explanation of the method of examining and correcting the adjustment of the vernier *b*, which, like all other mechanical adjustments, will occasionally get deranged; this verification must be done by means of a detached scale. Thus, suppose for example that our beam compass is divided into feet, inches, and tenths, and sub-divided by the vernier to hundredths, &c. First set the zero division of the vernier to the zero of the principal divisions on the beam, by means of the slow-motion screw *F*. This must be done very accurately. Then slide the box *c* with its point *G*, till the *zero* on the vernier *c* exactly coincides with any principal division on the beam, as 12 inches or 6

inches, &c., which must also be done to a great nicety, (*in some superior kind of beam-compasses, the box c is also furnished with a tangent or slow-motion screw, by which the setting of the points or the divisions may be done with the utmost precision in the same manner as the vernier b, by means of the screw r,*) then apply the points to a similar detached scale, and if the adjustment is perfect the interval of the points G H will measure on it the distance to which they were set on the beam. If they do not by ever so small a quantity, it should be corrected by turning the screw r till the joints exactly measure that quantity on the detached scale; then, by loosening the little screws which confine the vernier b in its place, the position of the vernier may be gradually changed till its *zero* coincides with the *zero* on the beam, and then tightening the screws again the adjustment will be complete.

Knife, File, Key, and Screw-driver.


The annexed engraving represents a very useful appendage to a case of drawing instruments, its use will



be too apparent to need much description. A is the knife blade, B the file, C the screw-driver, and D the key, which is adapted to fit the heads of the compasses for tightening or loosening them as may be required.

Drawing Pens.

These are made as represented in the accompanying engraving. The left-hand figure shows the form of the best kind, the handle is of ivory, and the blades have a joint whereby they may be opened for the purpose of more effectually cleaning them after use. The right-hand figure, which is in two parts, shows an older form of construction, the part A, to which is attached a pricker or protracting pin, screws into the part marked B, making the handle of sufficient length to use conveniently as a drawing pen, thus combining two instruments in one.



The milled head screw, which is represented as connecting the blades together, is for the purpose of setting their points at any opening to draw a line of an assigned thickness. In using the pen, it should be slightly inclined in the direction of the line to be drawn, taking care, however, that the edges of both the blades touch the paper. These observations are equally applicable to the pen point of the compasses before described, observing, as before stated, that whenever a circle or an arc of more than about an inch radius is to be described, the point should be so bent that the blades of the pen be nearly perpendicular to the paper, and both of them touched at the same time.

The Road Pen.

This instrument consists of two pens, A and B, so arranged with a spring which gives them a tendency to separate from each other to the extent of about half-an-inch, which tendency is counteracted by a screw, c, whereby the pen-points may be set to any required interval within the above limits. The screws a and b are for the purpose of setting the points of the blade to draw lines of any assigned degree of fineness, as before explained for the ordinary drawing pen. The use of this instrument is to draw two lines parallel and close to each other at the same time, whereby perfect parallelism may be secured. It is usually known by the name of the Road Pen, having been originally designed to draw lines of roads upon maps, both sides being drawn at the same time. For such purposes it is very convenient, as one side or fence may be drawn with a stronger line than the other, which is frequently done on general maps as a distinguishing mark for principal or turnpike-roads, &c. In like manner it is useful in drawing lines of canals, where bounding lines are generally more nearly parallel than on public roads; besides which, it may be successfully used in mechanical and architectural drawings, where extremely close parallel lines are very frequently required.

The Dotting Point.

The great expense of time in dotting by hand such lines upon a drawing as may be essential to be shown and not drawn in full, may be obviated by the use of this instrument. It in all respects resembles a drawing-pen, except that the points are not so sharp, and the back blade, as seen in the engraving, is a pivot on which may be placed a dotting-wheel, *a*, resembling the rowel of a spur; the screw, *b*, is for opening the blades to remove the wheel for cleaning after use, or replacing it with one of another character of dot. The cap, *c*, at the upper end of the instrument, is a box containing a variety of dotting wheels, each producing a different shaped dot. These are used as distinguishing marks for different classes of boundaries on maps; for instance, one kind of dot distinguishes county boundaries, another kind *parish* boundaries; a third kind distinguishes that which is both a county and a parish boundary. In using this instrument, the ink must be inserted between the blades of the dotting wheel, so that as the wheel revolves the points shall pass through the ink, each carrying with it a drop and marking the paper as it passes. It is sometimes stated as an objection, that the wheel will often revolve many times before it begins to deposit its ink on the drawing, thereby leaving the first part of the line altogether blank, and in attempting to go over it again, the made dots are



liable to get blotted; at all events, the line is likely to consist of dots of different sizes, which is at least unsightly. This evil may be mostly remedied by placing a piece of blank paper over the drawing at the very point the dotted line is commenced upon; then begin with drawing the wheel over the blank paper first, so that by the time it will have arrived at the proper point of commencement, the ink may be expected to flow over the points of the wheel, and make the dotted line perfect, as required.

The Pricking or Tracing Point.



This instrument consists of a pair of forceps, which firmly hold a needle point, or blunt point, *a*, by means of a sliding ring, *b*. Its use, which scarcely needs pointing out, is chiefly in copying drawings, the original being laid upon paper intended to receive the copy, and held down by weights or pins to prevent its shifting its position. The principal points are transferred to the copy by pricking through the original with a very fine needle. This method of copying cannot be resorted to when the original is of considerable value. When such is the case, a common method of copying is by placing between the drawing and the intended copy a sheet of thin paper (*such for instance as bank post paper*), one face of which has been sprinkled with black lead and rubbed until it be uniformly covered, and then as much wiped off as would come away with gentle rubbing. This being placed

with the blackened part towards the intended copy, a blunt point substituted for the needle point in the instrument may be drawn with gentle pressure over the lines of the original without damaging it, and the blackened paper will leave corresponding lines on the fair sheet beneath ; by reversing the needle in the instrument, leaving the eye end instead of the point exposed, and using it edgeways, it will be found a fine and smooth tracer.

Drawing Pins.

These require but little explanation. They are used to fix paper down upon a drawing or other board in any required position, and in most cases answer better than heavy weights, which are frequently used for that purpose, as the board may be shifted from place to place without moving the paper. They consist of a brass head with a steel point at right angles to its plane. A represents it as seen edgeways, and B as seen from above.



SPECIFICATION of the different Artificers' Work required for the erection of two houses proposed to be erected on a plot of ground, situate for according with, and corresponding to the various drawings, comprising plans, elevations, sections, and details, made and combined with this specification for the purpose of such erection, and under the superintendence of

CARCASS OF BUILDING.

EXCAVATOR.

THE ground is to be excavated to the whole of the extent of the principal building for the basement storey, and to the depth and dimensions shown, and described on the plans and section plates 2 and 3, which will average an area of about 50 feet by 50 feet, and 5 feet deep; and the trenches then to be dug out of sufficient breadth and depth for the construction of the foundations of the several walls, chimney breasts, piers for sleepers, &c. To excavate when and where directed, according to the dimensions, the earth required for the formation of the rain-water tank, being about 11 feet long, 8 feet deep, and 8 feet wide, as well as for all pipes, drains, traps, syphons, or cesspools, that are, or may be hereafter, described or necessary.

To fill in and well ram the earth or soil round all the foundations, piers, traps, gullies, syphons, &c., and to well puddle round and about the rain-water tank, sufficient to prevent the ingress or egress of water. To level all grounds and to cart away from time to time, as may be directed, all the superfluous earth or rubbish that accumulates round or in the buildings or grounds during their erection, and to leave them in a clean and perfect condition at the conclusion of the works.

BRICKLAYER.

Drains.

Provide and lay six-inch glazed earthenware socket-jointed pipes, for conveying soil and waste-water into principal drain or sewer, in the position and to the depth shown on the block-plan and section, Plate III., with a fall of not less than 6 inches to every 100 feet, and to fix and make perfect and secure, No. 8 15 inch earthenware gully-traps, and No. 4 syphons of the best and most approved description. To lay a 6-inch similar connecting pipe from principal and servants' water-closets, as well as 4-inch glazed pipes, from sink in back kitchens and front areas into the above named or principal drain, with all necessary bends, traps, &c., to render the drainage perfect. Build in 9-inch sound stock brickwork, the rain-water tank, and complete the same in the manner shown and described, and to the dimensions exemplified on Plate XIV., viz: The walls all round to be built in 9-inch brickwork in cement,

and the bottom to be paved with two course of bricks laid flat in the same material, upon which are to be two courses of tiles bedded in cement, and the whole to be rendered all round with compo $1\frac{1}{4}$ inch thick, and all the external portion to be well puddled. To lay and fix complete 4 inch glazed earthenware socket-pipes, from the zinc down-comers of roofs into the said tank, and a 6 inch waste ditto into the principal drain or soil pipe, with all necessary bends, neck, or traps, that may be requisite for the full completion of the conveyance of the water to and from the tank and the drainage.

Building.

The whole of the brickwork to be executed with sound hard-burnt stock bricks laid in well-made mortar, composed of Dorking lime (or any other that approximates to the same quality), mixed in the proportion of one measure of lime to three of clean sharp river or road sand, free from loam or earthy particles.

The whole of the external walls of the erection as high as the ground-floor line to be laid in old English bond and left rough for receiving Roman cement stucco, and from thence to the top of the building, to be carried up in Flemish bond and prepared and left for tuck pointing. No four courses in either bond to rise more than 12 inches in height, and all the several walls, chimney-breasts, piers, &c., with their various footings, to be built and finished in the manner and according to the dimensions shown and described upon the accompanying plates.

All openings below the ground-floor line to have rough skue-back arches turned over them, and all above, both to front and back elevation, to have 14-inch arches of the best picked malms rubbed and set in putty.

The foundations to be laid in three courses, and the piers for sleepers to be built 9 inches square, as shown and described on Plate XV. To provide and lay a course of slates between two beds of cement on all the walls at the level of the ground surface of the principal building to prevent the rising of the damp.

Each storey of the building to have two double tiers of hoop-iron bonds, of No. 12 gauge, properly tarred and bedded round and across all the walls of the building. To build up the bay-windows and porches to entrance-hall in cement, and according with the manner and dimensions shown and described on Plates XXII. and XXIII.

No. 6 air bricks to be inserted between the floor joists of each storey in front, and the same number in the back elevations, for allowing ventilation to the floors.

To turn over all door and window openings $4\frac{1}{2}$ discharging arches closely set, and to each fire-place a $4\frac{1}{2}$ inch brick trimmer, and insert a wrought-iron chimney-bar 2 inches wide by $\frac{3}{8}$ of an inch thick, as shown on Plate XVII., to all the chimney openings; the bars to have $4\frac{1}{2}$ inch bearing and to be turned up and down at the ends.

Carry up all the flues as shown on section, and in the

direction thereon described, and to properly core and parget the same.

To thoroughly bed in mortar all the sleepers, wall-plates, wood, bricks, bond-timber, lintels, and all others requiring to be set or bedded in mortar, and to fix in and point with lime and hair all the door and window frames.

A chasm in the brickwork of each house to be left where directed, from the ground to the principal water-closet, for soil and water-pipes.

Kitchen Offices.

The walls of these buildings to have two courses of footings, and carried up to their various heights one brick or 9 inches thick, and the flues to be taken, as shown on the section one tier of iron hoop bond similar to that described for the principal building, to be inserted all round the party and external walls.

A 6-inch glaze earthenware soil pipe to be laid from servants' water-closet into principal or main drain, and a 4-inch ditto from sink in back-kitchen into waste-drain, properly trapped and in connection with waste or soil-pipe of the above named closet.

To carry up 4½ inch division or protection walls between water-closet, coal-cellar, and back-kitchen. Also to 9-inch spandril brickwork, with necessary footings for the support of steps from ground-floor to garden.

CARPENTER.

All the timber used (*except for the sleepers*) to be the best Dantzic, Riga, or Memel fir. *The sleepers to be of well seasoned oak*, as free from knots, shakes, and sap as possible, and all the scantlings figured on the drawings or herein expressed to finish to their full dimensions. No ceiling joists, quarters, or rafters are to be more than 12 inches apart.

To provide and fix all wood, bricks where and when required, as well as all necessary centres, screens, springing slips, and all other articles necessary for the due execution of the carpenter's work.

BASEMENT STOREY.

The sleepers to be of oak 5 × 3 inches, halved and spiked together, and bedded level and soundly on the brick piers, as shown and described on Plate XV.

The floor joists to be 4 × 2 inches, bridged and well nailed to sleepers.

Wood bricks to be inserted where requisite in jambs of doors, windows, &c., as well as round the walls for fixing the skirting and other joiner's work to.

Lintels to be inserted over all the door and window-openings, 3 inches thick, and the width of the jamb; and to have at least a 4-inch bearing on each jamb.

Ground Floor.

Wall-plates $4\frac{1}{4} \times 3$ inches to be inserted the whole length of front and back walls, to be halved and dovetailed at the angles of the two external flank walls, and return upon the same not less than 6 feet, to form a connecting bond with the front and back walls of the building. A wall-plate of the same scantling to be also inserted upon the top of the wall dividing breakfast room from kitchens.

The floor-joists to be 9×2 inches, and to extend from front to back wall of building and over-bay window, and to be bolted and spiked to the wall-plates. The joists to be herring-bone trussed, and to have on the floors of each house No. 3, 1-inch wrought iron tension-rods inserted, as shown and described, with the trimmers on Plate XIX. It must be distinctly understood that before the herring-bone trussing and iron tension-rods are applied, the joists on each floor must be shored up in the centre to form a camber of at least $2\frac{1}{2}$ inches, when, after the trussing is filled in, and the above-mentioned rods screwed up, the shoring may be taken away.

The wood trimmers before and on the sides of chimney-breasts to be framed and supported as shown and described on Plate XVI. It may, perhaps, be as well to state, that they are framed at one end into the front one, and rest upon a stone corbel inserted purposely for their support at the other; and after being properly applied to their places, are secured by

an iron bar being well spiked to the end of each end trimmer.

The trimmers for well-hole of stairs to be of the same scantling, and supported from the flank walls in a similar manner.

Lintels, bond, wood, bricks, and every other requisite to be inserted as before described for the basement floor.

First or Chamber Floor.

The wall-plates to be $4\frac{1}{2} \times 3$ inches, and to extend the whole length of front and back walls of building, to be halved and dovetailed and well spiked at the angles, and to return upon the flank walls, not less than 6 feet, to form a connecting bond at the angles. The floor joists to be 9×2 inches, and to extend from front to back and over bay windows, and to be notched and spiked to wall-plates.

The joists to be herring-bone trussed, and wound up with wrought iron tension rods, as shown and described for the ground floor below.

Also, the trimmers to be framed, fixed, and supported in a similar manner; at the same time providing and fixing all necessary centres, bond, wood, bricks, and every other requisite.

Attic.

The wall-plates of this floor to be of the same scantling, and to be fixed on the walls in a similar manner, to that above described for the two floors below. The

floor joists to be also 9×2 inches, and fixed, herring-bone trussed with the iron rods applied in a like manner to those before described, as also the trimmers ; with all the necessary auxiliaries alluded to for the before-named floors.

Quarter-partitions.

The partitions to be framed and fixed in the manner shown and described on the Plates XXIV. and XXV., and the floor joists notched and secured to the heads or sills thereof (*as the case may be*), which heads and sills are to rest on a stone corbel inserted in the party wall for that purpose, and connected together by iron straps, as shown and described at fig. 2, Plate XXV. The scantlings to be of the following dimensions, viz. :—heads and sills, 7×3 inches ; side and door posts, $4 \times 3\frac{1}{2}$ inches ; braces, $3\frac{1}{2} \times 3\frac{1}{2}$ inches ; filling in quarters, $3\frac{1}{2} \times 2$ inches ; with all necessary bolts, ties, straps, &c., fixed complete.

Cisterns.

A cistern to be framed and fixed in the roof over water-closet, and put together with white lead, as shown and described in Plate XXIV., figs. 4 and 5, and to be of the following dimensions, viz. :—8 feet long, 6 feet wide, and 3 feet deep ; the quarterings of the *heads, sills, sides, and bottom*, to be 3×3 inches, framed and put together in the usual manner, with $1\frac{1}{2}$ by $\frac{1}{4}$ thick iron ties at all the angles, properly spiked

thereto; the whole to be lined with $1\frac{1}{2}$ inch ploughed and tongued yellow deal boarding.

A smaller cistern also to be prepared and fixed immediately under the one above described, but just above the water-closet, upon the quarter space of stairs between the ground and chamber floors; the size of which is to be 2 feet 6 inches long, 1 foot 6 inches wide, and 1 foot 6 inches deep—to be prepared from $1\frac{1}{2}$ inch yellow deal, ploughed, tongued, dove-tailed, and strapped in the usual manner.

Roof to principal Building.

The roof to be framed and fixed with wall-plates, tie-beams, queen and king posts, principal rafters, half principal ditto, pole plates, purlins, common rafters, diagonal ties, slips, ridges, &c., as shown and described on Plates XX. and XXI., and with the accompanying explanation, viz.:—Two whole pair of principal rafters to be framed and fixed at the intersection of the hips, and eight half principal rafters in the position shown on plan of roof to be framed into them; the wall plates to be properly scarfed and wedged together with oak or iron wedges, and to be halved, dove-tailed, and well spiked at the angles, so that it may form and be a continuous bond all round the external walls of the building; the tie-beam and angular ties to be properly coggled down upon the wall-plate; the principal rafters and half principal rafters to be framed with the necessary draft, and in the usual manner, with all the requisite *iron bolts, clips, straps, wedges, &c.*, fixed thereon;

the pole plates to be scarfed and wedged together, and tenoned and fixed at the angles, so that it may make a continuous tie to the roof, in the same manner the wall-plate does to the walls, and the purlins to be scarfed where required, and fixed to hips in the usual way—and to be bridged down upon principal rafters; the hip rafter to be framed into the dragging tie, and the common rafters to be notched on to purlins and pole plate. The ridge board and hip rafters to rise full 2 inches above the top or line of common rafters for dressing the lead round. The scantlings of the timbers for this roof are to be as follows:—

The plate for fixing brackets to	4½ by 3½
Wall-plate	4½ „ 4½
Cantilevers, to be halved and nailed to feet of	
common rafters	4 „ 2
Tie beam	9 „ 4
Principal rafters	7 „ 4
Pole plate and purlins	7 „ 4
Common rafters	4 „ 2
Queen and king posts in clear of joggles	4 „ 4
Braces or struts	4 „ 3
Hips and ridges	12 „ 2
Diagonal and dragging ties	4½ „ 4½
Battens for slates	2 „ 3
Collar pieces	7 „ 3
To prepare and fix to collar pieces of roof ceiling joists	4½ „ 2

And to fix, as shown in Plate XX., all canting fillets, facia, as may be required, to their various sizes, &c.

Kitchen Offices.

To prepare and fix in jambs and other places required, and where directed wood bricks for fixing and

completing the joiner's work, and to prepare and bed lintels over all door and window openings; the width of the jambs $3\frac{1}{2}$ inches thick, and to lay $4\frac{1}{2}$ inches on each jamb.

The servants' privy to have a wall-plate $4\frac{1}{2} \times 3$ inches inserted, and to have floor $4\frac{1}{2} \times 2$ inches notched thereon, and trimmed for pan of closet.

The roofs over these buildings to be plain lean-to roofs, each declining from the party-wall, and to the same inclination, as that of the principal building, and to comprise a *wall-plate*, *tie-beam*, *principal rafter*, *forming common rafter as well*, a *purlin* supported by a *strut* from the *tie-beam*, and a *pole plate*; the whole to be battened for receiving slates, &c.

The scantlings for these offices are to be of the following dimensions, namely:—

Wall-plates, $4\frac{1}{2} \times 3$ inches; tie-beams 8×4 inches; pole plate, $4\frac{1}{2} \times 3$ inches; principal rafter, 8×3 inches; common rafters, $3\frac{1}{2} \times 2$ inches; ridge-board, $6 \times 1\frac{1}{2}$ inches; and battens for slates, $2 \times \frac{3}{4}$ inches.

Two cisterns to be prepared and fixed in roofs over the sinks for receiving the water from the service and the rain-water tank; these cisterns are to be 4 feet long, 3 feet wide, and 2 feet 6 inches deep, and framed with skeleton angular framing; that is to have a head and sill all round with quartering, at all the angles similar to that described for the cistern in principal roof, with one upright in the middle, and a corresponding piece across the bottom, the whole to be lined with $1\frac{1}{2}$ inch yellow deal, ploughed, tongued, and put together with

white lead. A partition in each cistern prepared in the same manner, from one inch yellow deal, to be inserted and grooved into sides and bottom.

To provide and fix when and where directed, all centres, bond, timber, wood, bricks, springing pieces, &c., and set out all necessary work, and to do or cause to be done all and everything that is required of a carpenter in a building, providing all materials, the best of their respective qualities, and all requisite plant for the full completion of the work.

SMITH AND IRON-FOUNDER.

All the iron work, except that particularly described to be *cast*, to be of the best malleable metal, as free from blister or any other imperfections as possible. To prepare, deliver, and assist in fixing No. 16 wrought iron chimney bars, of the dimensions of the opening shown on the various drawings, and of the form and manner described in the detailed plates, each bar to be 2 inches wide, and $\frac{3}{4}$ th of an inch thick, to have a $4\frac{1}{2}$ bearing on each joint, and to turn up and down $2\frac{1}{2}$ inches at each end.

To prepare and deliver No. 8 iron straps, 2 feet 6 inches long, $2\frac{1}{2}$ inches wide, and $\frac{1}{4}$ thick, punched with holes for the necessary spikes, &c., for tying heads and sills of partitions together, and as shown on Plate XXIV. fig. 2, prepare No. 6 iron clips for partition posts, 2 feet long, $3\frac{1}{2}$ clip, 2 inches wide, and $\frac{1}{4}$ inch thick.

To prepare, provide, and assist in fixing, No. 18, one inch wrought iron tension rods, to extend from front

to back walls of the building, three of which are to be fixed in each floor of each house of the building, with 2-inch head, one inch thick at one end, and taped up at the other end at least four inches, with a nut of the same size as the head, with a pair of washers to each rod, 6 inches by 3 and $\frac{1}{4}$ of an inch thick. See Plate XIX.

To prepare and deliver No. 12 iron clips for feet of principal rafter as shown on Plate XXI., fig. 1, 18 inches long, 4 inches clip, 2 inches wide, and $\frac{1}{4}$ -inch thick, pierced for the necessary spikes, &c.; No. 4 clips for foot of queen posts, figs. 3 and 4, 2 feet long, 4-inch clip, 2 inches wide, &c., $\frac{1}{4}$ inch thick, with mortice for wedges, $1\frac{1}{2}$ inches deep, and $\frac{3}{8}$ thick, and a pair of corresponding wedges to each clip.

No. 4 pairs of iron straps to fix on to the heads of queen posts, *stretching piece* and head of principal rafter, made to the form shown on the same plate, 2 feet 6 inches long, 2 inches wide, $\frac{1}{4}$ inch thick, pierced for the requisite spike, &c.

No. 4, $\frac{3}{4}$ inch bolts for king posts, 2 feet long, taped down $3\frac{1}{4}$ inches, with 2 heads and washers, 4 inches by 3, and $\frac{1}{4}$ of an inch thick.

No. 8, clip similar to those described for the whole principal rafters, to be provided for the half principal rafter. No. 8 clips also to be provided for the heads of the same, 1 foot 6 inches long; clip 4 inches by 2 inches wide, and $\frac{1}{2}$ inch thick, with all necessary spikes, nails, wedges, &c., for making the work complete.

To provide and fix No. 8 angular irons to top and

sill of cistern in roof, 1 foot 6 inches upon each return, 2 inches wide, and $\frac{1}{4}$ -inch thick; and also No. 8 for the two smaller cisterns, 1 foot long, $1\frac{1}{2}$ -inch wide, and $\frac{3}{16}$ -inch thick.

STONE MASON.

To put to all the external doorways Yorkshire stone solid tooled steps, with mortice holes for receiving the ends of door-posts.

To provide and fix No. 8 properly dished and holed gully stones, 15 inches square and 3 inches thick, when and where directed; as also a 5-inch York landing, 10 feet long by 7 feet wide, or two stones to correspond to the same dimensions over the rain-water tank, with every preparation of receiving the slate filter, as shown on Plate XIV.

To prepare and bed No. 20 Yorkshire stones, 1 foot 3 inches square and 1 foot 4 inches deep, for receiving trimmers to floors and heads and sills of partitions, tooled as shown on Plate XXIV.

To prepare and fix 100 feet run of York throated coping, 12×3 , to area of front and back elevations, and to kitchen offices; also, 36 feet run of rough York, 1 foot 4 inches by 4 inches thick, to form core for the cornices of entrance porches and bay windows.

To prepare, provide, and fix tooled, rubbed, and throated window sills, 8 inches wide and $4\frac{1}{2}$ inches thick, properly dished, to all openings of windows in front and back elevations and kitchen offices, according to the dimensions shown on the various drawings.

To prepare and fix to the porches of entrance doors a 6-inch tooled and rubbed landing, with steps leading thereto, 12 inches by 6 inches, bedded to brick spandrils, as shown on Plate XXIII. Also, to fix a tooled landing 7 inches thick to the back or garden entrance, and the steps from thence to the garden, which are to be $2\frac{1}{2}$ inch tooled treads and risers securely bedded on brick spandrils carried up for that purpose.

To provide and fix in back kitchen a stone sink, to size shown on plan and 6 inches deep, with a hole cut and dished to receive bell trap and waste water pipe.

To cut on the stonework all necessary holes, mortices, rebates, grooves, as required, and all other work pertaining to the trade of a mason.

PLUMBER.

All the slips and ridges of principal roof to be covered with 6 lb. milled lead, and to be laid down over the slate at least 6 inches on each side with the usual lap, and secured in the most approved manner. The dormer lights to attics to be also covered with 6 lb. lead, and the vertical sides of each with 5 lb. lead. All the flashings for this roof, as well as that over kitchen office, to be of 5 lb. lead, and to dress over the slates and up the side at least 6 inches, and where requisite to be let into the brickwork at least 1 inch, with all necessary solder, holdfast screws, nails, &c., with every other requisite for making the internal roofs impervious to wet, from rain, snow, or other causes.

SLATER.

The roof over principal building to be covered with duchess slating, with at least 3 inches lap, and the usual gauge of about $10\frac{1}{2}$ inches securely fixed to the battens, with 2 copper nails to each slate; and to cover the kitchen office with lady slates, with the usual lap and gauge fixed to the battens, with 2 zinc nails to each slate, with all the necessary dressings to hips, valleys, and eaves, &c., and both roofs to be securely pointed with lime and hair.

To provide, prepare, and fix No. 12, 3 inch slate cantilevers, to the size and form shown in the drawing of details for roof.

To provide and fix in the rain-water tank a $\frac{3}{4}$ inch slate filter, according with and to the dimensions described on the plan and section Plate XIV., with all necessary lifts, perforated plates, taps, &c., and apparatus complete.

ZINC WORKER.

To prepare and fix all round principal building a gutter of the best Belgian zinc of 15 inch gauge, to the form and dimensions shown and explained on Plate XXI., with all proper falls to the various dimensions, and so manufactured in external appearance as to be level with the soffit of the projecting eave of the building, as shown on the before-named plate.

To put up and securely fix No. 6 downcomers of 4 inch calibre in the position marked on plan of roof.

To provide and fix the said in the position marked on the plan of roof, and each to have a suitable cistern head, with all necessary shoes, laps, joints, holdfasts, and every requisite to connect them with the earthenware pipes laid for conveying the water into the rain-water tank.

The gutters and downcomers from the roof over kitchen offices of 3 inch calibre, with corresponding cistern-head.

Also to provide and fix a 2 inch downcomer, with every requisite bend from the flats of the bay windows and entrance porches to the drain in front area.

FINISHINGS.

JOINER'S WORK.

Attic Floor.

The dormer light in each room to be fitted up with two inch beaded, and rebated frames, and $1\frac{1}{2}$ inch chamfered sashes, suspended on pivots in the centre, with all requisite cords, pullies, fastenings, &c., for the opening and closing of the same, in an impervious and efficient manner.

Floor.

The floor to be $1\frac{1}{4}$ inch white deal, and laid folding ; skirting ground 2 inches wide by $\frac{3}{4}$ thick, chamfered to receive plaster, and as shown on Plate 26, fig. 2, to be fixed all round the rooms, and a similar description

of ground to door and window joints, which are to be covered with a $1\frac{1}{4}$ inch moulding, to form an architrave and break the joints of plaster, and grounds, and to the ground round rooms, is to be fixed a 6-inch square skirting-board. The jambs of doors to have a $\frac{3}{4}$ inch beaded lining, and to have a slip braded on to form the rebate for doors, which are to be $1\frac{1}{4}$ inch; two panel square, hung with suitable butt hinges and fastenings.

Chamber Floor.

The floor to be $1\frac{1}{4}$ inch yellow deal, with a straight joint, and splayed heading, joints, with mitred borders to hearth's, a ground 2 inches wide by 1 inch thick, chamfered to be fixed all round the rooms for receiving the plaster and fixing the skirting to, and also one $3\frac{1}{2}$ wide of the same thickness round all door and window openings. The small housemaid's closet on this floor to be formed with a $1\frac{1}{2}$ inch square panelled partition, and the door to correspond with the other described for this floor.

The sashes and frames for the principal rooms on this floor, to be of the venetian character, with the centre sashes of each window, double hung, and side sashes fixed. The frame to be deal cased, with oak sunk sills, brass cased pullies, with $1\frac{1}{2}$ inch ovolo sashes hung with cast metal weights, patent cord, &c., and the sashes and frames for dressing-room and stairs to be of a similar description and double hung. The finishing to all these windows to be as shown and described on Plate XXVI.

The jamb lining for doors to be $1\frac{1}{4}$ inch thick, beaded

and single rebated, and to have $1\frac{1}{4}$ inch four-panel-square doors, properly hung with $2\frac{1}{2}$ butt hinges.

The skirting to be moulded 9 inches wide, and fixed in the manner shown at fig. 2, Plate XXVI.

Ground or Principal Floor.

The floor to be $1\frac{1}{4}$ inch yellow deal, straight jointed, splayed heading, joints edge-nailed, and mitred-borders to hearths.

Grounds.

Skirting grounds $2\frac{1}{2}$ inches wide, by one inch thick, to be fixed all round the floors for receiving the plaster, and fixing the skirting to the upper edge, to be ploughed, and all angles to be dovetailed together, as well as the ends secured in a similar manner to the vertical grounds of doors and windows—(see grounds to venetian window) Plate XXVI.

Entrance Hall.

The door frames to be 4 inches by $3\frac{1}{2}$ inches, rebated and beaded, with double rebated transom head, and to be tenoned into stone step.

The doors to be $2\frac{1}{2}$ inch, two panel bolection moulded on both sides, $\frac{7}{8}$ th panels, and to be hung with 3 pair of $2\frac{1}{2}$ butt hinges.

The fan-light to be a two-inch lamb's tongue moulded light and fixed above door, with grounds, linings, and architraves, corresponding with those shown and described for the floor on Plates XXVI. and XXVII. To put up with all the corresponding fittings, a pair of

two-inch sash doors, with a suitable light above, to divide the entrance hall from passage and stairs.

Also to provide and fix a two-inch sash door and partition to form the lobby under water-closet, and divide the stairs from the garden or back entrance to this floor, with all suitable finishings, and according to the one above described for dividing the hall from the stairs. The door frame from lobby to garden to be prepared for fan and side lights (*as shown on elevation of back front*), the external posts and head to be $3\frac{1}{2}$ inches by 3 inches, and the two vertical posts, as well as transom head, to be $3\frac{1}{2}$ inches by $2\frac{1}{2}$ inches, to be beaded, rebated, and tenoned into step, in a similar manner to that described for the front entrance door, and to have a two-inch sash-door fan and side-lights, with $1\frac{1}{4}$ inch framed boxing shutters as high as the transom head, the grounds, linings, and other finishings, to be similar to those shown on Plate XXVI., and described for the venetian window in the back parlour.

Bay-windows, Front parlours.

These windows to be fitted-up and finished in the manner shown, and described on Plate XXVII., with deal cased frames, oak sunk sills, and the centre position to have brass cased pullies, patent cords, and cast metal weights, and prepared to receive the sashes, which are to be 2-inch lamb tongue moulding, the middle sashes double hung, and those of the sides fixed. The other portions are to be prepared and fixed in the manner shown on the before-named Plate XXVII.,

for receiving metal, revolving shutters, and finished with the grounds, linings, soffit, skirting, architraves, as there shown and described.

Back Parlour.

The venetian window in this room to be fitted up in the manner shown and described in Plate XXVI., fig. 4; the middle sashes to be double hung, and the side lights fixed. To have $1\frac{1}{4}$ inch moulded shutters hung with brass, cased pullies, patent cord, and cast metal weights; and to have $1\frac{1}{4}$ inch framed and moulded back. The grounds, linings, architrave, &c., in a corresponding manner to those described and shown for the front parlour or dining room.

Doors.

To prepare and fix $1\frac{1}{4}$ inch double rebated and beaded jamb lining to the grounds for the folding-doors between the two parlours. The doors to be $1\frac{1}{2}$ inch double moulded, two panels in each door, and the grounds, architraves, &c., to be of the same description, and to correspond with those before described. The jamb-linings for the other doors to be of the same description as before stated, and to have $1\frac{1}{4}$ inch 4-panel doors moulded on both sides, with corresponding grounds and architraves.

Skirting.

All the skirting for this floor to be board wide and 1-inch thick, and to be surmounted with a $1\frac{1}{2}$ inch rebated moulding.

Basement.

Breakfast Room.—The floor to be $1\frac{1}{4}$ inch yellow deal, straight joints and splayed headings, and mitred borders to hearth. The bay window to have sashes and frames similar to those described for dining room above, and to have sliding shutters similar to those shown and explained for the back parlour windows, with door skirting, lining, and all others of a corresponding character.

Kitchen.

The floor to be $1\frac{1}{4}$ inch deal, folding and mitred border to hearth.

Sash Frames.

The sash frames to be of a similar description to those already described for the upper floor, and to have $1\frac{1}{2}$ inch ovolo sashes, and $1\frac{1}{4}$ inch square framed sliding or hung shutters with 1-inch grounds and $1\frac{1}{2}$ moulding to break the joint and form architrave, as those described for the attic storey.

Cellar Door.

Under principal entrance and back entrance doors to have frame $3\frac{1}{2}$ by 3 inches, beaded and single rebated and tenoned into stone steps or sills, and to have a $1\frac{1}{2}$ inch 4 panel bead and butt door. The back entrance door frame to be of similar scantling, but framed with a transom head for a $1\frac{1}{2}$ fan light, and the door to this frame to be a $1\frac{1}{2}$ inch sash

door with a lifting shutter; and all other doors on this floor to be $1\frac{1}{4}$ inch 4 panel square doors, with lining and finishing as above stated for the attics.

Stairs.

The stairs from basement to ground floor to have $1\frac{1}{4}$ wrought yellow deal strings, with $1\frac{1}{4}$ inch treads and 1 inch risers blocked and bracketed and securely housed into the strings in the usual manner.

The partitions forming the spandril framing, as well as those forming pantries and store closets, to be $1\frac{1}{4}$ inch square panel, and to have a 6 inch $\frac{1}{4}$ skirting board, to correspond with others that are to run round the passage.

Stairs from ground floor to chamber storey to be geometrical, with one circular string and quarter circular on landing as shown on Plan, and to have $1\frac{1}{4}$ inch yellow deal treads, risers, carriage and string boards, with all requisite carriage furrings to soffit, &c. The treads to have round and hollow nosings. The risers to mitre into the external string, which is to be dove-tailed to receive the ballusters and the return nosing; the other end of both treads and risers to be housed and securely wedged into the external string; a full scroll curtail step, with veneered riser and circular part to frame into external string, to be firmly fixed at the starting of the flight, and the succeeding step to be gradually carved until they join the straight flyers. (See Ground Plan, Plate V.) The whole flight to have $\frac{3}{4} \times \frac{5}{8}$ inch square ballusters dove-tailed into the end

of tread and string, and covered with the mitred nosing. One ornamental iron balluster, taped and to have nuts and screws complete, to be securely fixed in centre of scroll of curtail step, and No. 3 plain iron ballusters, corresponding with those of deal before described, to be fixed where requisite on the flight. The whole to be surmounted with a $2\frac{1}{2}$ inch moulded Spanish mahogany hand-rail, sunk to receive the ballusters and properly wreathed to well, and to have a corresponding mitred cap over curtail step. The same description of skirting as described for rooms of ground floor to be fixed all round hall and passage, and the same mouldings to continue up inside string of stairs: finding and applying all necessary joints, screws, and every other requisite to make the work complete.

Water Closet.

On quarter space.—The partition dividing stairs from water-closet to be a 2-inch framed and moulded sash partition with sash doors to correspond, prepared for receiving ground or stained glass, with the moulded skirting of stairs continued round on the stair side, and the whole to finish in accordance with the stairs.

Inside.—The window-frame and sash to correspond with the one described for the chamber storey. To fit up the seat and riser with $1\frac{1}{4}$ inch Honduras mahogany, the riser to be properly dished out to the form of pan, and to have a beaded box for handle. This seat to be covered with a framed and beaded skeleton for the flap to hang to, which is to be $1\frac{1}{4}$ inch selected mahogany,

hung with brass butts, and both frame and flap to have a projected moulded nosing; $\frac{1}{2}$ inch beaded skirting 6 inches deep to be fixed round back and sides, as also on ground in front of riser. The whole to be fitted up with all necessary scantling, bearers, &c., for the support of pan and apparatus, as well as the efficient support of the seat and riser, in the most approved manner.

Also to fit up with 1-inch Honduras mahogany an angular wash-board and closet, the closet underneath with a 1-inch square panel-door, hung to a beaded and suitable skeleton frame, with all suitable appendages for receiving basins and depositing towels, &c., and also to fix over chasm of soil, waste and supply-pipe, a 1-inch mahogany-framed skeleton-ground, rebated and beaded for a corresponding board, to be slightly screwed to the same for allowing easy access to the before-named pipe, a small moulding, to be fixed over ground, and plaster to break the joint; and to fix on all other articles that may be required for the full completion of the closet.

Kitchen Offices.

All the external door-frames to be $3\frac{1}{2} \times 3$ in yellow deal, beaded and rebated, and tenoned into stone sills or steps. Those to servants' water-closets, and to the lobby between kitchen and back kitchen to be framed with transom heads, and to have $1\frac{1}{4}$ lights fixed therein. The whole of the external doors to be $1\frac{1}{2}$ inch bead and butt, 4 panel doors framed flush on

one side, and square panel on the other. All internal doors to be fitted up in the same manner as those described for the attic. The doors for coal-shoots to have a small $2\frac{1}{2}$ inch \times 2 inch frame rebated and beaded, and 1-inch ledged doors.

The sash-frames and sashes for kitchens to be of a similar description to those described for chamber-floors; and each window to have a pair of $1\frac{1}{4}$ bead, bead and flush-panel shutters hung to the frame on the outside.

The small window to pantries, marked D D on the basement plan, to have $2\frac{1}{2} \times 2$ inch beaded and rebated frames, and a $1\frac{1}{2}$ inch sack hung upon centres for ventilation. The servants' water-closet, marked A on the same plan, are to have floor-joints 5×2 inches, and laid with $1\frac{1}{4}$ yellow deal. The seat and risers to be also of $1\frac{1}{4}$ inch deal, properly fixed and blocked to pan, and dished out in a corresponding manner; and a beaded box prepared for the pull; a movable $\frac{3}{4}$ beaded casing to be placed over pipes, with every article to make the work complete.

PLASTERER.

Attic.

Lath, plaster, and set the ceilings and partitions, and also render, and set the walls of the same.

Chamber Floor.

To lath, plaster, float, and set the ceilings and

partitions, and render, float, and set the walls; run a plain moulded cornice round the porch room of this floor of 6 inches girth, and one round back room of 5 inches girth.

Ground Floor.

Entrance and passage, lath, plaster, float, and set the ceilings; the partitions to be lathed, floated, and set in stucco; and render, float, and set the walls in stucco; and finish the whole for painting; and a plain moulded cornice of 5 inches girth to be run all round so far as the break for stair will admit.

The front and back parlours to have their ceilings and partitions lathed, plastered, floated, and set, and to have a 10-inch plain moulded cornice run round both rooms.

Basement Floor.

The ceilings of this floor to be lathed, plastered, floated, and set; and the walls rendered, floated, and set; the front room, or breakfast parlour, to have a plain moulded cornice of 5 inches girth run all round.

Stairs.

The stairs from basement to ground floor and all other contiguous conveniences, not before alluded to, to be finished as the rooms of the attic floor. The next flight from ground floors to chamber floors, with the lobby and water-closet included. To finish in the manner described for the entrance halls, that is to say, the soffit of the stairs and ceilings to be lathed,

plastered, and set, and partitions to be lathed, plastered, floated, and set with stucco; and all the walls rendered, floated, and set in stucco, and finished for painting. The stairs from chamber floors to attic to be finished in a corresponding manner to that already described for the chamber floor. All the ceiling and soffits to be twice lime-whitened.

Kitchen Offices.

To lath, plaster, and set all the ceilings, and to render and set the walls.

The ceiling and walls of these buildings to be twice lime-whitened.

Outside Work.

The tops of chimneys to be stuccoed in cement all round, with fillet moulding and blocking, as shown on front elevation, Plate IX.

The soffit of the eaves of principal building, to have a sinking between each bracket to form a panel, as shown on section fig. 1, Plate XXI., and to be lathed, plastered, and set, the portion round flank and back to be finished plain. The string-course and frieze to be finished in stucco, with Atkinson's cement, and in the manner shown and described on the same Plate.

The entrance porches and bay-windows to be finished in stucco as shown and described on Plates XXII. and XXIII., with cornice, piers, pilasters, spandrils, &c., all complete. The whole of principal front from basement to ground floor, line to be stuccoed with cement, and

have returned reveals, sides of steps to entrance hall, and party wall of area with sunk joints, as shown on Plate XXII.

MASON.

Attics.

To put to each fire-place in attic a hearth and back hearth of 3 inches Yorkshire stone, and to each opening jambs and head 5 inches wide and 1 inch thick, with a shelf of the same dimensions, properly cramped and fixed together.

Chamber Floor.

To provide and fix on this floor No. 4 marble chimney piece, with back-hearths, slabs, and shelves complete, to the value of 40s. each.

Ground Floor.

Provide and fix on this floor No. 4 marble chimney pieces, with back-hearth, slabs, and mantel complete, to the value of £3 each.

Basement Storey.

To provide and fix in the breakfast-room No. 1 marble chimney piece, with back hearth, slab, and mantel complete, to the value of £2 10s.

Kitchens.

To fix complete, rubbed York chimneys, with mantels and hearths complete, to the value of £2 each, and to

the back kitchen chimney pieces of the same description of stone to the value of 30s. each.

To pave the lobby leading from kitchen to back kitchen, and the whole of the kitchen offices, as well as the front and back areas, with $2\frac{1}{2}$ tooled York paving.

FURNISHING IRONMONGER.

Attic Floor.

To provide and deliver for dormer lights on this floor No. 8, $\frac{3}{4}$ -inch pivots, with side-plates, patent cord and pulleys for opening and closing the lights, as also No. 4 barrel 4-in. bolts, and requisite staples for fastening the same, with all necessary screws, nails, &c. Also to deliver No. 4, 6-inch iron-rim locks, with box staples, keys, and brass furniture, with all necessary screws and nails complete for the doors to these rooms.

Chamber Floor.

To provide and deliver all the brass cased pulleys, patent cord, cast metals, weights, &c., shown on the drawings, and described in the joiner's work for this floor, as well as 2-inch spring-fastenings to each sash.

To provide No. 16 pair of butt-hinges, with all necessary screws, &c., as well as No. 4, 6-inch morticed locks, with brass furniture complete, for the principal doors; No. 2, 4-inch brass spring and bolt latches for dressing rooms, and No. 2, 4-inch iron closet locks, with all requisite striking plates and furniture complete.

Water-Closet.

To provide the brass cased pulleys, cords, weights, fastenings, &c., for this window, as before described, as well as one pair of $2\frac{1}{2}$ butt-hinges for door, and a $4\frac{1}{2}$ brass spring and bolt latch with furniture complete for door.

Ground Floor.

To provide the brass cased pulleys, patent cord, weights, fastenings, &c., as before described for the sashes, as also a set of a similar description for shutters of back-parlour, and to provide and fix to the bay-window of this floor the metal revolving shutter shown on Plate XXVII., with all requisite machinery for their efficient action, as well as the necessary furnishing.

To provide for entrance doors to hall No. 4 pair of 4-inch butt-hinges, with all necessary screws, &c., and a best 10-inch draw-back mounted lock, with staple and all necessary furniture complete; as also a 12-inch door-chain, with brass knobs and asp complete, and two 10-inch barrel bolts, with staples and plates complete for top and bottom of door. The back entrance doors to have hinges, lock, bolts, and chain of a similar description; the shutters to have 18-inch bow-latch shutter-bars complete, with every necessary, &c., and to provide for doors dividing lobby from stairs, a 3-inch brass spring bolt latch.

To provide for shutters in back-parlour No. 4, 1-inch brass flush rings, with No. 2 brass clips for fastenings. To provide for doors not before alluded to on this floor

No. 8 pair of 3-inch butt-hinges, with all necessary screws, &c., and for folding doors No. 4, 12-inch brass flush-bolts, with all necessities, &c., as also to provide No. 6, inch mortice locks, with brass striking plates and furniture complete.

Breakfast Room.

To provide for the sashes brass cased pulleys, patent cords, and fastenings, as described above for back-parlour; but the shutter will require 3 pair of brass cased pulleys with weights, fastenings, and cords complete; the door of this room to be provided with a 6-inch mortice lock,* and brass furniture complete.

To provide for kitchen window and shutters the same number of brass cased pulleys, cords, and fastenings, as before described for the back-parlour.

To provide for the six back-entrance doors 9-inch iron spring-stock locks with staples complete, No. 6, 10-inch door chains, and No. 12, 10-inch barrel-bolts and staples all complete, as also No. 6, 6-inch iron rim stock locks with box-staples complete for the other doors, and to provide No. 24 pair of 3-inch butt-hinges, as well as No. 8 pair of 2½ ditto, with all necessary auxiliaries, &c.

To provide one ornamental cast-iron balluster, 1½ diameter, 3 feet 6 inches long, tapped at one end, with nut and plates complete for curtail step, and three other, ¾ by ⅝, two feet 5 inches long.

It is to be distinctly understood that the furnishing ironmonger is to deliver all articles here expressed, and all others that may be requisite for the due execution of

the work into the possession of the joiner, who will apply and fix the same in their relative positions, providing and delivering as may be required glue, brads, nails, screws, and materials generally supplied by the ironmonger.

BELL-HANGER.

To provide and hang bells with all proper springs, cranks, wires, &c., of the size required, and in the position when and where may be hereafter directed, to the value of £10.

PLUMBER.

To line the cisterns in roof of principal building, as well as the four smaller ones described for supply of water-closet and kitchen offices, with six pounds milled lead, in the most efficient and workman-like manner, and to lay on from principal main to the large cistern in each house a $1\frac{1}{4}$ lead main supply-pipe, with a 6-inch ball-cock properly applied at the cistern end, with a standing waste of the same calibre to be taken down and connected with principal drains. The house-service, to be 1-inch calibre, to be taken into small cisterns over water-closets, and from thence into cistern in roof of kitchen offices; each of the smaller cisterns to be furnished with a suitable ball-cock, standing waste and service with rose-tops, and every other requisite article. The water-closets to be fitted up with Beetsen's patent valve closets, with Warner's registered valves and patent regulators fitted up

complete, and to have a 5-inch soil-pipe connected and continued perfectly sound into principal drain; and to complete the closet apparatus with all necessary bends, valves, traps, &c., to render them efficient and complete in all their actions, the service-pipes to be brought from the small cistern above, as well as two $\frac{3}{4}$ -inch service-pipes to supply the water to the washing-basins in corner; to provide and fix No. 2, 10-inch wash-basins, and fix to the $\frac{3}{4}$ pipes suitable cocks, and to the basins a stop valve, with chain and waste pipe complete, into principal drain.

To provide and fix to each house one of Warner's vibrating lift and force pumps, with all necessary pipe, bosses, and fastenings for supplying the filtered rain water into the cisterns situate in roof over kitchen offices, &c., and bring from the said cisterns two 1-inch service pipes to sinks in washhouse, with all proper taps, &c., as well as the waste pipes from cisterns, and all other articles that are requisite to make the supply of water complete; to provide and fit up in servants' privies two single-valve-pan water-closets, with flushing apparatus, and pipes of 1-inch calibre for water brought from cisterns in roofs, with necessary bends, traps, joints, &c., for carrying soil into principal drain.

The plumber to furnish and provide the water-closets as described, with all necessary traps, syphons, bends, pipes, lead, solder, joints, taps, cocks, bosses, roses, and every other article that is necessary for the full completion of his work.

GLAZIER.

To glaze the windows in attics with good seconds Newcastle glass, properly bedded and back puttied, and the window in chamber-floor and water-closet with good crown glass, which is to be well bedded, braded, and back puttied.

Ground Floor.

All the sashes on this floor to be glazed with 20-ounce crown glass.

Basement Floor.

The bay-window in breakfast-room to be glazed with 20-ounce glass, and all the other windows to be with the best Newcastle seconds glass.

PAINTER.

To knot, prime, and paint in three oils all the outside wood and iron work, and to flat any of the inside work when and where directed, and to finish the other in any colour that may be hereafter decided on.

PAPER-HANGER.

To prepare and hang (*except the hall passage, staircase, water-closet, and landing, which are to be painted*) the whole of the chamber floor with paper hereafter to be chosen, to the amount of 1s. 6d. a piece, and the front and back parlour on the ground floor, and the breakfast room on the basement floor, with paper to the amount of 2s. 6d. per piece, hanging and bordering included.

General Conditions.

It is to be distinctly understood that the party or parties contracting for the erection of the buildings herewith described, are to provide and deliver on the premises, all the materials, the best of their respective qualities, also to provide and furnish all necessary plant, scaffolding, labour, and all other articles that are requisite for the full completion and finishing of the work, according with the accompanying drawings and this specification; and if anything should be shown in the drawings and not herein specified, or anything herein specified that is not shown on the drawings, the same to be executed as if fully shown and explained in both; and if any alteration from the drawings or this specification should take place during the progress of the works, such alteration not to make the contract or estimate null and void, but the expense of such deviation to be added to, or deducted from (*as the case may be*), such estimate.

It is requested that the amount for each particular trade, with a tariff of prices upon which such estimate is founded, shall accompany each tender.

Quantities of the various Materials, and the Excavation necessary, for the erection of two Houses proposed to be built on a plot of ground situate

according to the various drawings (numbered from 1 to 17 inclusive) and specifications made for that purpose.

PRINCIPAL BUILDING—CARCASS.

EXCAVATOR.

Cube yards.		at		
		£	s.	d.
573	To be excavated and carted away . . . Levelling, filling-in, pugging, ramming, and carting away earth, rubbish, &c. . . .			

BRICKLAYER.

Rods.	Super.	Run.		at		
				£	s.	d.
		200	Of 6-inch glazed socket-pipes, with requisite bends . . .			
		200	Of 4-inch ditto . . .			
			No. 8 15-inch gully traps . .			
			No. 4 6-inch syphons . . .			
28	Of reduced or standard brick- work . . .			
	64	...	Of rubbed malm arches . . .			

CARPENTER.

Cube feet.	Super.	Run.		£	at s.	d.
25	Of English oak, for sleepers .			
925	18½ loads of Riga timber, framed in floors, partitions, roof, cisterns, &c., according to drawings and specifica- tion*			

* It perhaps is necessary to observe that this calculation embraces the net quantity of timber required for the erection of the carcass of the buildings, exclusive of any other article.

SMITH AND IRONFOUNDER.

Weight.		£	at s.	d.
1140	Hoop-iron bond			
160	Chimney bars			
110	Clips and straps for partitions			
1080	For tension rods, &c.			
187	For clips and straps to roof			
26	For bolts, &c.			
56	Ties to cistern, &c.			
2759 lbs. = 24 cwt. 71 lbs.				
Exclusive of all spikes, holdfasts, nails, screws, and every other article requisite for the sound fixing of the above-named works, which are to be calculated in the estimate.				

PLUMBER.

lbs. weight.		£	at s.	d.
900	Of 6-lb. lead, for flashings, &c.			
1728	Ditto, to dormer lights			
1320	5-lb. ditto, to sides of ditto			
1050	6-lb. flashings to lights and chimney, &c.			
145	ditto to cisterns			
5143 lbs. = 45 cwt. 3 lbs. weight of milled lead, exclu- sive of any other article.				

MASON.

Cube.	Super.	Run.		at		
				£	s.	d.
50	Of tooled steps for doors . . .			
			No. 8 15-inch gully-stones, properly dished, and five holes in each . . .			
	70	...	Of 5-inch York landing for rain-water tank . . .			
100	Of tooled York, for trimmers of floors, and heads, and sills of partitions, &c. . .			
		50	Of 12-inch \times 3-inch throated coping, for area walls, &c. .			
		36	Of stone core for cornice, 1 ft. 4 in. wide, 4 in. thick . .			
		60	Of dished and throated window-sills . . .			
	30	...	Of 6-inch rubbed York landing, for entrance porches . .			
50	No. 20 tooled and rubbed York steps, for entrance doors . .			
	36	...	Of 7-inch tooled landing . .			
		75	Of 2½-inch tooled treads, 13 in. wide, and . .			
		71	Ditto, for riser, 7 in. wide, for steps from back entrance of ground-floor to garden . .			

SLATER.

Square.		at		
		£	s.	d.
24½	Of Duchess slating, with all cuttings and pointings complete . . .			
	No. 12 slate cantilevers or brackets, for principal elevation—(See details of roof, Plate 21) . . .			
	No. 1 sawn slate filter, as shown and described on Plate 14, with all necessary bolts, nuts, screws, rods, perforated plates, &c., complete . . .			

ZINC WORKER.

Super.	Run.		at		
			£	s.	d.
	168	Of 6-inch gutter, worked and fixed as shown on details of roof, Plate 21 .			
		No. 6 octagon heads, with shoes, &c., complete			
	210	Of 4-inch piping, for down-corners, fixed complete			
	80	Of 3-inch ditto, for ditto of entrance-porches and bay windows			

Quantities of the various Materials requisite for finishing and completing the Carcasses of two Houses, before calculated for.

JOINER'S WORK.

Feet Super.	Feet Run.	No.	FLOORS.	at		
				£	s.	d.
1304	Or 13 square 4 feet of 1½-inch white floor-boards, laid folding in attic and part of basement stories			
3120	Or 31 square 20 feet yellow deal floor-boards, laid with a straight joint and splayed headings, for chamber, ground-floor, and part of basement stories			
			GROUND.			
	120	...	Of ¾-inch grounds 2-inch wide, faced and chamfered, for attic			
	250	...	Of 1-inch ditto, for chamber floor			
106	Of 1-inch splayed framed ground, 3¼-inch wide, for chamber floors			

JOINERS' WORK *continued.*

Feet Super.	Feet Run.	No.		£	s.	d.
	330	...	Of 1-inch × 2½-inch ploughed skirting grounds, for ground floor			
164	Of 1-inch ploughed and framed, and 5 inches wide, for door and windows (<i>see</i> plate 26)			
SASHES AND FRAMES.						
54	Of champhered and rebated lights, with frames and finishings made complete according to the specification			
VENETIAN WINDOWS — CHAMBER FLOOR.						
120	To front and back windows, with frames 1½-inch, oval sashes, lining, and all finishing complete, as shown on * the drawings and described in the specification . . .			
120	Ditto for back-parlour and kitchen windows, with sashes, frames, suspended shutters, and all finishings complete			
52	Of small frames, sashes, and finishings complete, for small windows, &c.			
DAY WINDOWS.						
390	Of frames, sashes, lining, soffit, and all other finishings complete, except the metal shutters			
390	With suspended shutters and finishings complete, for breakfast-room (<i>see</i> , for the finishings of these windows, plates 26 and 27, and specification)			

JOINERS' WORK *continued.*

Feet Super.	Feet Run.	No.		at		
				£	s.	d.
			JAMB-LININGS.			
60	Of 1-inch beaded linings, with stops braided on, for attic and part of basement story			
256	Of 1-inch beaded and single rebated ditto ditto.			
106	Of 1½-inch beaded and double rebated ditto ditto			
			DOOR-FRAMES, DOORS, AND FINISHINGS.			
75	Of 1½-inch two-panel square doors, for attics and part of basement			
280	Of ditto four-panel square doors, for ground-floor and part of basement			
188	Of 1½-inch four-panel, moulded on both sides, for ground-floor and breakfast-room			
95	For entrance-hall door-frames, transom-head, fan-light, doors, and finishings, all complete (<i>see</i> specification)			
126	For back or garden entrance, door-frame, sash-door, side-lights, fan-lights, boxing shutters, and all other finishings complete			
40	Of door frame, with 1½-inch four-bead and butt complete, for cellar			
40	Frame, with transom-head light and 1½-inch sash door, lifting shutters, and all other finishings complete			
			FRAMED PARTITIONS, WITH DOORS, COMPLETE.			
729	Of 1½-inch square panel, including 6 two-panel 1½-inch doors complete, for store-closet and pantries			
140	Ditto, sash-partition and doors,			

JOINERS' WORK *continued.*

Feet Super.	Feet Run.	No.		at £ s. d.
130	to divide stairs from lobby of garden entrance Of 1½-inch sash partition, to di- vide stairs from water-closet	
SKIRTINGS.				
160	Of ¾-inch skirting, six inches wide, for attic and part of basement floors	
220	Of 1-inch ditto moulded, for chamber floors	
270	Of 1-inch rebated ditto, for ground-floor and breakfast- room	
MOULDINGS.				
	210	...	Of 1½-inch, to form architrave over grounds, and pilaster in attic story	
	350	...	Of 2-inch, for chamber floor	
	280	...	Of 3½-inch, for ground-floors and breakfast-room . . .	
	120	...	Of 1½-inch, for basement	
WATER-CLOSET.				
112	Of mahogany seat and riser, dished to basin and handles	
32	Ditto mahogany-framed top, with moulded nosing, lining complete, and finished with skirting all round	
25	Of mahogany wash-stand, with closet and shelves, &c., un- derneath	
7	Of mahogany doors to ditto .	
	3	...	Feet run of ¾-inch skirting, six inches wide	
8	Of rebated and beaded maho- gany box, to cover service and supply pipes (See specification for these privies.)	

JOINERS' WORK *continued.*

Feet Super.	Feet Run.	No.		£	s.	d.
			STAIRS FROM KITCHEN TO GROUND-FLOOR.			
80	Of 1½-inch treads, properly blocked			
40	Of 1-inch risers			
to 40	Of 1½-inch string boards with bracket housings and carriage complete			
			GEOMETRICAL CIRCULAR WELL- STAIRS, FROM GROUND TO CHAMBER-FLOOR.			
936	Of 1½-inch yellow deal treads, risers, strings, and carriage; the risers mitred into external string, and treads moulded and mitred to return nosings, and the whole completed as shown on and described in specification			
		1	Blocked and veneered curtail step, with return to join external string			
	32	...	Of 2½-inch sunk mahogany moulded hand-rail, wreathed to circular well, as well as to curtail step, and to be mitred into a hand-work mahogany cap, with all bal- lusters complete to cham- ber landing, comprising the fixing of one ornamental bal- luster to curtail, and three plain ones on the flight . .			
			STAIRS FROM CHAMBER-FLOOR TO ATTIC-FLOOR.			
136	Of treads, risers, strings, and carriage complete (See plan and specification.)			

PLASTERERS' WORK.

Yards.	Superficial		Run.		£	at	
	Feet.					s.	d.
1018		Of lath, plaster, float and set to ceilings and partitions .			
484		Of render, float and set on walls			
		240		Of cornice, 10-inch girth .			
		188		Of ditto, 6-inch ditto .			
		236		Of ditto, 5-inch ditto .			
STAIRS.							
65		Of lath, plaster, and stucco, to hall, passage, and stairs .			
70		Of render, set and float in stucco, on walls, &c. .			
596		Of lime whitening .			
OUTSIDE WORK, IN ATKINSON CEMENT.							
		50		Of cornice, 5-inch girth, &c. .			
		50		Of ditto, 3-inch fillet, for chimney-top .			
	200	...		Of string-course, freize, avolo moulding, and sunk soffit, under eaves of front elevation .			
		10		Of sunk dentiles, to front elevation .			
	320	...		Of plain lathed and trowelled soffit, under eaves of sides and back elevation .			
PORCHES.							
4		Of lath and float, to ceilings .			
	46	...		Of cornice, on brickwork .			
	42	...		To caps and bases of pilasters			
	12	...		To bases of ditto .			
20		Of render, float, and jointed to spandrils of steps .			
9		Ditto, champhered and worked to steps (<i>see</i> plate 23) .			
BAY WINDOWS.							
3		With sunk joints to jambs .			
60		Plain work to top .			
	50	...		Of cornice .			
34		To front, rendered, floated, and sunk-jointed .			
47		Ditto, to area walls .			
		44		Of 6-inch string-course .			

MASON.

Feet Super.	No.		£	at s.	d.
10	...	Of 1-inch rubbed York stone, for chimney-pieces in attic . . .			
	4	Chimney-pieces for chamber-floors .			
	4	Ditto ditto for ground-floors .			
	2	Ditto ditto for basement-floors .			
397	...	Of 2½ tooled York, for paving to areas and cellars, including steps . .			

FURNISHING IRONMONGER.

No.		£	at s.	d.
ATTIC-FLOOR.				
8	¾-inch pivots, with patent cords, complete . .			
8	pair of brass-cased pulleys			
24	yards of patent sash-cord			
16	metal sash-weights			
8	2-inch spring sash-fastenings			
16	pair of 2½ butt hinge			
2	4-inch leaf spring latches			
2	4-inch iron closet locks			
4	6-inch mortice-locks, with furniture, complete .			
WATER-CLOSET.				
4	pair of 2½ butts			
2	4½-inch brass spring latches, complete . . .			
GROUND-FLOOR.				
12	brass-cased pulleys			
30	yards patent cord			
12	metal weights			
4	2-inch brass fastenings			
	revolving shutters, with all requisite finishing, to be estimated at so much each.			
ENTRANCE-HALL AND BACK ENTRANCE.				
8	pair of 4-inch butt hinges			
4	best 10-inch draw-back mounted spring-locks .			
4	12-inch door-chains, brass-mounted, with asp, and all complete			
4	10-inch barrel bolts			
4	18-inch bow-latch shutter-bolts			
4	3-inch brass spring-locks			

FURNISHING IRONMONGER *continued.*


SHUTTERS IN PARLOUR.		£	at	d.
No.			s.	
4	1-inch brass flush-rings			
4	brass clips for fastenings, with requisite pins			
8	pair of 3-inch butt hinges			
4	3-inch flush bolts			
6	6-inch mortice locks, with furniture, complete			
BASEMENT-STORY.				
10	pair of brass-cased pulleys			
30	yards patent cord			
20	metal weights			
2	6-inch mortice locks			
6	9-inch iron-rim locks, with furniture, complete			
12	10-inch barrel bolts, complete			
6	6-inch iron-rim locks, ditto			
24	pair of 3-inch butt hinges			
8	pair of 2½-inch ditto			
1	ornamental cast baluster			
3	plain ditto ditto, 2 ft. 6 in. high, ¾ in. × ⅝ in.			

BELL-HANGER. (*See specification.*)

PLUMBER.


Feet Run.		at		
		£	s.	d.
300	Of 1½-inch service-pipe to principal cistern, with fittings-up, complete			
140	Ditto of waste into water-closet			
100	Ditto to water-closet cistern and kitchen			
	To fit up, complete, two of Warner's patent water-closets, (<i>see specification</i>), and two single-valve closets, for secondary closets, in yard			
50	Of 1-inch service-pipe to the same			

PLATE II.

BLOCK PLAN OF GROUND,
SHOWING WATER TANK DRAINS &c.

0 10 20 30 40 50
SCALE OF FEET


A. RAIN WATER TANK.
B. PIPES TO D'S.
C. DRAIN TO SEWER.
D. TRAPS TO THE SAME.




SECTION OF GROUND: NOTE INVERTICAL TWICE THE SIZE OF THE HORIZONTAL

PLATE III.

BLOCK PLAN, SHOWING BUILDINGS, &c.


A. RAIN WATER
TANK.B.B. TRAPS.
C. AREA.

0 10 20 30 40 50 60 70 80 90 100
SCALE OF FEET





GROUND FLOOR PLANS




X V O X XX XXX
SCALE OF FEET



PLATE VI.

PLANS OF CHAMBER FLOOR.




X | | | | | | | | 0 X X X
 SCALE OF FEET



PLATE VII.

PLAN OF ATTICS.







PLATE VIII.

P

A. DOWNCOMERS
FROM GUTTER



X



0

PLATE IX.





PLATE X.

BACK ELEVATION.







PLATE XII.

TRANSVERSE SECTION OF CARCASS, SHOWING
FLUES AND POSITION OF STAIRS.



TRAPS FOR DRAINS.

FIG. I




FIG. II




FIG. III




FIG. IV



PLAN

FIG. V

SECTION




FIG. VI

SECTION



PLATE XIV.





FIG. I. SECTION OF RAIN WATER
TANK

FIG. II. PLAN OF CISTERN











DETAILS OF BRICKWORK.








DETAILS OF BRICKWORK FOR CHIMNIES



PLAN AND SECTION OF CHIMNEY BREAST AND TRIMMERS.









FIG. I.



PLAN OF
FLOOR JOISTS.





FIG. II.
SECTION OF
FIG. I

FIG. III.
PERSPECTIVE
SKETCH






FIG. IV.
TRANSVERSE TRUSSES TO -



- FLOOR JOIST


- A. JOIST
- B. TRUSS
- C. TENSION ROD

FIG. V.
FLOOR JOIST WITH SOUND BOARD-



- AND PUGING

- A. FLOOR BOARDS
- B. FLOOR JOISTS
- C. SOUND BOARDING
- D. FILLETS NAILED TO JOISTS
- E. PUGING.



SCALE OF FEET

PLATE XX.



FIG. I. SECTION OF PORTION OF ROOF
SHOWING THE WHOLE PRINCIPAL
RAFTER AT EACH HIP.

FIG. II. PLAN OF PORTION OF ROOF.



10 5 0 5 10
SCALE OF FEET

DETAILS OF ROOF..




FIG. IV. SIDE

FIG. - III.








PLATE XXII.

PLAN AND ELEVATION OF A PORTION
OF BAY WINDOW

0 1 2 3 4 5 6 7
SCALE OF FEET



NOTE. THE PARTS
REPRESENTED BLACK
INDICATE CEMENT

DETAILS OF ENTRANCE PORCH.








FIG. I. PLAN OF SIDE AND PILASTER.



FIG. II. PLAN OF SPANDRIL.






PLATE XXIV.


TRANSVERSE SECTION SHOWING
PARTITIONS FROM A. TO B. ON PLAN.



PLATE XXV.

SECTION SHOWING PARTITIONS
FROM C. TO D. ON PLANS.







FIG. I. FOR DOORS,
WINDOWS ATTIC,


DETAILS FOR
FINISHINGS
CHAMBER AND
ATTIC FLOOR.

FIG. II.
SKIRTING CHAMBER FLOORFIG. III. WINDOWS + DOORS, &
CHAMBER FLOORFIG. IV. WINDOW AND DOORS
BACK PARLOR, AND
BREAKFAST ROOM.

PLAN OF SASHES
AND FRAME.




DETAILS OF BAY WINDOW



- A. SASH FRAME
- B. METAL ANGULAR
- C. GROOVE FOR REVOLVING SHUTTERS
- D. GROOVE FOR D.

FIG. I. PORTION OF PLAN



CHAPTER VI.

INSTRUMENTS.

Having in Chapter V. endeavoured to explain the construction of such instruments as are used for the purpose of drawing lines, whether straight or curved, and hence producing geometrical figures, we will now proceed to explain the best form of protractors which are essential for laying down angles.

Protractors.

The edge of the semicircular is divided into 180 degrees, and subdivided to half degrees, or 30 minutes, and numbered for the convenience of plotting. Round the edge is carried a vernier, which subdivides the principal divisions into single minutes. The vernier is attached to an arm, forming a radius to the semicircle, which is extended beyond the circumference, and has on the extended part a fiducial edge, on which the angular line is to be drawn.

The centre of the instrument, which is visible from above, by the centre upon which the vernier radius moves, is a ring placed concentric with the centre. To use this instrument, it is only necessary

to set the vernier to the given angle, then place the protractors so that the fiducial edge may in every part exactly coincide with the line already given, and the centre with the given angular point. A line then being drawn along the fiducial edge will be the direction of the line forming the angle required; and upon moving the protractor, such line may be produced and connected with the angular point. In adjusting the fiducial edge upon the given line, so that the centre may exactly coincide with the given angular point, there is a certain degree of practical difficulty (*we are now alluding to whenever great accuracy is aimed at*).

It is not, therefore, essential, in setting the instrument, to have any regard to the given angular point, but only to set the edge nicely upon the given line; then, with a needle point, make three punctures in the paper, one near the extreme point, a second at the circumference of the arc, and the third as nearly as possible at the centre. The protractor may then be removed; and if all has been accurately performed, these three points will be in one straight line, which may be transferred to pass through the given angular point by straight edge or ruler.

The Circular Protractor.

* Is a complete circle, connected in its centre by four radii. Like the instrument last described, the centre is left open, and surrounded by a concentric ring or collar, which carries two radial bars. To the extremity of one bar is a pinion, working in a toothed rack, quite round

the outer circumference of the protractor. To the opposite extremity of the other bar is fixed a vernier, which subdivides the primary divisions on the protractor to single minutes,* and, by estimation, to 30 seconds. This vernier, as may readily be understood, is carried round the protractor by turning the pinion. Upon each radial bar is placed a branch, carrying at their extremities a fine steel pricker, whose points are kept above the surface of the papers by springs placed under their supports, which give way when the branches are pressed downwards, and allow the points to make the necessary punctures in the paper. The branches are attached to the bars with a joint, which admits of being folded backwards over the instrument when not in use, and for packing in its case.

The centre of the instrument is represented by the intersection of two lines, drawn at right angles to each other on a piece of glass, which enables the person using it to place it so that the centre, or intersection of the cross lines, may coincide with any given point on the plane. If the instrument is in correct order, a line, connecting the fine pricking points with each other, would pass through the centre of the instrument, as denoted by the before-mentioned intersection of the cross lines upon the glass, which, it may be observed, are drawn so nearly level with the under surface of the instrument, as to do away with any serious amount of parallax when setting the instrument over a point from which any angular lines are intended to be drawn.

In using this instrument, the vernier should first be set to *—zero (or the division marked 360)*, on the divided limb, and then placed on the paper, so that the two fine steel points may be on the given line (*from whence other and angular lines are to be drawn*), and the centre of the instrument coincides with the given angular point on such line. This done, press the protractor gently down, which will fix it in position by means of very fine points on the under sides. It is now ready to lay off the given angle, or any number of angles that may be required, which is done by turning the pinion till the opposite *vernier* reaches the required angle. Then press down the branches, which will cause the points to make punctures in the paper on opposite sides of the circle; which being afterwards connected, the line will pass through the given angular point, if the instrument was first correctly set. In this manner, at one setting of the instrument a great number of angles may be laid from the same point.

As described for the last instrument, it is not essential that the centre be over the given point when applied to the given line, provided the pricking points exactly fall upon the line; for an imaginary line, connecting the pricking points in this instrument, correspond with the line on the diameter of the protractor last described. Sometimes, instead of a rack and pinion motion, a third radial arm is attached to the centre at right angles to the other two, upon which is fixed a clamp and tangent screw, by which the vernier

is not only fixed in position upon the circular limb of the instrument, but by the tangent, or slow motion screw, it may be set to the required angle with the greatest accuracy.

Plain, Circular, and Semicircular Protractors.

Other and very useful protractors are made, consisting of a circle or semicircle, without verniers, slow-motion screws, or any other appendages, having simply a fiducial circular edge, nicely divided to degrees and half-degrees, or more minute subdivisions, if the instrument is sufficiently large to admit of them. A very useful instrument of this kind has a diameter of six inches, and will be found sufficiently accurate for most ordinary purposes, and not above one-third of the cost of the above-named instrument, which, however, must be resorted to when the utmost attainable accuracy is required.

The Plain Scale.

This instrument is usually made of ivory, 6 inches long, and $1\frac{1}{4}$ inches broad; it has on it two diagonal scales, one half the size of the other, on the same plane or face of the instrument, which, for distinction sake, we will call the upper side. These diagonal scales consist of eleven parallel lines, drawn equidistant from each other, and divided by vertical lines into equal parts of an inch long, and numbered from right to left—1, 2, 3, &c. The top and bottom lines of the extreme half-inch space to the right is sub-

divided into ten equal parts by diagonal lines drawn from the tenth below to the ninth above, from the ninth below to the eighth above, from the eighth below to the seventh above, &c., till from the first below to the nothing above, so that by these means the half-inch space is subdivided into 100 equal parts. Thus, if each of the first divisions of the half-inch spaces be considered to represent unity, each of the first divisions will express $\frac{1}{10}$ of 1, and each of the subdivisions taken on the diagonal lines, counting from the top downwards, will express $\frac{1}{10}$ of the last subdivisions, $\frac{1}{100}$ of the half-inch spaces (*or primary divisions*). If each of the half-inch spaces (*or primary divisions*) be considered as representing 10, then each of the first subdivisions will express 1 (*or unity*), and each of the second $\frac{1}{10}$ of unity. Again, if each of the primary divisions (*or half-inch spaces*) be considered to represent 100, then each of the first subdivisions will express 10, and each of the second subdivisions 1, or unity, &c., &c.

The method of taking distances from the scale may be thus shown:—Suppose the distance to be 347 on the diagonal, lined, joined to the 4th subdivision on the top line, count 7 downwards, reckoning the distance of each parallel as 1; there set one point of the compasses, and extend the other till it falls on the intersection of the third primary division with the same parallel in which the other point of the compasses rests, and their opening will then express a line of 347, 34·7, or 3·47, according as we may have con-

sidered the primary divisions to represent 100, 10, or unity.

The smaller diagonal scale is formed by dividing the half-inch space into two, and the further or left-hand quarter of an inch space is then diagonally divided as above described.

On the same or upper face of the instrument, a protractor is formed round its edges, and after what has been stated upon that instrument, nothing more than the mention of it is requisite in this place. On the under surface of the instrument a variety of scales are engraved, among which are the following:—

Line of Chords	marked	C or C H.
„ Rhombs	„	R H.
„ Tangents	„	T A.
„ Sines	„	S I.
„ Secants	„	S E C.
„ Longitudes	„	L O N.
„ Latitudes	„	L A.
„ Inclination of Meridians }	„	I M.
„ Hours	„	H O.

Besides scales having the following number of equal divisions to the inch :—30, 35, 45, 50, and 60.

The line of chords serves either to set off an angle from a given point to any line, or to measure the quantity of any angle already laid down. The first is done by opening the compasses to the extent of 60 degrees upon the line of chords (which is always equal to the radius, the circle of projection), and setting one foot upon the angular point; with that extent describe an

arc; then taking the angular quantity from the same chord line, set it off from the given line upon the arc described; a right line connecting the given point with that upon the arc will form the angle required. To measure an angle already laid down, describe as before an arc of 60 degrees; and then taking the extent with a pair of compasses between the lines which form the angle upon the said arc, the opening measured upon the same line of chords will denote the dimensions of the angle.

The line of rhombs serves to lay down or measure on a chart the angle of a ship's course in navigation.

The lines of tangents, sines, and secants, are used in the stereographical and orthographical projection of the sphere.

The line of longitudes, with the help of the line of chords, will show how many miles are contained in a degree of longitude at any latitude. Thus, with a pair of compasses take from the line of chords the number of degrees of the given latitude, and apply the opening of the compasses to the line of longitude, placing one point of the compasses on the last division, marked 60 on the longitudes, the other point will note upon the same line the number of miles in one degree of longitude at the given latitude. For example, if the given latitude be 60 degrees, take 60 from the line of chords, and applying one point of the compasses on the last division of the line of longitude (*marked 60*), the other point will fall upon the division marked 30 on the same line, showing that 30 miles is contained in one degree

of longitude at the latitude of 60 degrees. The lines of latitude, inclination of meridian, and of hours, are applicable to the practice of dialling, which does not fall within our present purpose.

Plotting Scales and Rules.

These need but few observations, as they are nothing more than scales of equal parts, the divisions being placed on a fiducial edge, by which any length may be pricked off on the paper without using the compasses, whose points, by frequent use, destroy the fineness of the graduation. Plotting scales are made of various dimensions, and of all varieties of graduation, to suit the purposes of the draftsman. Parallel rulers are also made of various constructions—some of them sliding, and others with rollers, each having its own advantages. The plain scale above described is frequently fitted with rollers, making it at the same time a convenient small parallel. The instrument shown in the engraving is so constructed and shown.

The Sector.

The sector derives its name from the fourth proposition of the sixth book of Euclid, where it is demonstrated that similar triangles have their like sides proportional.

This instrument consists of two rulers, moveable round an axis or joint, from whence several scales are drawn on the faces of the rulers.

The two rulers are called legs, and represent the

radii, and the middle of the joint expresses the centre of a circle.

The scales generally put upon sectors may be distinguished into single and double. The single scales are such as are commonly put on plain scales, and may be applied in the same manner. The double scales are those which proceed from the centre; each scale is laid twice on the same face of the instrument, namely, one on each leg. From these scales, dimensions or distances are to be taken, when the legs of the instrument are in an angular position.

The Decimal Scale.

This scale lies on the edge of the instrument, and is of the same length as the sector when opened (*one foot is the usual length for sectors placed in cases of instruments*), and is divided into 10 equal parts or primary divisions, and each of these into 10 other equal parts, so that the whole (foot) is divided into 100 equal parts.

The Line of Artificial Numbers.

The line of numbers (marked *N*), or Gunter's Line, as it is commonly called, is a line of geometrical proportion divided into nine unequal parts, beginning at 1 towards the left hand, and numbered on with 2, 3, 4, 5, &c., to 10, about the middle of the line, where another radius begins, and the same divisions are repeated, numbered as before to 10, at the end of the line on the right hand. Each of these primes, or first grand

divisions, are subdivided, according to the same ratio, into ten other parts, and each of these divisions (if the line be of sufficient length) should again be subdivided into ten lesser parts. But upon pocket sectors, which, when opened, are twelve inches in length, only the part from 1 in the middle to 2 towards the right hand is a second time divided, and that but into five parts instead of ten, every one of which must be accounted as two centesms in numbering; therefore, upon the line the figures 1, 2, 3, &c., which denote the primes, may be taken arbitrarily, either as units, tens, hundreds, or thousands, or thousandth parts of an unit.

If 1, at the beginning of the line, be taken for unity, then 1 in the middle will be 10, and 10 at the end 100; but if the first 1 be accounted 10, then 1 in the middle will stand for 100, and 10 at the end for 1000. Again, if the first 1 be reckoned 100, then 1 in the middle will be 1000, and 10 at the end 10,000.

When, therefore, the first, or prime, represents 10 units, the figures 2, 3, 4, &c. to 1 in the middle, will stand for 20, 30, 40, &c.; and each tenth, or subdivision in the first radius of the line, will signify 1 unit; and each centesm in those tenths (if *there be any*) will be one-tenth part of an unit; 1 in the middle will be (*as before observed*) 100; and the figures 2, 3, 4, &c. following, 200, 300, 400, &c.; each tenth, or subdivision in the second radius, will denote 10 units; and each centesm 1 unit. Again, let the first 1 represent 100, then the 2, 3, 4, &c. following, 200, 300, 400, &c.; 1 in the middle 1000; and 10 at the end 10,000. According

to this supposition, in the first, each tenth of a prime will be 10 units, and each centesim 1 unit; and in the second radius, each tenth of a prime 100, and each centesim 10.

In estimating decimal fractions upon the line, if 1 in the middle be accounted as unity, then will each prime in the first radius denote $\cdot 1$, each tenth of a prime $\cdot 01$, and each centesim $\cdot 001$. If 10 at the end of the line to the right hand be accounted as unity, the whole first radius will represent 1, and 2, 3, 4, &c., in the second radius will represent 2, 3, 4, &c.; every prime in the first radius, and every tenth of a prime in the second radius, will signify $\cdot 01$, or one hundredth part of unity, or centesim; in the second, will denote $\cdot 001$, or thousandth part of unity.

The numeration of the line thus explained, let it now be proposed to find the point thereon, answering to the number 436. For four hundred, take the first four primes next the left hand; for the second figure, 3, take three tenths of the grand division between 4 and 5; and for the six units, reckon six centesims, or six parts of the next tenth, so that the extent from 1 at the beginning of the line to that point, will express the number 436. The same point will likewise represent the numbers 43 \cdot 6, 4 \cdot 36, or 436; if the first be accordingly accounted 10, 1, or $\frac{1}{10}$ of unity.

To multiply upon the line, extend your compasses from 1 at the beginning, to the point representing the number of your multiplier. The same extent will

reach from the number of your multiplicand to the product. Thus, if 125 were given to be multiplied by 42, extend the compasses from 1 to 42, and the same extent will reach from 125 to 5250.

To divide upon the line, extend your compasses backwards from the numbers of the division to unity. The same extent, laid the same way, will reach from the number of the dividend to the quotient. Thus, if 5250 were to be divided by 125, extend the compasses backwards from 125 to unity; the same extent will reach the same way, from 5250 to 42.

The Lines of Artificial Sines and Tangents.

The line of artificial sines (*marked s*) consists only of the logarithms of the natural sines, transferred from a table of logarithms to the scale. They are numbered from the left to the right, with the figures 1, 2, 3, &c., to 10, which stands about the middle of the line; and so forward with 20, 30, 40, &c., to 90, at the end on the right. In the first part of the line, the grand divisions each represent one degree; so that if each prime be subdivided into twelve parts (*as they* are commonly called upon *sectors*), each subdivision will represent five minutes. In the latter part of the line, the grand divisions, which are each ten degrees, being subdivided into ten parts, each of them will signify five minutes. In the latter part of the line the grand divisions, which are each ten degrees, being subdivided

into ten parts, each of them will represent one degree; and according as they are again subdivided into four, three, or two parts, such second divisions contain fifteen, twenty, or thirty minutes each.

What has been stated of the line of sines, is likewise to be understood of the line of artificial tangents, (*marked t*), whose divisions begin also at 1, and run on to 10 in the middle of the line, signifying degrees. In the second part it runs on with 20, 30, &c., to 45, which stands at the end of the line; then returns back again to 90, where it began.

The use of these lines is in working proportions, whether arithmetical or geometrical, as well as in trigonometrical solutions. Thus, in all proportions, three terms are given to find a fourth. Seek out, therefore, the first term, whether number, sine, or tangent, on its proper line; and in that point set one foot of the compasses, and extend the other to the second or third term, whichever of them is of the same name as the first: the same extent laid from the other term the same way, will reach to the fourth term required.

Example.—As the sine of $52^{\circ}. 30'$: 85 :: radius, or the sine of 90° to the fourth number required.

Set one foot of the compasses in the line of artificial sines on $52^{\circ}. 30'$, and extend the other foot to 90° on that line; the same extent will reach from 85 on the line of numbers to 107, the fourth term required.

The Double Scales.

These consist of the line of lines, or of equal parts marked *L*; the line of chords marked *c*; the line of sines marked *s*; the line of secants also marked *s*, but placed on the reverse side of the sector; the line of polygons marked *Pol*; a line of tangents to 45° marked *t*; and also a second line of tangents from 45° to 75° . Each of these scales begins at the centre of the instrument, and is terminated near the other extremity of each leg; viz. the lines at 10, the chords at 60, the sines at 90° , and the tangents at 45° ; the remainder of the tangents, or those above 45° , are on other scales beginning at $\frac{1}{4}$ of the length of the former, counted from the centre, and marked with 45, and run to about 76 degrees.

The secants also begin at the same distance from the centre, where they are marked with 10, and are continued to as many degrees as the length of the sector will allow, which is about 75° .

The angles made by the double scales of lines of chords, of sines, and of tangents to 45 degrees, are always equal.

The angles made by the scales of upper tangents, and of secants, are also equal, and sometimes these angles are made equal to those made by the *other* double scales.

The scale of polygons is put near the inner edge of the legs; their beginning is not so far removed from

the centre as the 60 on the chords is. The beginning of this scale is marked 4, and from thence is figured towards the centre of the instrument to 12.

From this disposition of the double scales, it is plain that those angles which are equal to each other when the legs of the sector are close, will continue equal to each other at every opening of the instrument.

Method of using the Double Lines on the Sector.

When a measure is taken on any of the sectoral lines beginning at the centre, it is called a lateral distance; but when a measure is taken from any point on one line, to its corresponding point on the line of the same denomination on the other leg, it is called a transverse distance.

The divisions of each sectoral line are contained within three parallel lines, the innermost being the line on which the points of the compasses are to be placed, because this is the only line of the three which goes to the centre, and is therefore the sectoral line.

Line of Lines.

Multiplication.—With the compasses, take from any convenient distance from the scale of equal parts the length of one of the factors, and open the sector until the transverse distance between 10 and 10 is equal to it; then the transverse distance of the other factor (*measured upon the same scale of equal parts*) will represent the product.

Example.—Multiply 4 by 5, expand the compasses

from the centre of the sector to 4 on the primary divisions (*or take it from any other scale of equal parts*), and open the sector till this division becomes the transverse distance from 10 to 10 on the same divisions; then the transverse distance from 5 to 5 measured upon the same scale as the former, will equal 2 or 20, the answer.

Division.—Make the lateral distance of the dividend the transverse distance of the divisor; the transverse distance of 10 will be the quotient.

Example.—Divide 20 by 4. Make 20, taken from any convenient scale of equal parts, the transverse distance of 4, then the transverse of 10 (measured upon the same scale) will be 5, the answer.

It will readily be perceived for the multiplication or division of high numbers, aliquot parts of both factors must be taken, and the result multiplied by the same. The application of the sector to such common arithmetical operations is therefore very limited (*and of doubtful utility*).

Proportion.—Two lines being given to find a third proportional.

Example.—The given = 2 and 6, a third proportional required. Take between the compasses the lateral distance of the second term 6 (*either from the line of lines on the sector, or any convenient scale*), and open the sector until this distance becomes the transverse distance to the first term 2, then the transverse distance of the second term 6 measured upon the same scale as the former, will equal 18, the third proportional required.

If the legs of the sector will not open so far as to let the lateral distance of the second term fall between the divisions expressing the first term, then take $\frac{1}{2}$, $\frac{1}{3}$, $\frac{1}{4}$, or any aliquot part of the second term (*such* as will conveniently fall within the opening of the sector), and make such part the transverse distance of the first term; then, if the transverse distance of the second term be multiplied by the denominator of the part taken of the second term, the product will give the third proportional required. Thus, in the above example, take $\frac{1}{3}$ of 6 = 2, which make the transverse distance of 2 the first term; then the transverse distance of 6 the second term will be = 6, which multiplied by 3, will give 18, the answer.

Three lines being given to find a fourth proportional, open the sector until the lateral distance of the second term, or some aliquot part thereof, becomes the transverse section of the first term, or some aliquot part thereof, becomes the transverse distance of the first term; then the transverse distance of the third term will be the fourth proportional required, or such a sub-multiple thereof as was taken of the second term.

Example.—To find a fourth proportional to the numbers 2, 6 and 10.

Take this lateral distance of the second term 6 from any convenient scale of equal parts, and open the sector until that quantity, or any aliquot part thereof, becomes the transverse distance of the first term 2, then the transverse distance of the third term 10, taken from the same scale of equal parts will give 30, the fourth proportional required.

To diminish a Line in any Assigned Proportion.

Example.—Let it be required to diminish a line of 4 inches in the proportion of 8 to 7. Open the sector until the transverse distance of 8 is equal to a lateral distance of 7.

Mark the point where 4 inches will reach as a lateral distance taken from the centre, which will be in this case 6.86, and the transverse distance taken at the point will be 3 inches and a-half, the proportion required, that is, $8 : 7 :: 4 : 3\frac{1}{2}$.

We may remark, once for all, that in all problems with the sector, if any given line is too long for the legs of the instrument, take $\frac{1}{2}$, $\frac{1}{3}$, or $\frac{1}{4}$, &c. of it, and the result multiplied by 2, 3, or 4, will give the quantity required.

The use of the sector in reducing drawings may be thus shown:—Suppose a triangle was to be reduced to the proportion of 4 to 7.

Take the length of one side of the triangle in the compasses, and make it the transverse distance of 7 and 7; then take the transverse distance 4 and 4, which will be the length of the corresponding side of the reduced triangle. Next take the length of another side of the given triangles, and make the transverse distance of 7 and 7 as before. Then the transverse distance of 4 and 4 will be the length of the corresponding side of the reduced triangle, one point of the compasses being placed at the proper extremity of the first reduced line,

describe an arc with the length of the second line as *radius*. Lastly, the third side of the given triangle being made the transverse distance of 7 and 7, and that of 4 and 4 being taken, another arc intersecting the former one, described from the opposite end of the first reduced line, will give the point to be connected with each end of the first reduced line, and the triangle will be completed.

In the same manner, any right-lined figure, of how many sides soever, may be reduced in any given proportion or augmented by the same rule.

To divide a given line into any proposed number of equal parts :—

Make the length of the given line the transverse distance to the figures representing the number of parts required ; then the transverse distance of 1 and 1 will divide the given line as required.

Example.—Suppose a line to be divided into 9 equal parts, take the length of the given line in the compasses, and open the sector until it becomes the transverse distance between 9 and 9 ; then the transverse of 1 and 1 will be $\frac{1}{9}$ th part of the given line, or such a sub-multiple of the $\frac{1}{9}$ th part as was taken of the given line. Or the $\frac{1}{9}$ th part will be the difference between the given line and the transverse distance 8 and 8.

The latter of these methods is to be preferred when the parts required falls near the centre of the instrument.

To make the line of lines represent any scale of equal parts for drawing, plans, elevations, &c. Thus, sup-

pose a scale of one to five chains, or one inch to five feet were required. Take one inch in the compasses, and, by opening the sector, make it the transverse distances of 5 and 5, and then the transverse distance of any other corresponding points, as 6 and 6, $7\frac{1}{2}$ and $7\frac{1}{2}$ will be that number of chains, and links or feet, &c., to the scale required.

Line of Chords.

The double scales of chords upon the sectors are more generally useful than the single line of chords described on the plane scale: for, on the sector, the radius with which the arc is to be described may be of any length, between the transverse distance of 60 and of 60, when the legs are close, and that of the transverse of 60 and 60 when the legs are opened as far as the instrument will admit of. But with the chords on the plane scale, the arc described must be always of the same radius.

To protract or lay down a right-lined angle, which shall contain a given number of degrees, suppose 46° .

Case 1.—When the angles contain less than 60 degrees, make the transverse distance of 60 and 60 equal to the length of the radius of the circle, and with that opening describe an arc. Take the transverse distance of the given degrees 46, and lay this distance on the arc. From the centre of the arc, draw two lines, each passing through one extremity of the distance laid on the arc, and these two lines will contain the angle required.

Case 2.—When the angle contains more than 60 degrees. Suppose, for example, we wish to form an angle containing 148 degrees. Describe an arc, and make the transverse distance of $\frac{1}{2}$ or $\frac{1}{3}$, &c., of the given number of degrees, and lay this distance on the arc twice or thrice. Draw two lines connecting them, and they will form the angle required.

When the required angle contains less than 5 degrees, suppose $3\frac{1}{2}$, it will be better to proceed thus with the given radius, and from the centre describe an arc, and from a given point lay off the chord of 60° , which suppose to give the point A; and also from the first point lay off in the same direction the chord of $56\frac{1}{2}$ degrees ($=60^\circ - 3\frac{1}{2}^\circ$), which would give the point B; then through these two points draw lines to the point A, and they will represent the angle of $3\frac{1}{2}$ degrees, as required. From what has been stated about the protracting of an angle to contain a given number of degrees, it will easily be seen how to find the degrees or measure of an angle already laid down.

Line of Polygons.

The line of polygons is chiefly useful for the ready division of the circumference of a circle into any number of equal parts from 4 to 12, that is as a ready means to inscribe regular polygons of any given number of sides from 4 to 12, within a given circle. To which set off the radius of the given circle (which is always equal to the side of an inscribed hexagon), as the transverse distance of 6 and 6 upon

the line of polygons. Then the transverse distance of 6 and 6 upon the line of polygons. Then the transverse distance of 4 and 4 will be the side of a square; the transverse distance between 5 and 5, the side of a pentagon; between 7 and 7, the side of a heptagon; between 8 and 8 the side of an octagon; between 9 and 9, the side of a nonagon, &c.; all of which is too plain to require an example.

If it be required to form a polygon upon a given right line, set off the extent of the given line as a transverse distance between the points upon the lines of polygons, answering to the number of sides of which the polygon is to consist, as for a pentagon between 5 and 5, or for an octagon between 8 and 8; then the transverse distance between 6 and 6 will be the radius of a circle whose circumference would be divided by the given line into the number of sides required.

The line of polygons may likewise be used in describing, upon a given line, an isosceles triangle, whose angles at the base are each double that at the vertex. For, taking the given line between the compasses, open the sector, till the extent becomes the transverse distance of 10 and 10, then the transverse distance of 6 and 6 will be the length of each of the two equal sides of the isosceles triangle.

All such regular polygons, whose number of sides will exactly divide 360 (the number of degrees into which all *circles* are supposed to be divided) without a remainder, may likewise be set off upon the circumference of a circle by the line of chords. Thus, take

the radius of the circle between the compasses, and open the sector till that extent is the transverse distance between 60 and 60 upon the line of chords; then having divided 360 by the required number of sides, the transverse distance between the numbers of the quotient will be the side of the polygon required. Thus for an octagon, take the distance between 45 and 45; and for a polygon of 36 sides, take the distance between 10 and 10, &c.

Lines of Sines, Tangents, and Secants.

Given the radius of a circle (suppose to two inches); required the sine and tangent of $28^{\circ}.30'$ to the radius.

Open the sector so that the transverse distance of 90 and 90 on the sines, or of 45 and 45 on the tangents, may be equal to the given radius, viz. two inches; then will the transverse distance of $28^{\circ}.30'$, taken from the sines, be the length of that sine to the given radius; or if taken from the tangents, will be the length of that tangent to the given radius. But if the secant of $28^{\circ}.30'$ was required, make the given radius of two inches a transverse distance of 0 and 0, at the beginning of the line of secants, and then take the transverse distance of the degrees wanted, viz. $28^{\circ}.30'$.

A tangent greater than 45 degrees (suppose 60) is found thus:—

Make the given radius, suppose two inches, a transverse distance to 45, and 45 at the beginning of the scale of upper tangents, and then the required degrees (60) may be taken from the scale.

Given the length of the sine, tangent, or secant of any degrees, to find the length of the radius to that sine, tangent, or secant.

Make the given length a transverse distance to its given degrees on its respective scale. Then,

If a sine If a tangent under 45° If a tangent above 45° If a secant	} the trans- verse dis- tance of	$\left\{ \begin{array}{l} 90 \text{ and } 90 \text{ on the sines} \\ 45 \text{ and } 45 \text{ on the tangents} \\ 45 \text{ and } 45 \text{ on the upper tangents} \\ 0 \text{ and } 0 \text{ on secants} \end{array} \right\}$	will be the radius sought.
--	--	--	-------------------------------------

To find the length of a versed sine to a given number of degrees, and a given radius.

Make the transverse distance of 90 and 90 on the sine, equal to the given radius.

Take the transverse distance of the complement of the given number of degrees.

If the given number of degrees is less than 90, subtract the complement of the sine from the radius, the remainder will be the versed sine.

If the given number of degrees are more than 0, add the complement of the sine to the radius, and the sum will be the versed sine.

To open the legs of a sector, so that the corresponding double scale of lines, chords, sines, tangents, may make each a right angle.

On the line of lines, make the lateral distance 10, a transverse distance between 8 on one leg, and 6 on the other leg.

On the line of sines, make the lateral distance 90, a transverse distance 45 to 45; or from 40 to 50; or from 30 to 60; or from the sine of any degrees to their complement.

On the line of tangents, make the lateral distance of 45 a transverse distance between 30 and 30.

Having now endeavoured to describe the principal drawing instruments in general use, and the principal scales from which all others emanate, we propose at some future period to exemplify the simplicity of their application to all the trades engaged in the building art, accompanied by some useful diagrams and geometrical problems.

The Author is desirous of soliciting a favourable consideration for any unintentional errors that may have inadvertently been made; for, although every precaution has been taken to make the work correct, some inaccuracies will no doubt be found, and which are unavoidable in a work of this description.

THE END.

BLADEBURY AND EVANS, PRINTERS, WHITEFRIARS.

005707098

In 1 vol. 4to., with 74 plates, extra cloth boards and lettered, price 21s.,

THE CARPENTER'S NEW GUIDE :

OR,

THE BOOK OF LINES FOR CARPENTERS, GEOMETRICALLY EXPLAINED;

COMPRISING ALL THE ELEMENTARY PRINCIPLES ESSENTIAL FOR ACQUIRING A
KNOWLEDGE OF THE THEORY AND PRACTICE OF CARPENTRY.

A NEW EDITION,

FOUNDED ON THAT OF THE LATE PETER NICHOLSON'S STANDARD WORK;

REVISED BY

ARTHUR ASHPITEL, ARCHITECT, F.S.A., F.I.B.A.

JOHN WEALE'S NEW LIST OF WORKS

SUPPLEMENT TO THE PRECEDING WORK ON BRIDGES,

In large and thick 8vo. volume, uniform in half blue morocco, price 2l. 10s.

The volume comprises 68 Plates, consisting of Bridges of Stone, Viaducts, Iron Girder Bridges, Timber Bridges, and Mr. Tierney Clark's Suspension Bridge over the Danube, with every valuable detail; together with Text Description of the several subjects contained in this interesting volume.

With 72 Engravings, new, improved, and extended edition, price 2l. 12s. 6d.,
extra large 4to, extra cloth boards and lettered,

THE PRACTICAL RAILWAY ENGINEER :

EXAMPLES OF THE MECHANICAL AND ENGINEERING OPERATIONS AND STRUCTURES
COMBINED IN THE MAKING OF A RAILWAY.

By G. D. DEMPSEY, C.E.

CONTENTS.

- | | |
|---|---|
| Section I.—Curves, gradients, gauge, and slopes. | Section IV.—Retaining walls, bridges, tunnels, &c. |
| Section II.—Survey and levels for a railway—Parliamentary plan and section—Limits of deviation—Setting out the line—Working plans and sections—Computing quantities—Opening the ground. | Section V.—Permanent way and construction. |
| Section III.—Earthworks, cuttings, embankments, and drains. | Section VI.—Stations, &c. |
| | Section VII.—Rolling stock—Carriages, trucks, wheels, and axles—Brakes, and details—Locomotive engines and tenders. |
| | Section VIII.—Signals and electric telegraph. |

LIST OF PLATES.

- | | |
|---|--------------------------------------|
| 1. Cuttings. | 42. Ditto ditto, details. |
| 2, 3, 4. Earthworks, excavating. | 43. Ditto, spring-crossings, &c. |
| 5. Ditto, embanking. | 44. Ditto, turn-table. |
| 6. Ditto, waggons. | 45, 46. Terminal station. |
| 7. Drains under bridges. | 47, 48, 49. Stations. |
| 8. Brick and stone culverts. | 50. Goods stations. |
| 9. Paved crossings. | 51. Polygonal engine-house. |
| 10. Railway bridges, diagram. | 52. Engine-house. |
| 11, 12, 13, 14. Bridges, brick and stone. | 53. Watering apparatus.—(A). Tanks. |
| 15, 16. Ditto, iron. | 54. Ditto, (B.) Details of pumps. |
| 17, 18, 19, 20, 21. Ditto, timber. | 55. Ditto, (C.) Details of engines. |
| 22. Centers for bridges. | 56. Ditto, (D.) Cranes. |
| 23, 24, 25, 26, 27. "Pont de Montlouis." | 57. Hoisting machinery. |
| 28. "Pont du Cher." | 58. Ditto, details. |
| 29. Suspension bridge. | 59. Traversing platform. |
| 30. Box-girder bridge. | 60. Ditto, details. |
| 31. Trestle bridge and Chepstow bridge. | 61. Station-roof at King's Cross. |
| 32. Details of Chepstow bridge. | 62. Ditto, Liverpool. |
| 33. Crossotting, screw piling, &c. | 63. Ditto, Birmingham. |
| 34. Permanent way and rails. | 64, 65. Railway carriages. |
| 35. Ditto, chairs. | 66. Ditto, details. |
| 36. Ditto, fish-joints, &c. | 67, 68. Railways, trucks and wheels. |
| 37. Ditto, fish-joint chairs. | 69. Iron and covered waggons. |
| 38, 39. Ditto, cast-iron sleepers, &c. | 70. Details of cranes. |
| 40. Ditto, Stephenson's, Brunel's, Hemans's, Macneill's, and Dockray's. | 71. Wheels and details. |
| 41. Ditto, crossings. | 72. Portrait. |

JOHN WEALE'S NEW LIST OF WORKS.

In 1 Vol. 4to, extra cloth, boards and lettered, 67 Engravings, 21s.,

DESIGNS AND EXAMPLES OF COTTAGES, VILLAS, AND COUNTRY HOUSES;

BEING THE STUDIES OF SEVERAL EMINENT ARCHITECTS AND BUILDERS.

CONSISTING OF PLANS, ELEVATIONS, AND PERSPECTIVE VIEWS, WITH
APPROXIMATE ESTIMATES OF THE COST OF EACH.

In imperial 8vo., with 18 large folding Plates, extra cloth boards, price 12s.,

A PRACTICAL AND THEORETICAL ESSAY ON OBLIQUE BRIDGES.

By GEORGE WATSON BUCK, M.Inst. C.E.

TOGETHER WITH A

DESCRIPTION TO DIAGRAMS FOR FACILI- TATING THE CONSTRUCTION OF OBLIQUE BRIDGES.

By W. H. BARLOW, C.E.,

Second Edition, corrected and improved.

In 1 vol. 4to., 50 plates, with dimensions, extra cloth boards, price 21s.,

EXAMPLES FOR BUILDERS, CARPENTERS, AND JOINERS;

BEING WELL-SELECTED ILLUSTRATIONS OF RECENT MODERN ART AND CONSTRUCTION.

CONTENTS OF PLATES.

- | | |
|---|---|
| 1. Geometrical Staircase. | 26. Elizabethan terminations of a Shop front entablature. |
| 2. " " | 27. Joinery at Windsor Castle. |
| 3. " " | 28. " " |
| 4. " " | 29. " " |
| 5. " " | 30. " " |
| 6. Construction of the Wooden Columns in King's College. | 31. " " |
| 7. Details of do. | 32. Gate at the town entrance to the Royal Mews, Windsor. |
| 8. Plan and Elevation of the Athenæum Club House. | 33. Joinery at the Duke of Sutherland's, at Lillieshall. |
| 9. Do. do. Arthur's Club, St. James' Street. | 34. Mullions of Windows, do. |
| 10. Do. do. details. | 35. Plan and Elevation of a Public-house. |
| 11. Do. do. " | 36. Exeter Hall roof. |
| 12. Design for Verandah. | 37. Country mansion. |
| 13. Details of do. | 38. Italian Designs. |
| 14. Design for Verandah. | 39. " " |
| 15. Details of do. | 40. " " |
| 16. Design for Verandah. | 41. Longitudinal Section, do. |
| 17. Details of do. | 42. Windows, Doors, &c. do. |
| 18. Elevation of a Group of New Houses. | 43. Windows, &c. do. |
| 19. Joinery of Doors. | 44. Grand Staircase, do. |
| 20. Base, Subbase, and Dado. | 45. An Elegant Italian façade. |
| 21. Plan and Elevation of Doors. | 46. Penton Mensey Church, Bell Turret. |
| 22. Sections do. do. | 47. Plan and South Elevation of do. |
| 23. Section of the framing or frontispiece of an entablature of a Shop front. | 48. West Elevation of do. |
| 24. Roof at Charter House. | 49. Elevations, with horizontal and vertical sections of the Bell Turret, do. |
| 25. " Clerkenwell Ch. Pub. | 50. Transverse section of do. |

DRAWING BOOKS

For Students' use in Schools, Mechanics' Institutions, and others, desiring to acquire a superior method of Drawing and Shadowing, as practised in the best Schools of France.

COURS ELEMENTAIRES de LAVIS appliqué à L'ARCHITECTURE; folio volume, containing 50 elaborately engraved plates, in shadows and tints, very finely executed by the best artists of France, price 2*l.* 10*s.* *Paris.*

COURS ELEMENTAIRES de LAVIS appliqué à ORNEMENTATION; folio volume, containing 50 elaborately engraved plates, in shadows and tints, very finely executed by the best artists of France, price 2*l.* 10*s.* *Paris.*

ETUDES PROGRESSIVES ET COMPLETES D'ARCHITECTURE de Lavis par J. B. Tripon; large folio, 24 fine plates, comprising the Orders of Architecture, mouldings with profiles, ornaments, and forms of their proportion, art of shadowing, doors, balusters, parterres, &c. &c. &c., price 1*l.* 4*s.* *Paris.*

In 4to., with 14 plates, in half cloth, boards, price 7*s.* 6*d.*

PRACTICAL RULES ON DRAWING FOR THE OPERATIVE BUILDER AND YOUNG STUDENT in Architecture.

1. Practical Rules on Drawing, Outlines.
 2. Practical Rules on Drawing, the Grecian and Roman Orders.
 3. Practical Rules on Light and Shade.
 4. Practical Rules on Colour, &c. &c.
-

In 4to., boards, 8 plates, and 76 woodcuts, price 6*s.*

ARCHITECTURE OF MACHINERY. An Essay on Propriety of Form and Proportion. Intended as a guide to assist the Student in the Drawing and Designing of Machinery. For the use of Students and Schoolmasters.

MR. WEALE'S

NEW SERIES OF EDUCATIONAL WORKS.

I., II.

CONSTITUTIONAL HISTORY OF ENGLAND. 2 Vols. By
W. D. HAMILTON. 2s.

III., IV.

CONSTITUTIONAL HISTORY OF ENGLAND DOWN TO
VICTORIA. By W. D. HAMILTON. 2s.

V.

OUTLINES OF THE HISTORY OF GREECE, By E. LEVIEN,
M.A. Vol. I. 1s.

VI.

OUTLINES OF THE HISTORY OF GREECE, VOL. II,
TO ITS BECOMING A ROMAN PROVINCE. By E. LEVIEN, M.A. 1s. 6d.

VII.

OUTLINE HISTORY OF ROME. By E. LEVIEN, M.A. Vol. I.
1s.

VIII.

OUTLINE HISTORY OF ROME, VOL. II, TO THE
DECLINE. By E. LEVIEN. 1s. 6d.

IX., X.

A CHRONOLOGY OF CIVIL AND ECCLESIASTICAL
HISTORY, LITERATURE, ART, AND CIVILISATION, FROM THE
EARLIEST PERIOD TO 1855. 2 Vols. 2s. 6d.

XI.

GRAMMAR OF THE ENGLISH LANGUAGE, FOR USE
IN SCHOOLS AND FOR PRIVATE INSTRUCTION. By HYDE CLARKE,
D.C.L. 1s.

XII., XIII.

DICTIONARY OF THE ENGLISH LANGUAGE. A New
and Compressed Dictionary of the English Tongue, as Spoken and Written, in-
cluding above 100,000 Words, or 60,000 more than in any Existing Work, and
including 10,000 Additional Meanings of Old Words. By HYDE CLARKE, D.C.L.
3 Vols. in 1. 3s. 6d.

XIV.

GRAMMAR OF THE GREEK LANGUAGE. By H. C.
HAMILTON. 1s.

XV., XVI.

DICTIONARY OF THE GREEK AND ENGLISH LAN-
GUAGE. By H. R. HAMILTON. 2 Vols. in 1. 2s.

XVII., XVIII.

DICTIONARY OF THE ENGLISH AND GREEK LAN-
GUAGES. By H. R. HAMILTON. 2 Vols. in 1. 2s.

XIX.

GRAMMAR OF THE LATIN LANGUAGE. By T. GOODWIN,
of Greenwich. 1s.

XX., XXI.

DICTIONARY OF THE LATIN AND ENGLISH LAN-
GUAGES, by T. GOODWIN of Greenwich. Vol. I. 2s.

XXII., XXIII.

DICTIONARY OF THE ENGLISH AND LATIN LANGUAGES. By T. GOODWIN of Greenwich. Vol. II. 1s. 6d.

XXIV.

GRAMMAR OF THE FRENCH LANGUAGE. By DR. STRAUSS, late Lecturer at Besançon. 1s.

XXV.

DICTIONARY OF THE FRENCH AND ENGLISH LANGUAGES. By A. ELWES. Vol. I. 1s.

XXVI.

DICTIONARY OF THE ENGLISH AND FRENCH LANGUAGES. By A. ELWES. Vol. II. 1s. 6d.

XXVII.

GRAMMAR OF THE ITALIAN LANGUAGE. By A. ELWES. 1s.

XXVIII., XXIX.

DICTIONARY OF THE ITALIAN, ENGLISH, AND FRENCH LANGUAGES. By A. ELWES. Vol. I. 2s.

XXX., XXXI.

DICTIONARY OF THE ENGLISH, ITALIAN, AND FRENCH LANGUAGES. By A. ELWES. Vol. II. 2s.

XXXII., XXXIII.

DICTIONARY OF THE FRENCH, ITALIAN, AND ENGLISH LANGUAGES. By A. ELWES. Vol. III. 2s.

XXXIV.

GRAMMAR OF THE SPANISH LANGUAGE. By A. ELWES. 1s.

XXXV., XXXVI.

DICTIONARY OF THE SPANISH AND ENGLISH LANGUAGES. By A. ELWES. Vol. I. 2s.

XXXVII., XXXVIII.

DICTIONARY OF THE ENGLISH AND SPANISH LANGUAGES. By A. ELWES. Vol. II. 2s.

XXXIX.

GRAMMAR OF THE GERMAN LANGUAGE. By DR. STRAUSS. 1s.

XL.

CLASSICAL GERMAN READER, FROM THE BEST AUTHORS. 1s.

XLi., XLII., XLIII.

DICTIONARIES OF THE ENGLISH, GERMAN, AND FRENCH LANGUAGES. By N. E. HAMILTON. 3 Vols. 3s.

XLIV., XLV.

DICTIONARY OF THE HEBREW AND ENGLISH, AND ENGLISH AND HEBREW LANGUAGES, CONTAINING ALL THE BIBLICAL AND RABBINICAL WORDS. 3 Vols. (together with the Grammar, which may be had separately for 1s.) By DR. BRESSLAU, Hebrew Professor, 10s.

EDUCATIONAL WORKS.

THE SERIES OF EDUCATIONAL WORKS

ARE ON SALE IN TWO KINDS OF BINDING.

HAMILTON'S Outlines of the History of England, 4 vols. in 1, bound in cloth	5s.
———— Ditto, in half morocco, gilt, marbled edges	5s. 6d.
LEVIEN'S History of Greece, 2 vols. in 1, bound in cloth	3s. 6d.
———— Ditto, in half morocco, gilt, marbled edges	4s.
———— History of Rome, 2 vols. in 1, bound in cloth	3s. 6d.
———— Ditto, in half morocco, gilt, marbled edges	4s.
CHRONOLOGY of Civil and Ecclesiastical History, Literature, Art, &c., 2 vols. in 1, bound in cloth	(3s. 6d.
———— Ditto, in half morocco, gilt, marbled edges	4s.
CLARKE'S Dictionary of the English Language, bound in cloth	4s. 6d.
———— in half morocco, gilt, marbled edges	5s.
———— bound with Dr. Clarke's English Grammar, in cloth	5s. 6d.
———— Ditto, in half morocco, gilt, marbled edges	6s.
HAMILTON'S Greek and English and English and Greek Dictionary, 4 vols. in 1, bound in cloth	5s.
———— Ditto, in half morocco, gilt, marbled edges	5s. 6d.
———— Ditto, with the Greek Grammar, bound in cloth	6s.
———— Ditto, with Ditto, in half morocco, gilt, marbled edges	6s. 6d.
GOODWIN'S Latin and English and English and Latin Dictionary, 2 vols. in 1, bound in cloth	4s. 6d.
———— Ditto, in half morocco, gilt, marbled edges	5s.
———— Ditto, with the Latin Grammar, bound in cloth	5s. 6d.
———— Ditto, with Ditto, in half morocco, gilt, marbled edges	6s.
ELWES'S French and English and English and French Dictionary, 2 vols. in 1, in cloth	3s. 6d.
———— Ditto, in half morocco, gilt, marbled edges	4s.
———— Ditto, with the French Grammar, bound in cloth	4s. 6d.
———— Ditto, with ditto, in half morocco, gilt, marbled edges	5s.
FRENCH and English Phrase Book, or Vocabulary of all Conversational Words, elaborately set forth for Travelling Use, as a Self-Interpreter, bound	1s. 6d.
ELWES'S Italian, English, and French,—English, Italian, and French,—French, Italian, and English Dictionary, 3 vols. in 1, bound in cloth	7s. 6d.
———— Ditto, in half morocco, gilt, marbled edges	8s. 6d.
———— Ditto, with the Grammar, bound in embossed cloth, marbled edges	8s. 6d.
———— Ditto, with Ditto, in half morocco, gilt, marbled edges	9s.
ELWES'S Spanish and English and English and Spanish Dictionary, 4 vols. in 1, bound in cloth	5s.
———— Ditto, in half morocco, gilt, marbled edges	5s. 6d.
———— Ditto, with the Grammar, bound in cloth	6s.
———— Ditto, with Ditto, in half morocco, gilt, marbled edges	6s. 6d.
HAMILTON'S English, German, and French,—German, French, and English,—French, German, and English Dictionary, 3 vols. in 1, bound in cloth	4s.
———— Ditto, in half morocco, gilt, marbled edges	4s. 6d.
———— Ditto, with the Grammar, bound in embossed cloth, marbled edges	5s.
———— Ditto, with Ditto, in half morocco, gilt, marbled edges	5s. 6d.
BRESLAU'S Hebrew and English Dictionary, with the Grammar, 2 vols. in 1, bound in cloth	8s. 6d.
———— Ditto, 2 vols. in 1, in half morocco, 9s. 6d.—With vol. 3, English and Hebrew	12s. 6d.

MR. WEALE'S PUBLICATIONS FOR 1861.

RUDIMENTARY SERIES.

In demy 12mo, cloth, price 1s.
RUDIMENTARY.—1.—CHEMISTRY, by Professor FOWNES, F.R.S., including Agricultural Chemistry, for the Use of Farmers.

In demy 12mo, with Woodcuts, cloth, price 1s.
RUDIMENTARY.—2.—NATURAL PHILOSOPHY, by CHARLES TOMLINSON.

In demy 12mo, with Woodcuts, cloth, price 1s. 6d.
RUDIMENTARY.—3.—GEOLOGY, by Major-Gen. PORTLOCK, F.R.S. &c.

In demy 12mo, with Woodcuts, cloth, price 2s.
RUDIMENTARY.—4, 5.—MINERALOGY, with Mr. DANA'S Additions. 2 vols. in 1.

In demy 12mo, with Woodcuts, cloth, price 1s.
RUDIMENTARY.—6.—MECHANICS, by CHARLES TOMLINSON.

In demy 12mo, with Woodcuts, cloth, price 1s. 6d.
RUDIMENTARY.—7.—ELECTRICITY, by Sir WILLIAM SNOW HARRIS, F.R.S.

In demy 12mo, with Woodcuts, cloth, price 1s. 6d.
RUDIMENTARY.—7*.—ON GALVANISM; ANIMAL AND VOLTAIC ELECTRICITY; by Sir W. SNOW HARRIS.

In demy 12mo, with Woodcuts, cloth, price 3s. 6d.
RUDIMENTARY.—8, 9, 10 — MAGNETISM, Concise Exposition of, by Sir W. SNOW HARRIS, 3 vols. in 1.

In demy 12mo, with Woodcuts, cloth, price 2s.
RUDIMENTARY.—11, 11*.—ELECTRIC TELEGRAPH, History of the, by E. HIGHTON, C.E.

In demy 12mo, with Woodcuts, cloth, price 1s.
RUDIMENTARY.—12.—PNEUMATICS, by CHARLES TOMLINSON.

In demy 12mo, with Woodcuts, cloth, price 4s. 6d.
RUDIMENTARY.—13, 14, 15, 15*. — CIVIL ENGINEERING, by HENRY LAW, C.E., 3 vols.; and Supplement by G. R. BURNELL, C.E.

In demy 12mo, with Woodcuts, cloth, price 1s.
RUDIMENTARY.—16.—ARCHITECTURE, Orders of, by W. H. LEEDS.

In demy 12mo, with Woodcuts, cloth, price 1s. 6d.
RUDIMENTARY.—17.—ARCHITECTURE Styles of, by T. BURY, Architect.
John Weale, 59, High Holborn, London, W.C.

MR. WEALE'S RUDIMENTARY SERIES.

In demy 12mo, with Woodcuts, cloth, price 2s.
RUDIMENTARY.—18, 19.—ARCHITECTURE,
 Principles of Design in by E. L. GARBETT, Architect, 2 vols.
 in 1.

In demy 12mo, with Woodcuts, cloth, price 2s.
RUDIMENTARY.—20, 21.—PERSPECTIVE,
 by G. PYNE, Artist, 2 vols. in 1.

In demy 12mo, with Woodcuts, cloth, price 1s.
RUDIMENTARY.—22.—BUILDING, Art of,
 by E. DOBSON, C.E.

In demy 12mo, with Woodcuts, cloth, price 2s.
RUDIMENTARY.—23, 24.—BRICK-MAKING,
 TILE-MAKING, &c., Art of, by E. DOBSON, C.E., 2 vols.
 in 1.

In demy 12mo, with Woodcuts, cloth, price 2s.
RUDIMENTARY.—25, 26.—MASONRY AND
 STONE-CUTTING, Art of, by E. DOBSON, C.E., 2 vols.
 in 1.

In demy 12mo, with Woodcuts, cloth, price 2s.
RUDIMENTARY.—27, 28.—PAINTING, Art of,
 or a GRAMMAR OF COLOURING, by GEORGE FIELD,
 2 vols. in 1.

In demy 12mo, with Woodcuts, cloth, price 1s.
RUDIMENTARY.—29.—PRACTICE OF
 DRAINING DISTRICTS AND LANDS, Art of, by G. D.
 DEMPSEY, C.E.

In demy 12mo, with Woodcuts, cloth, price 1s. 6d.
RUDIMENTARY.—30.—PRACTICE OF
 DRAINING AND SEWAGE OF TOWNS AND BUILD-
 INGS, Art of, by G. D. DEMPSEY, C.E.

In demy 12mo, with Woodcuts, cloth, price 1s.
RUDIMENTARY.—31.—WELL-SINKING
 AND BORING, Art of, by G. R. BURNELL, C.E.

In demy 12mo, with Woodcuts, cloth, price 1s.
RUDIMENTARY.—32.—USE OF INSTRU-
 MENTS, Art of the, by J. F. HEATHER, M.A.

In demy 12mo, with Woodcuts, cloth, price 1s.
RUDIMENTARY.—33.—CONSTRUCTING
 CRANES, Art of, by J. GLYNN, F.R.S., C.E.

In demy 12mo, with Woodcuts, cloth, price 1s.
RUDIMENTARY.—34.—STEAM ENGINE,
 Treatise on the, by Dr. LARDNER.

In demy 12mo, with Woodcuts, cloth, price 1s.
RUDIMENTARY.—35.—BLASTING ROCKS
 AND QUARRYING, AND ON STONE, by Lieut.-Gen. Sir
 J. BURGOYNE HART, G.C.B., R.E.

In demy 12mo, with Woodcuts, cloth, price 4s.
RUDIMENTARY.—36, 37, 38, 39.—DICTION-
 ARY OF TERMS used by Architects, Builders, Civil and
 Mechanical Engineers, Surveyors, Artists, Ship-builders, &c.,
 vols. in 1.

In demy 12mo, cloth, price 1s.
RUDIMENTARY.—40.—GLASS STAINING
 Art of, by Dr. M. A. GESSERT.
 John Weale, 69, High Holborn, London, W.C.

MR. WEALE'S RUDIMENTARY SERIES.

In demy 12mo, cloth, price 1s.

RUDIMENTARY. — 41. — PAINTING ON GLASS, Essay on, by E. O. FROMBERG.

In demy 12mo, with Woodcuts, cloth, price 1s.

RUDIMENTARY. — 42. — COTTAGE BUILDING, Treatise on.

In demy 12mo, with Woodcuts, cloth, price 1s.

RUDIMENTARY. — 43. — TUBULAR AND GIRDER BRIDGES, and others, Treatise on, more particularly describing the Britannia and Conway Bridges.

In demy 12mo, with Woodcuts, cloth, price 1s.

RUDIMENTARY. — 44. — FOUNDATIONS, &c., by E. DOBSON, C.E.

In demy 12mo, with Woodcuts, cloth, price 1s.

RUDIMENTARY. — 45. — LIMES, CEMENTS, MORTARS, CONCRETE, MASTICS, &c., by G. R. BURNELL, C.E.

In demy 12mo, with Woodcuts, cloth, price 1s.

RUDIMENTARY. — 46. — CONSTRUCTING AND REPAIRING COMMON ROADS, by H. LAW, C.E.

In demy 12mo, with Woodcuts, cloth, price 3s.

RUDIMENTARY. — 47, 48, 49. — CONSTRUCTION AND ILLUMINATION OF LIGHTHOUSES, by ALAN STEVENSON, C.E., 3 vols. in 1.

In demy 12mo, with Woodcuts, cloth, price 1s.

RUDIMENTARY. — 50. — LAW OF CONTRACTS FOR WORKS AND SERVICES, by DAVID GIBBONS, S.P.

In demy 12mo, with Woodcuts, cloth, price 3s.

RUDIMENTARY. — 51, 52, 53. — NAVAL ARCHITECTURE, Principles of the Science, by J. PEAKE, N.A., 3 vols. in 1.

In demy 12mo, with Woodcuts, cloth, price 1s.

RUDIMENTARY AND ELEMENTARY. — 53*. — PRACTICAL CONSTRUCTION concisely stated of Ships for Ocean or River Service, by Captain H. A. SOMMERFELDT, N.R.N.

In royal 4to. with Engraved Plates, cloth, price 7s. 6d.

RUDIMENTARY. — 53. — ATLAS of 15 Plates** to ditto, drawn and engraved to a Scale for Practice.—For the convenience of the Operative Ship Builder the Atlas may be had in three separate Parts. Part I., 2s. 6d. Part II., 2s. 6d. Part III., 2s. 6d.

In demy 12mo, with Woodcuts, cloth, price 1s. 6d.

RUDIMENTARY. — 54. — MASTING, MAST-MAKING, AND RIGGING OF SHIPS, by R. KIPPING, A.

In demy 12mo, with Woodcuts, cloth, price 2s. 6d.

RUDIMENTARY. — 54*. — IRON SHIP BUILDING, by JOHN GRANTHAM, N.A. and C.E.

In demy 12mo, with Woodcuts, cloth, price 2s.

RUDIMENTARY. — 55, 56. — NAVIGATION; THE SAILOR'S SEA-BOOK.—How to Keep the Log and Work it Off—Latitude and Longitude—Great Circle Sailing—Law of Storms and variable Winds; and an Explanation of Terms used, with coloured Illustrations of Flags.

John Weale, 59, 111th Holborn, London, W.C.

MR. WEALE'S RUDIMENTARY SERIES.

In demy 12mo. with Woodcuts, cloth, price 2s.
RUDIMENTARY.—57, 58.—WARMING AND VENTILATION, by CHARLES TOMLINSON, 2 vols. in 1.

In demy 12mo. with Woodcuts, cloth, price 1s.
RUDIMENTARY.—59.—STEAM BOILERS, by R. ARMSTRONG, C.E.

In demy 12mo. with Woodcuts, cloth, price 2s.
RUDIMENTARY.—60, 61.—LAND AND ENGINEERING SURVEYING, by T. BAKER, C.E., 2 vols. in 1.

In demy 12mo. with Woodcuts, cloth, price 1s.
RUDIMENTARY AND ELEMENTARY.—62.—PRINCIPLES OF RAILWAYS, for the Use of the Beginner in his Studies; with Sketches for Construction. By Sir R. MACDONALD STEPHENSON. Vol. I.

In demy 12mo. with Woodcuts, cloth, price 1s.
RUDIMENTARY.—62*.—RAILWAY WORKING IN GREAT BRITAIN, Statistical Details, Table of Capital and Dividends, Revenues Accounts, Signals, &c., Vol. II.

In demy 12mo. with Woodcuts, cloth, price 3s.
RUDIMENTARY.—63, 64, 65.—AGRICULTURAL BUILDINGS, the Construction of, on Motive Powers, and the Machinery of the Steading; and on Agricultural Field Engines, Machines, and Implements, by G. H. ANDREWS, 3 vols in 1. —John Weale, 59, High Holborn, London, W.C.

In demy 12mo. cloth, price 1s.
RUDIMENTARY.—66.—CLAY LANDS AND LOAMY SOILS, by Professor JOHN DONALDSON, A.E.

In demy 12mo. with Woodcuts, cloth, price 3s.
RUDIMENTARY.—67, 68.—CLOCK AND WATCH-MAKING, AND ON CHURCH CLOCKS AND BELLS, by E. B. DENISON, M.A., 2 vols. in 1, considerably extended. Fourth Edition.

In demy 12mo. with Woodcuts, cloth, price 2s.
RUDIMENTARY.—69, 70.—MUSIC, Practical Treatise on, by C. C. SPENCER, Mus. Dr. 2 vols. in 1.

In demy 12mo. cloth, price 1s.
RUDIMENTARY.—71.—PIANOFORTE, Instruction for Playing the, by C. C. SPENCER, Mus. Dr.

In demy 12mo. with Steel Engravings and Woodcuts, cloth, price 5s. 6d.

RUDIMENTARY.—72, 73, 74, 75, 75*.—RECENT FOSSIL SHELLS (A Manual of the Mollusca), by SAMUEL P. WOODWARD, of the Brit. Mus. 4 vols. in 1, with Supplement.

In demy 12mo., with Woodcuts, cloth, price 2s.
RUDIMENTARY.—76, 77.—DESCRIPTIVE GEOMETRY, by J. F. HEATHER, M.A. 2 vols. in 1.

In demy 12mo. with Woodcuts, price 1s.
RUDIMENTARY.—77*.—ECONOMY OF FUEL, by T. S. PRIDEAUX.

In demy 12mo. 2 vols. in 1, with Woodcuts, cloth, price 2s.
RUDIMENTARY.—78, 79.—STEAM AS APPLIED TO GENERAL PURPOSES.
 John Weale, 59, High Holborn, London, W.C.

MR. WEALE'S RUDIMENTARY SERIES.

In demy 12mo, with Woodcuts, cloth, price 1s. 6d.

RUDIMENTARY.—78*.—LOCOMOTIVE ENGINE, by G. D. DEMPSEY, C.E.

In royal 4to, cloth, price 4s. 6d.

RUDIMENTARY.—79*.—ATLAS OF ENGRAVED PLATES to DEMPSEY'S LOCOMOTIVE ENGINES.

In demy 12mo, with Woodcuts, cloth, price 1s.

RUDIMENTARY.—79.—ON PHOTOGRAPHY**, the Composition and Properties of the Chemical Substances used, by Dr. H. HALLEUR.

In demy 12mo., with Woodcuts, cloth, price 2s. 6d.

RUDIMENTARY.—80, 81.—MARINE ENGINES AND ON THE SCREW, &c., by R. MURRAY, C.E. 2 vols. in 1.

In demy 12mo, cloth, price 2s.

RUDIMENTARY.—80*, 81*.—EMBANKING LANDS FROM THE SEA, by JOHN WIGGINS, F.G.S. 2 vols. in 1.

In demy 12mo, with Woodcuts, cloth, price 2s.

RUDIMENTARY.—82, 82*.—POWER OF WATER, AS APPLIED TO DRIVE FLOUR MILLS, by JOSEPH GLYNN, F.R.S., C.E.

In demy 12mo, cloth, price 1s.

RUDIMENTARY.—83.—BOOK-KEEPING, by JAMES HADDON, M.A.

In demy 12mo, with Woodcuts, price 3s.

RUDIMENTARY.—82, 83*, 83 (bis) COAL GAS**, on the Manufacture and Distribution of, by SAMUEL HUGHES, C.E.

In demy 12mo, with Woodcuts, cloth, price 3s.

RUDIMENTARY.—82*.—WATER WORKS FOR THE SUPPLY OF CITIES AND TOWNS**; Works which have been executed for procuring Supplies by means of Drainage Areas and by Pumping from Wells, by SAMUEL HUGHES, C.E.

In demy 12mo, with Woodcuts, cloth, price 1s. 6d.

RUDIMENTARY.—83.—CONSTRUCTION OF DOOR LOCKS.**

In demy 12mo, with Woodcuts, cloth, price 1s.

RUDIMENTARY.—83 (bis) — FORMS OF SHIPS AND BOATS, by W. BLAND, of Hartlip.

In demy 12mo, cloth, price 1s. 6d.

RUDIMENTARY.—84.—ARITHMETIC, with numerous Examples, by Prof. J. R. YOUNG.

In demy 12mo, cloth, price 1s. 6d.

RUDIMENTARY.—84*.—KEY to the above, by Prof. J. R. YOUNG.

In demy 12mo, cloth, price 1s.

RUDIMENTARY.—85.—EQUATIONAL ARITHMETIC, Questions of Interest, Annuities, &c., by W. HIPSLEY.

John Weale, 59, High Holborn, London, W.C.

MR. WEALE'S RUDIMENTARY SERIES.

In demy 12mo, cloth, price 1s.

RUDIMENTARY.—85*.—SUPPLEMENTARY
VOLUME TO HIPSLEY'S EQUATIONAL ARITHME-
TIC, Tables for the Calculation of Simple Interest, with Logarithms
for Compound Interest and Annuities, &c, &c., by W. HIPSLEY.

In demy 12mo, cloth, price 2s.

RUDIMENTARY.—86, 87.—ALGEBRA, by
JAMES HADDON, M.A. 2 vols. in 1.

In demy 12mo, in cloth, price 1s. 6d.

RUDIMENTARY.—86*, 87*.—ELEMENTS OF
ALGEBRA, Key to the, by Prof. YOUNG.

In demy 12mo, with Woodcuts, price 2s.

RUDIMENTARY.—88, 89.—ELEMENTS OF
GEOMETRY, by HENRY LAW, C.E. 2 vols. in 1.

In demy 12mo. with Woodcuts, cloth, price 1s.

RUDIMENTARY.—90.—GEOMETRY, ANA-
LYTICAL, by Prof. JAMES HANN.

In demy 12mo, with Woodcuts, cloth, price 2s.

RUDIMENTARY.—91, 92.—PLANE AND
SPHERICAL TRIGONOMETRY, by the same. 2 vols. in 1.

In demy 12mo, with Woodcuts, cloth, price 1s.

RUDIMENTARY.—93.—MENSURATION, by
T. BAKER, C.E.

In demy 12mo, cloth, price 2s. 6d.

RUDIMENTARY.—94, 95.—LOGARITHMS,
Tables for facilitating Astronomical, Nautical, Trigonometri-
cal, and Logarithmic Calculations, by H. LAW, C.E. New Edition,
with Tables of Natural Sines and Tangents, and Natural Cosines.
2 vols. in 1.

In demy 12mo, with Woodcuts, cloth, price 1s.

RUDIMENTARY.—96.—POPULAR ASTRO-
NOMY. By the Rev. ROBERT MAIN, M.R.A.S.

In demy 12mo, with Woodcuts, cloth, price 1s.

RUDIMENTARY.—97.—STATICS AND DY-
NAMICS, by T. BAKER, C.E.

In demy 12mo, with 220 Woodcuts, cloth, price 2s. 6d.

RUDIMENTARY.—98, 98*.—MECHANISM
AND PRACTICAL CONSTRUCTION OF MACHINES,
by T. BAKER, C.E., and ON TOOLS AND MACHINES, by
JAMES NASMYTH, C.E.

In demy 12mo, with Woodcuts, cloth, price 2s.

RUDIMENTARY.—99, 100.—NAUTICAL AS-
TRONOMY AND NAVIGATION, by Prof. YOUNG. 2
vols. in 1.

In demy 12mo, cloth, price 1s. 6d.

RUDIMENTARY.—100*.—NAVIGATION
TABLES, compiled for practical use with the above.

In demy 12mo, cloth, price 1s.

RUDIMENTARY.—101.—DIFFERENTIAL
CALCULUS, by Mr. WOOLHOUSE, F.R.A.S.
John Wente, 59, High Holborn, London, W.C.

MR. WEALE'S RUDIMENTARY SERIES.

In demy 12mo, cloth, price 1s. 6d.

RUDIMENTARY. — 101*. — WEIGHTS AND MEASURES OF ALL NATIONS: Weights, Coins, and the various Divisions of Time, with the principles which determine Rates of Exchange, by Mr. WOOLHOUSE, F.R.A.S.

In demy 12mo, in cloth, price 1s.

RUDIMENTARY. — 102. — INTEGRAL CALCULUS, by H. COX, M.A.

In demy 12mo, in cloth, price 1s.

RUDIMENTARY. — 103. — INTEGRAL CALCULUS. Examples of, by Prof. JAMES HANN.

In demy 12mo, cloth, price 1s.

RUDIMENTARY. — 104. — DIFFERENTIAL CALCULUS. Examples of, by J. HADDON, M.A.

In demy 12mo, with Woodcuts, cloth, price 1s. 6d.

RUDIMENTARY. — 105. — ALGEBRA, GEOMETRY, AND TRIGONOMETRY, Mnemonical Lessons, by the R.-v. T. PENYNGTON KIRKMAN, M.A.

In demy 12mo, with Woodcuts, cloth, price 1s. 6d.

RUDIMENTARY. — 106. — SHIPS' ANCHORS FOR ALL SERVICES, by Mr. GEORGE COTSELL, N.A.

In demy 12mo, with Woodcuts, price 2s. 6d.

RUDIMENTARY. — 107. — METROPOLITAN BUILDINGS ACT in present operation, with Notes, and the Act dated August 28th, 1860, for better supplying of Gas to the Metropolis.

In demy 12mo, cloth, price 1s. 6d.

RUDIMENTARY. — 108. — METROPOLITAN LOCAL MANAGEMENT ACTS. All the Acts.

In demy 12mo, cloth, price 1s. 6d.

RUDIMENTARY. — 109. — LIMITED LIABILITY AND PARTNERSHIP ACTS.

In demy 12mo, cloth, price 1s.

RUDIMENTARY. — 110. — SIX RECENT LEGISLATIVE ENACTMENTS, for Contractors, Merchants, and Tradesmen.

In demy 12mo, cloth, price 1s.

RUDIMENTARY. — 111. — NUISANCES REMOVAL AND DISEASE PREVENTION ACT.

In demy 12mo, cloth, price 1s. 6d.

RUDIMENTARY. — 112. — DOMESTIC MEDICINE, PRESERVING HEALTH, by M. RASPAIL.

In demy 12mo, cloth, price 1s. 6d.

RUDIMENTARY. — 113. — USE OF FIELD ARTILLERY ON SERVICE, by Lieut.-Col. HAMILTON MAXWELL, B.A.

In demy 12mo, with Woodcuts, cloth, price 1s. 6d.

RUDIMENTARY. — 114. — ON MACHINERY: Rudimentary and Elementary Principles of the Construction and on the Working of Machinery, by C. D. ABEL, C.E.

In royal 4to, cloth, price 7s. 6d.

RUDIMENTARY. — 115. — ATLAS OF PLATES OF SEVERAL KINDS OF MACHINES, 17 very valuable Illustrative plates.

John Weale, 59, High Holborn, London, W.C.

MR. WEALE'S RUDIMENTARY SERIES.

In demy 12mo, with Woodcuts, cloth, price 1s. 6d.

RUDIMENTARY. — 116. — TREATISE ON ACOUSTICS: The Distribution of Sound, by T. ROGER SMITH, Architect.

In demy 12mo, with Woodcuts, cloth, price 2s. 6d.

RUDIMENTARY. — 117. — SUBTERRANEAN SURVEYING, RANGING THE LINE WITHOUT THE MAGNET. By THOMAS FENWICK, Coal Viewer. With Improvements and Modern Additions by T. BAKER, C.E.

In demy 12mo, with Plates and Woodcuts, cloth, price 3s.

RUDIMENTARY. — 118, 119. — ON THE CIVIL ENGINEERING OF NORTH AMERICA, by D. STEVENSON, C.E. 2 vols. in 1.

In demy 12mo, with Woodcuts, cloth, price 3s.

RUDIMENTARY. — 120. — ON HYDRAULIC ENGINEERING, by G. R. BURNELL, C.E. 2 vols. in 1.

In demy 12mo, with 2 Engraved Plates, cloth, price 1s. 6d.

RUDIMENTARY. — 121. — TREATISE ON RIVERS AND TORRENTS, from the Italian of PAUL FRISI.

In demy 12mo, by PAUL FRISI, in cloth, price 1s.

RUDIMENTARY. — 122. — ON RIVERS THAT CARRY SAND AND MUD, and an ESSAY ON NAVIGABLE CANALS. 121 and 122 bound together, 2s. 6d.

In demy 12mo, with Woodcuts, cloth, price 1s. 6d.

RUDIMENTARY. — 123. — ON CARPENTRY AND JOINERY, founded on Dr. Robtson's Work.

In demy 4to, cloth, price 4s. 6d.

RUDIMENTARY. — 123*. — ATLAS of PLATES in detail to the CARPENTRY AND JOINERY. 123 and 123* bound together in cloth in 1 vol.

In demy 12mo, with Woodcuts, cloth, price 1s. 6d.

RUDIMENTARY. — 124. — ON ROOFS FOR PUBLIC AND PRIVATE BUILDINGS, founded on Dr. Robtson's Work.

In roy-1 4to, cloth, price 4s. 6l.

RUDIMENTARY. — 124*. — RECENTLY CONSTRUCTED IRON ROOFS, Atlas of plates.

In demy 12mo, with Woodcuts, cloth, price 3s.

RUDIMENTARY. — 125. — ON THE COMBUSTION OF COAL AND THE PREVENTION OF SMOKE, Chemically and Practically Considered, by CHARLES WYE WILLIAMS.

In demy 12mo, cloth. 125 and 126 together, price 3s.

RUDIMENTARY. — 126. — ILLUSTRATIONS to WILLIAMS'S COMBUSTION OF COAL. 125 and 126, 2 vols. bound in 1.

In demy 12mo, with Woodcuts, cloth, price 1s. 6d.

RUDIMENTARY. — 127. — PRACTICAL INSTRUCTIONS IN THE ART OF ARCHITECTURAL MODELLING.

John Weale, 59, High Holborn, London, W.C.

MR. WEALE'S RUDIMENTARY SERIES.

In demy 12mo, with Engravings and Woodcuts.

RUDIMENTARY.—128.—THE TEN BOOKS OF M. VITRUVIUS ON CIVIL, MILITARY, AND NAVAL ARCHITECTURE, translated by JOSEPH GWILT, Arch. 2 vols. in 1.

In demy 12mo, 128 and 129 together, cloth, price 5s.

RUDIMENTARY.—129.—ILLUSTRATIVE PLATES TO VITRUVIUS'S TEN BOOKS, by the Author and JOSEPH GANDY, R.A.

In demy 12mo, cloth, price 1s.

RUDIMENTARY.—130.—INQUIRY INTO THE PRINCIPLES OF BEAUTY IN GRECIAN ARCHITECTURE, by the Right Hon. the Earl of ABERDEEN, &c. &c.

In demy 12mo, cloth, price 1s.

RUDIMENTARY.—131.—THE MILLER'S, MERCHANT'S, AND FARMER'S READY RECKONER, for ascertaining at Sight the Value of any quantity of Corn; together with the approximate value of Millstones and Millwork.

In demy 12mo, with Woodcuts, cloth, price 2s. 6d.

RUDIMENTARY.—132.—TREATISE ON THE ERECTION OF DWELLING HOUSES, WITH SPECIFICATIONS, QUANTITIES OF THE VARIOUS MATERIALS, &c., by S. H. BROOKS, Architect. 27 Plates.

RUDIMENTARY SERIES.—ON MINES, SMELTING WORKS, AND THE MANUFACTURE OF METALS, as follows.

In demy 12mo, with Woodcuts, cloth, price 2s.

RUDIMENTARY.—Vol. 1.—TREATISE ON THE METALLURGY OF COPPER, by R. H. LAMBORN.

In demy 12mo, to have Woodcuts, cloth.

RUDIMENTARY.—Vol. 2.—TREATISE ON THE METALLURGY OF SILVER AND LEAD.

In demy 12mo, to have Woodcuts, cloth.

RUDIMENTARY AND ELEMENTARY.—Vol. 3.—TREATISE ON IRON METALLURGY up to the Manufacture of the latest processes.

In demy 12mo, to have Woodcuts, cloth.

RUDIMENTARY AND ELEMENTARY.—Vol. 4.—TREATISE ON GOLD MINING AND ASSAYING PLATINUM, IRIIDIUM, &c.

In demy 12mo, to have Woodcuts, cloth.

RUDIMENTARY AND ELEMENTARY.—Vol. 5.—TREATISE ON THE MINING OF ZINC, TIN, NICKEL, COBALT, &c.

In demy 12mo, to have Woodcuts, cloth.

RUDIMENTARY AND ELEMENTARY.—Vol. 6.—TREATISE ON COAL MINING (Geology and Means of Discovering, &c.)

In demy 12mo, with Woodcuts, cloth, price 1s. 6d.

RUDIMENTARY.—Vol. 7.—ELECTRO-METALLURGY.—Practically treated by ALEXANDER WATT, F.R.S.A.

John Weale, 59, High Holborn, London, W.C.

NEW SERIES OF EDUCATIONAL WORKS.

In demy 12mo, with Woodcuts, cloth, price 4s.
ONSTITUTIONAL HISTORY OF ENGLAND.—1, 2, 3, 4.—By W. D. HAMILTON, of the State P. O.

In demy 12mo, with Woodcuts, cloth, price 2s. 6d.
OUTLINES OF THE HISTORY OF GREECE.
 —5, 6.—By W. D. HAMILTON, 2 vols.

In demy 12mo, with Map of Italy and Woodcuts, cloth, price 2s. 6d.
OUTLINE OF THE HISTORY OF ROME.—
 7, 8.—By W. D. HAMILTON, 2 vols.

In demy 12mo, cloth, price 2s. 6l.
CHRONOLOGY OF CIVIL AND ECCLESIASTICAL HISTORY, LITERATURE, ART, AND CIVILISATION, from the earliest period to the present.—9, 10.—2 vols.

In demy 12mo, cloth, price 1s.
GRAMMAR OF THE ENGLISH LANGUAGE.
 —11.—By HYDE CLARKE, D.C.L.

In demy 12mo, cloth, price 1s.
HANDBOOK OF COMPARATIVE PHILOLOGY.—11*.—By HYDE CLARKE, D.C.L.

In demy stout 12mo, cloth, price 3s. 6d.
DICTIONARY OF THE ENGLISH LANGUAGE.—12, 13.—A New Dictionary of the English Tongue as spoken and written, above 100,000 words, or 50,000 more than in any existing work, by HYDE CLARKE, D.C.L., 3 vols. in 1.

In demy 12mo, cloth, price 1s.
GRAMMAR OF THE GREEK LANGUAGE.
 —14.—By H. C. HAMILTON.

In demy 12mo, cloth, price 2s.
DICTIONARY OF THE GREEK AND ENGLISH LANGUAGES.—15, 16.—By H. R. HAMILTON, 2 vols. in 1.

In demy 12mo, cloth, price 2s.
DICTIONARY OF THE ENGLISH AND GREEK LANGUAGES.—17, 18.—By H. R. HAMILTON, 2 vols. in 1.

In demy 12mo, cloth, price 1s.
GRAMMAR OF THE LATIN LANGUAGE.
 —19.—By the Rev. T. GOODWIN, A.B.

In demy 12mo, cloth, price 2s.
DICTIONARY OF THE LATIN AND ENGLISH LANGUAGES.—20, 21.—By the Rev. T. GOODWIN, A.B. Vol. 1.

In demy 12mo, cloth, price 1s. 6d.
DICTIONARY OF THE ENGLISH AND LATIN LANGUAGES.—22, 23.—By the Rev. T. GOODWIN, A.B. Vol. II.

In demy 12mo, cloth, price 1s.
GRAMMAR OF THE FRENCH LANGUAGE.
 —24.

John Weale, 59, High Holborn, London, W.C.

MR. WEALE'S EDUCATIONAL SERIES.

In demy 12mo, cloth, price 1s.
DICTIONARY OF THE FRENCH AND
ENGLISH LANGUAGES.—26.—By A. ELWES. Vol. I.

In demy 12mo, cloth, price 1s. 6d.
DICTIONARY OF THE ENGLISH AND
FRENCH LANGUAGES.—26.—By A. ELWES. Vol. II.

In demy 12mo, cloth, price 1s.
GRAMMAR OF THE ITALIAN LANGUAGE
—27.—By A. ELWES.

In demy 12mo, cloth, price 2s.
DICTIONARY OF THE ITALIAN, ENG-
LISH, AND FRENCH LANGUAGES.—28, 29.—By A.
ELWES. Vol. I.

In demy 12mo, cloth, price 2s.
DICTIONARY OF THE ENGLISH, ITALIAN,
AND FRENCH LANGUAGES.—30, 31.—By A. ELWES.
Vol. II.

In demy 12mo, cloth, price 2s.
DICTIONARY OF THE FRENCH, ITALIAN,
AND ENGLISH LANGUAGES.—32, 33.—By A. ELWES.
Vol. III.

In demy 12mo, cloth, price 1s.
GRAMMAR OF THE SPANISH LANGUAGE.
—34.—By A. ELWES.

In demy 12mo, cloth, price 4s.
DICTIONARY OF THE SPANISH AND
ENGLISH LANGUAGES.—35, 36, 37, 38.—By A. ELWES.
4 vols. in 1.

In demy 12mo, cloth, price 1s.
GRAMMAR OF THE GERMAN LANGUAGE.
—39.

In demy 12mo, cloth, price 1s.
CLASSICAL GERMAN READER.—40.—From
the best Authors.

In demy 12mo, cloth, price 3s.
DICTIONARIES OF THE ENGLISH, GER-
MAN, AND FRENCH LANGUAGES.—41, 42, 43.—By N.
E. HAMILTON, 3 vols., separately, 1s. each.

In demy 12mo, cloth, price 7s.
DICTIONARY OF THE HEBREW AND
ENGLISH LANGUAGES.—44, 45.—Containing the Biblical
and Rabbinical words, 2 vols. (together with the Grammar, which
may be had separately for 1s.), by Dr. BRESSLAU, Hebrew Pro-
fessor.

In demy 12mo, cloth, price 3s.
DICTIONARY OF THE ENGLISH AND
HEBREW LANGUAGES.—46.—Vol. III. to complete.

In demy 12mo, cloth, price 1s.
FRENCH AND ENGLISH PHRASE BOOK.
—47.

John Weale, 59, High Holborn, London, W.C.

MR. WEALE'S CLASSICAL SERIES.

Now in course of Publication, in demy 12mo, price 1s. per Volume (except in some instances, and those are 1s. 6d. or 2s. each), very neatly printed on good paper. Those priced are published.

GREEK AND LATIN CLASSICS.—A Series of Volumes containing the principal Greek and Latin Authors, accompanied by Explanatory Notes in English, principally selected from the best and most recent German Commentators, and comprising all those Works that are essential for the Scholar and the Pupil, and applicable for the Universities of Oxford, Cambridge, Edinburgh, Glasgow, Aberdeen, and Dublin—the Colleges at Belfast, Cork, Galway, Winchester, and Eton, and the great Schools at Harrow, Rugby, &c.—also for Private Tuition and Instruction, and for the Library, as follows:

LATIN SERIES.

In demy 12mo, boards, price 1s.

A NEW LATIN DELECTUS.—1.—Extracts from Classical Authors, with Vocabularies and Explanatory Notes.

In demy 12mo, boards, price 2s.

CÆSAR'S COMMENTARIES ON THE GAL-LIC WAR.—2.—With Grammatical and Explanatory Notes in English, and a Geographical Index.

In demy 12mo, boards, price 1s.

CORNELIUS NEPOS.—3.—With English Notes, &c.

In demy 12mo, boards, price 1s.

VIRGIL.—4.—The Georgics, Bucolics, with English Notes.

In demy 12mo, boards, price 2s.

VIRGIL'S ÆNEID.—5.—(On the same plan as the preceding).

In demy 12mo, boards, price 1s.

HORACE.—6.—Odes and Epodes; with English Notes, and Analysis and Explanation of the Metres.

In demy 12mo, boards, price 1s. 6d.

HORACE.—7.—Satires and Epistles, with English Notes, &c.

In demy 12mo, boards, price 1s. 6d.

SALLUST.—8.—Conspiracy of Catiline, Jugurthine War, with English Notes.

In demy 12mo, boards, price 1s. 6d.

TERENCE.—9.—*Andria* and *Heautontimorumenos*, with English Notes.

In demy 12mo, boards, price 2s.

TERENCE.—10.—*Phormio*, *Adelphi*, and *Hecyra*, with English Notes.

In demy 12mo.

CICERO.—11.—Orations against Catiline, for Sulla, for Archias, and for the Manilian Law.

In demy 12mo.

CICERO.—12.—First and Second Philippics; Orations for Milo, for Marcellus, &c.
John Weale, 59, High Holborn London, W.C.

MR. WEALE'S CLASSICAL SERIES.

CICERO.—13.—*De Officiis.*
In demy 12mo.

CICERO.—14.—*De Amicitia, de Senectute, and Brutus, with English Notes.*
In demy 12mo, boards, price 2s.

JUVENAL AND PERSIUS.—15.—(The indelicate parts expunged.)
In demy 12mo.

LIVY.—16.—Books i. to v. in two vols., with English Notes.
In demy 12mo, boards, price 3s.

LIVY.—17.—Books xxi. and xxii., with English Notes.
In demy 12mo, boards, price 1s.

TACITUS.—18.—*Agricola; Germania; and Annals, Book i.*
In demy 12mo.

SELECTIONS FROM TIBULLUS, OVID, and PROPERTIUS.—19.—With English Notes,
In demy 12mo, boards, price 2s.

SELECTIONS FROM SUETONIUS and the later Latin Writers.—20.
In demy 12mo.

GREEK SERIES, ON A SIMILAR PLAN TO THE LATIN SERIES.

Those not priced are in the Press.

INTRODUCTORY GREEK READER.—1.—
On the same plan as the Latin Reader.
In demy 12mo, boards, price 1s.

XENOPHON.—2.—*Anabasis, i. ii. iii., with English Notes.*
In demy 12mo, boards, price 1s.

XENOPHON.—3.—*Anabasis, iv. v. vi. vii., with English Notes.*
In demy 12mo, boards, price 1s.

LUCIAN.—4.—*Select Dialogues, with English Notes.*
In demy 12mo, boards, price 1s.

HOMER.—5.—*Iliad, i. to vi., with English Notes.*
In demy 12mo, boards, price 1s. 6d.

HOMER.—6.—*Iliad, vii. to xii., with English Notes.*
In demy 12mo, boards, price 1s. 6d.

HOMER.—7.—*Iliad, xiii. to xviii. with English Notes.*
In demy 12mo, boards, price 1s. 6d.

HOMER.—8.—*Iliad, xix. to xxiv., with English Notes.*
In demy 12mo, boards, price 1s. 6d.

John Weale, 59, High Holborn, London, W.C.

MR. WEALE'S CLASSICAL SERIES.

In demy 12mo, boards, price 1s. 6d.

HOMER.—9.—*Odyssey, i. to vi., with English Notes.*

In demy 12mo, boards, price 1s. 6d.

HOMER.—10.—*Odyssey, vii. to xii., with English Notes.*

In demy 12mo, boards, price 1s. 6d.

HOMER.—11.—*Odyssey, xiii. to xviii. with English Notes.*

In demy 12mo, boards, price 1s. 6d.

HOMER.—12.—*Odyssey, xix. to xxiv.; and Hymns, with English Notes.*

In demy 12mo, boards, price 2s.

PLATO.—13.—*Apology, Crito, and Phædo, with English Notes.*

In demy 12mo, boards, price 1s. 6d.

HERODOTUS.—14.—i. ii., with English Notes.—
Dedicated to His Grace the Duke of Devonshire.

In demy 12mo, boards, price 1s. 6d.

HERODOTUS.—15.—iii. iv., with English Notes.
Dedicated to His Grace the Duke of Devonshire.

In demy 12mo.

HERODOTUS.—16.—v. vi. and part of vii.
Dedicated to His Grace the Duke of Devonshire.

In demy 12mo.

HERODOTUS.—17.—*Remainder of vii., viii., and ix. Dedicated to His Grace the Duke of Devonshire.*

In demy 12mo, boards, price 1s.

SOPHOCLES.—18.—*Œdipus Rex, with English Notes.*

In demy 12mo.

SOPHOCLES.—19.—*Œdipus Colonæus.*

In demy 12mo.

SOPHOCLES.—20.—*Antigone.*

In demy 12mo.

SOPHOCLES.—21.—*Ajax.*

In demy 12mo.

SOPHOCLES.—22.—*Philoctetes.*

In demy 12mo, boards, price 1s. 6d.

EURIPIDES.—23.—*Hecuba, with English Notes.*

In demy 12mo.

EURIPIDES.—24.—*Medea.*

In demy 12mo.

EURIPIDES.—25.—*Hippolytus.*

John Weale, 59, High Holborn, London, W.C.

MR. WEALE'S CLASSICAL SERIES.

In demy 12mo, boards, price 1s.

EURIPIDES.—26.—*Alceſtis*, with English Notes.

In demy 12mo.

EURIPIDES.—27.—*Oreſtes*.

In demy 12mo.

EURIPIDES.—28.—*Extracts from the remaining Plays.*

In demy 12mo.

SOPHOCLES.—29.—*Extracts from the remaining Plays.*

In demy 12mo.

ÆSCHYLUS.—30.—*Prometheus Vincſtus*.

In demy 12mo.

ÆSCHYLUS.—31.—*Persæ*.

In demy 12mo.

ÆSCHYLUS.—32.—*Septem contra Thebas*.

In demy 12mo.

ÆSCHYLUS.—33.—*Choëphoræ*.

In demy 12mo.

ÆSCHYLUS.—34.—*Eumenides*.

In demy 12mo.

ÆSCHYLUS.—35.—*Agamemnon*.

In demy 12mo.

ÆSCHYLUS.—36.—*Supplices*.

In demy 12mo.

PLUTARCH.—37.—*Select Lives*.

In demy 12mo.

ARISTOPHANES.—38.—*Clouds*.

In demy 12mo.

ARISTOPHANES.—39.—*Frogs*.

In demy 12mo.

ARISTOPHANES.—40.—*Selections from the remaining Comedies.*

In demy 12mo, boards, price 1s.

THUCYDIDES.—41.—*I.*, with English Notes.

In demy 12mo.

THUCYDIDES.—42.—*II.*

John Weale, 59, High Holborn, London, W.C.

MR. WEALE'S CLASSICAL SERIES.

THEOCRITUS.—43.—Select Idyls.
In demy 12mo.

PINDAR.—44.
In demy 12mo.

SOCRATES.—45.
In demy 12mo.

HESIOD.—46.
In demy 12mo.

**MR. WEALE'S PUBLICATIONS OF WORKS
ON ARCHITECTURE, ENGINEERING, AND THE
FINE ARTS.**

In 1 large Atlas, folio Volume, with fine Plates, price £4 4s.

“**BRITISH GOVERNMENT WORK.**”—THE
ARCHITECTURAL ANTIQUITIES AND RESTO-
RATION OF ST. STEPHEN'S CHAPEL, WESTMINSTER
(late the House of Commons).

Fine Plates and Vignettes, Atlas folio, price £3 10s.

“**NORWEGIAN GOVERNMENT WORK.**”
—THE CATHEDRAL OF THRONDHHEIM, IN
NORWAY. Text by Professor MUNCH; drawings by H. E.
SCHIRMER, Architect.

Large Atlas folio, 4 livraisons, published in Madrid, at 100 reals
each, or £1 in England. Illustrated by beautifully executed
Engravings, some of which are coloured.

“**SPANISH GOVERNMENT WORK.**”—
MONUMENTS ARCHITECTONQUES DE L'ES-
PAGNE, PUBLIÉS AUX FRAIS DE LA NATION.—PART I
Provincia de Toledo, Granada, Alcalá de Henares.—PART 2. Cate-
dral Toledo, Detalles.—PART 3. Granada, Segovia, Toledo, Sala-
manca.—PART 4. Santa Maria de Alcalá de Henares, Casa Lonja de
Valencia, Toledo, Segovia, &c.—This work surpasses in beauty all
other works.

Columbier folio plates, with text also uniform, with gold borders,
and sumptuously bound in red morocco, gilt; gilt leaves, £12 12s.,
Columbier folio plates, with text also uniform, with gold borders,
and elegantly half-bound in morocco, gilt, £10 10s.; Plates in
Columbier folio, and text in imperial 4to, half-bound in morocco,
gilt, £7 7s.; Plates in Columbier folio, and text in imperial 4to,
in cloth extra, boards and lettered, £4 14s. 6d.

THE VICTORIA BRIDGE, AT MONTREAL,
IN CANADA. — Elaborately illustrated by views, plans,
elevations, and details of the Bridge; together with the illustrations
of the Machinery and Contrivances used in the construction of this
stupendously important and valuable engineering work. The whole
produced in the finest style of art, pictorially and geometrically
drawn, and the views highly coloured, and a descriptive text.
Dedicated to His Royal Highness the Prince of Wales. By JAMES
HODGES, Engineer to the Contractors. Engineers: ROBERT
STEPHENSON and ALEX. M. ROSS. Contractors: Sir S.
MORTON PETO, Bart., M.P., THOMAS BRASSEY, and ED-
WARD LADD BETTS, Esqrs.

John Weale, 59, High Holborn, London, W.C.

MR. WEALE'S WORKS ON ARCHITECTURE, ENGINEERING, FINE ARTS, &c.

In one imperial folio volume, with exquisite illustrative Plates from costly Drawings made by the most eminent artists, half-bound very neat, price £5 6s. Only 150 copies printed for sale.

PROFESSOR COCKERELL'S WORK.— THE TEMPLES OF JUPITER PANHELLENIUS AT ÆGINA, AND OF APOLLO EPICURIUS AT BASSÆ, NEAR PHIGALIA, IN ARCADIA.

It is proposed to publish the Life and Works of the late

ISAMBARD KINGDON BRUNEL, F.R.S.,
Civil Engineer. — The genius, talent, and great enterprise of the late Mr. Brunel has a world-wide fame, his whole life was devoted alone to the science of his profession, not in imitation or copying others, but in invention. In finding out new roads to the onward advancement of his Art, the lifting up from the slow and beating path of Engineering Art, new ideas and realities, and which has or have given to England a name for reference and of renowned intelligence in this Art.

Just published, in 4to, with 100 Engravings, price, bound, 21s. THE PRACTICAL HOUSE CARPENTER.—

More particularly for country practice, with specifications, quantities, and contracts: also containing—1. Designs for the Centering of Groins, Niches, &c.; 2. Designs for Roofs and Staircases. 3. The Five Orders laid down to a scale; 4. Modern Method of Trussing Girders, Joints of Carpenters' work; 5. Designs for Modern Shop Fronts with their details; 6. Designs for Modern Doors with their details; 7. Designs for Modern Windows, with their details, and for Villa Architecture. The whole amply described, for the use of the Operative Carpenter and Builder. Firstly written and published by WILLIAM PAIN. Secondly, with Modern Designs, and Improvements, by S. H. BROOKS, Architect.

In 1861 will be published a volume in 12mo, entitled
A DIGEST OF PRICES of Works in Civil Engineering and Railway Engineering, Mechanical Engineering, Tools, Wrought and Cast Iron Works, Stone, Timber and Wire Works, and every kind of information that can be obtained and made useful in Estimating, Specifying, and Reporting.

In 4to, 2s. 6d.
AIRY, ASTRONOMER ROYAL, F.R.S., &c.—
Results of Experiments on the Disturbance of the Compass in Iron-built Ships.

In a sheet, 8s., in case, 8s. 6d.
ANCIENT DOORWAYS AND WINDOWS
(Examples of). Arranged to illustrate the different styles of Gothic Architecture, from the Conquest to the Reformation.

In 1 vol. imperial 4to, with 20 fine Plates, neatly half-bound in cloth, £1 5s.
ANCIENT DOMESTIC ARCHITECTURE.—
Principally selected from original drawings in the collection of the late Sir William Burroll, Bart., with observations on the application of ancient architecture to the pictorial composition of modern edifices.

The stained glass fac-simile. 4s. 6d., in an extra case, or in a sheet, 3s. 6d.
ANGLICAN CHURCH ORNAMENT.—
Wherein are figured the Saints of the English calendar, with their appropriate emblems; the different styles of stained glass; and various sacred symbols and ornaments used in churches.

John Weale, 59, High Holborn, London, W.C.

MR. WEALE'S WORKS ON ARCHITECTURE, ENGINEERING, FINE ARTS, &c.

In 4to, 1s. 6d.

ARAGO, Mons. — Report on the Atmospheric System, and on the proposed Atmospheric Railway at Paris.

In 4to, with about 500 Engravings, some of which are highly coloured, 4 vols., original copies, half-bound in morocco, £6 6s.

ARCHITECTURAL PAPERS.

2 Engravings, in folio, useful to learners and for schools, 2s. 6d.

ARCHITECTURAL ORDERS (FIVE) AND THEIR ENTABLATURES, drawn to a larger scale, with Figured Dimensions.

4to, 1s.

ARNOLLET, M. — Report on his Atmospheric Railway.

In 4to, 10 Plates, 7s. 6d.

ATMOSPHERIC RAILWAYS. — THREE REPORTS on improved methods of Constructing and Working Atmospheric Railways. By R. MALLET, C.E.

In 8vo, 1s. 6d.

BARLOW, P. W. — Observations on the Niagara Railway Suspension Bridge.

In large 4to, very neat half-morocco, 18s., with Engravings.

BARRY, SIR CHARLES, R.A., &c. — Studies of Modern English Architecture. By W. H. LEEDS; The Travellers' Club-House, illustrated by Engravings of Plans, Sections, Elevations, and details.

In 1 Vol., large 8vo, with coloured Plates, half-morocco, price £1 1s.

BEWICK'S (J. G.) GEOLOGICAL TREATISE ON THE DISTRICT OF CLEVELAND IN NORTH YORKSHIRE, its Ferruginous Deposits, Lias and Oolites; with some Observations on Ironstone Mining.

In 8vo, with Plates. Price 4s.

BINNS, W. S. — Work on Geometrical Drawing, embracing Practical Geometry, including the use of Drawing Instruments, the construction and use of Scales, Orthographic Projection, and Elementary Descriptive Geometry.

In 4to, with 105 Illustrative Plates, cloth boards, £1 11s. 6d.

BLASHFIELD, J. M., M. R. Inst., &c. — SELECTIONS OF VASES, STATUES, BUSTS, &c, from TERRA COTTAS.

In 8vo, Woodcuts, 1s.

BLASHFIELD, J. M., M. R. Inst., &c. — ACCOUNT OF THE HISTORY AND MANUFACTURE OF ANCIENT AND MODERN TERRA COTTA.

In 4to, 2s. 6d.

BODMER, R., C.E. — On the Propulsion of Vessels by the Screw.

15s.

BRIDGE. — A large magnificent Plate, 3 feet 6 inches by 2 feet, on a scale of 25 feet to an inch, of LONDON BRIDGE; containing Plan and Elevation. Engraved and elaborately finished. The Work of the RENNIES.

John Weale, 59, High Holborn, London, W.C.

MR. WEALE'S WORKS ON ARCHITECTURE, ENGINEERING, FINE ARTS, &c.

BRIDGE. — ^{10s.} Plan and Elevation, on a scale of 10 feet to an Inch, of STAINES BRIDGE; a fine Engraving. The work of the RENNIES.

In royal 8vo, with very elaborate Plates (folded), £1 10s.
BRIDGES, SUSPENSION. — An Account, with Illustrations, of the Suspension Bridge across the River Danube, by Wm. T. CLARK, F.R.S.

In 4 vols., royal 8vo, bound in 3 vols., half-morocco, price £1 10s.
BRIDGES. — THE THEORY, PRACTICE, AND ARCHITECTURE OF BRIDGES OF STONE, IRON, TIMBER, AND WIRE; with Examples on the Principle of Suspension; illustrated by 138 Engravings and 92 Woodcuts.

In one large 8vo volume, with explanatory Text, and 68 Plates comprising details and measured dimensions. Bound in half-morocco, uniform with the preceding work, price £2 10s.

BRIDGES. — SUPPLEMENT TO "THE THEORY, PRACTICE, AND ARCHITECTURE OF BRIDGES OF STONE, IRON, TIMBER, WIRE, AND SUSPENSION."

1 large folio Engraving, price 7s. 6d.

BRIDGE across the Thames.—SOUTHWARK IRON BRIDGE.

1 large folio Engraving, price 5s.

BRIDGE across the Thames. — WATERLOO STONE BRIDGE.

1 very large Engraving, price 5s.

BRIDGE across the Thames. — VAUXHALL IRON BRIDGE.

1 very large Engraving, price 4s. 6d.

BRIDGE across the Thames.—HAMMERSMITH SUSPENSION BRIDGE.

1 large Engraving, price 4s. 6d.

BRIDGE (the UPPER SCHUYLKILL) at PHILADELPHIA, the greatest known span of one arch, covered.

1 large Engraving, price 3s. 6d.

BRIDGE (the SCHUYLKILL) at PHILADELPHIA, covered.

1 large Engraving, price 3s. 6d.

BRIDGE. — ON THE PRINCIPLE OF SUSPENSION, by Sir I. BRUNEL, in the ISLAND OF BOURBON.

1 large Engraving, price 4s.

BRIDGE. — PLAN and ELEVATION of the PATENT IRON BAR BRIDGE over the River Tweed, near Berwick.

34 Plates, folio, £1 1s., boards.

BRIDGEN, R. — Interior Decorations, Details, and Views of Sefton Church, Lancashire, erected in the reign of Henry VIII.

John Weale, 59, High Holborn, London, W.C.

MR. WEALE'S WORKS ON ARCHITECTURE, ENGINEERING, FINE ARTS, &c.

1 large Engraving, price 3s. 6d.
BRITTON'S (John) VIEWS of the WEST FRONTS of 14 ENGLISH CATHEDRALS.

1 large Engraving in outline, price 2s. 6d.
BRITTON'S (John) PERSPECTIVE VIEWS of the INTERIOR of 14 CATHEDRALS.

In 4to, 2s. 6d.
BRODIE, R., C.E. — Rules for Ranging Railway Curves, with the Theodolite, and without Tables.

1 large Engraving, price 4s. 6d.
BROWN'S (Capt. S.) CHAIN PIER at Brighton, with Details.

The Text in one large volume 8vo, and the Plates, upwards of 70 in number, in an atlas folio volume, very neatly half-bound, £2 10s.

BUCHANAN, R. — PRACTICAL ESSAYS ON MILL WORK AND OTHER MACHINERY; with Examples of Tools of modern invention; first published by ROBERT BUCHANAN, M.E.; afterwards improved and edited by THOMAS TREDGOLD, C.E.; and re-edited, with the improvements of the present age, by GEORGE RENNIE, F.R.S., C.E., &c., &c. The whole forming 70 Plates, and 103 Woodcuts.
 John Weale, 59, High Holborn, London, W.C.

Text in royal 8vo, and Plates in Imperial folio, 18s.
BUCHANAN, R. — SUPPLEMENT. — PRACTICAL EXAMPLES ON MODERN TOOLS AND MACHINES; a Supplementary Volume to Mr. RENNIE'S edition of BUCHANAN "On Mill-Work and Other Machinery," by TREDGOLD. The work consists of 18 Plates.

In 8vo, with Plates, 2nd Edition, 1s. 6d.
BURN, C., C.E.—On Tram and Horse Railways.

In one volume, 4to, 21 Plates, half-bound in morocco, £1 1s.
BURY, T., Architect. — Examples of Ancient Ecclesiastical Woodwork.

7s. 6d.
CALCULATOR (THE): Or, TIMBER MERCHANT'S AND BUILDER'S GUIDE. By WILLIAM RICHARDSON and CHARLES GANE, of Wisbeach.

In 8vo, Plates, cloth boards, 7s. 6d.
CALVER, E. K., R.N.—THE CONSERVATION AND IMPROVEMENT OF TIDAL RIVERS.

In 8vo, Woodcuts, 1s. 6d.
CALVER, E. K., R.N.—ON THE CONSTRUCTION AND PRINCIPLE OF A WAVE SCREEN, designed for the Formation of Harbours of Refuge.

In 4to, half-bound, price £1 5s.
CARTER, OWEN B., Architect.—A SERIES OF THE ANCIENT PAINTED GLASS OF WINCHESTER CATHEDRAL, Examples of. 28 Coloured Illustrations.

In 4to, 17 Plates, half-bound, 7s. 6d.
CARTER, OWEN B., Architect.—ACCOUNT OF THE CHURCH OF ST. JOHN THE BAPTIST, at Bishopstone, with Illustrations of its Architecture.
 John Weale, 59, High Holborn, London, W.C.

MR. WEALE'S WORKS ON ARCHITECTURE, ENGINEERING, FINE ARTS, &c.

In 4to, with 19 Engravings, £1 1s.

CHATEAUNEUF, A. de, Architect.—*Architettura Domestica*; a Series of very neat examples of Interiors and Exteriors of residences in the Italian style.

Large 4to, in half-red morocco, price £1 8s.

CHIPPENDALE, INIGO JONES, JOHNSON, LOCK, and PETHER.—Old English and French Ornaments: comprising 244 designs on 105 Plates of elaborate examples of Hall Glasses, Picture Frames, Chimney-pieces, Ceilings, Stands for China, Clock and Watch Cases, Girandoles, Brackets, Grates, Lanterns, Ornamental Furniture, Ornaments for brass workers and silver workers, real ornamental iron work Patterns, and for carvers, modellers, &c., &c., &c.

4to, third Edition with additions, price £1 11s. 6d.

CLEGG, SAM., C.E.—*A PRACTICAL TREATISE ON THE MANUFACTURE AND DISTRIBUTION OF COAL GAS*, illustrated by Engravings from Working Drawings, with General Estimates.

In 4to, Plates, and 76 Woodcuts, boards, price 6s.

CLEGG, SAM., C.E.—*ARCHITECTURE OF MACHINERY*. An Essay on Propriety of Form and Proportion. For the use of Students and Schoolmasters.

In 8vo, 1s.

COLBURN, Z.—On Steam Boiler Explosions.

One very large Engraving, price 4s. 6d.

CONEY'S (J.) Interior View of the Cathedral Church of St. Paul.

In 4to, on card board, 1s.

COWPER, C.—Diagram of the Expansion of Steam.

In one vol. 4to, with 20 Folding Plates, price £1 1s.

CROTON AQUEDUCT.—Description of the New York Croton Aqueduct, in 20 large detailed and engineering explanatory Plates, with text in the English, German, and French languages, by T. SCHRAMKE, C.E.

In demy 12mo, cloth, extra bound and lettered, price 4s.

DENISON.—*A Rudimentary Treatise on Clocks and Watches, and Bells*; with a full account of the Westminster Clock and Bells, by EDMUND BECKET DENISON, M.A., Q.C. Fourth Edition re-written and enlarged, with Engravings.

In royal 4to, cloth boards, price £1 11s. 6d.

DOWNES, CHARLES, Architect.—*Great Exhibition Building*. The Building erected in Hyde Park for the Great Exhibition, 1851; 28 large folding Plates, embracing Plans, Elevations, Sections, and Details, laid down to a large scale, and the Working and Measured Drawings.

DRAWING BOOKS.—Showing to Students the superior method of Drawing and Shadowing.

DRAWING BOOK.—*COURS ELEMENTAIRES DE LAVIS APPLIQUE A L'ARCHITECTURE*; folio volume, containing 40 elaborately engraved Plates, in shadows and tints, very finely executed, by the best artists in France. £2. Paris.

John Weale, 59, High Holborn, London, W.C.

MR. WEALE'S WORKS ON ARCHITECTURE, ENGINEERING, FINE ARTS, &c.

DRAWING BOOK.—COURS ÉLÉMENTAIRES DE LAVIS APPLIQUÉ À MÉCANIQUE) folio volume, containing 60 elaborately engraved Plates, in shadows and tints, very finely executed, by the best artists in France. £2 10s. Paris.

DRAWING BOOK.—COURS ÉLÉMENTAIRES DE LAVIS APPLIQUÉ À ORNEMENTATION; folio volume, containing 20 elaborately engraved Plates, in shadows and tints, very finely executed, by the best artists in France. £1. Paris.

DRAWING BOOK.—ÉTUDES PROGRESSIVES ET COMPLÈTES D'ARCHITECTURE DE LAVIS, par J. B. TRITON; large folio, 24 fine Plates, comprising the Orders of Architecture, mouldings, with profiles, ornaments, and forms of their proportion, art of shadowing doors, balusters, parterres, &c., &c., &c. £1 4s. Paris.

In 12mo, cloth boards, lettered, price 5s.

ECKSTEIN, G. F.—A Practical Treatise on Chimneys; with remarks on Stoves, the consumption of Smoke and Coal, Ventilation, &c.

Plates, imperial 8vo, price 7s.

ELLET, CHARLES, C. E., of the U. S.—Report on the Improvement of Kanawha, and incidentally of the Ohio River, by means of Artificial Lakes.

In 8vo, with Plates, price 12s.

EXAMPLES of Cheap Railway Making, American and Belgian.

In one vol. 4to, 49 Plates, with dimensions, extra cloth boards, price 21s.

EXAMPLES for Builders, Carpenters, and Joiners; being well-selected Illustrations of recent Modern Art and Construction.

With Engravings and Woodcuts, price 12s.

FROME, Lieutenant-Colonel, R.E.—Outline of the Method of conducting a Trigonometrical Survey, for the Formation of Topographical Plans; and Instructions for filling in the Interior Detail, both by Measurement and Sketching; Military Reconnaissances, Levelling, &c., &c., together with Colonial Surveying.

In 4to, with Plates, price 7s. 6d.

FAIRBAIRN, W., C.E., F.R.S.—ON WATER-WHEELS, WITH VENTILATED BUCKETS.

In royal 8vo, with Plates and Woodcuts, Second Edition, much improved, price, in extra cloth boards, 16s.

FAIRBAIRN, W., C.E., F.R.S.—ON THE APPLICATION OF CAST AND WROUGHT IRON TO BUILDING PURPOSES.

In imperial 8vo, with fine Plates, a re-issue, price 16s., or 21s. in half-morocco, gilt edges.

FERGUSON'S (J.) Essay on the Ancient Topography of Jerusalem, with restored Plans of the Temple, &c.

In 8vo, sewed in wrapper, price 2s.

GILL, J.—ESSAY ON THE THERMODYNAMICS OF ELASTIC FLUIDS, by JOSEPH GILL, with Diagrams.

John Weale, 59, High Holborn, London, W.C.

MR. WEALE'S WORKS ON ARCHITECTURE, ENGINEERING, FINE ARTS, &c.

Plates, 8vo, boards, 5s.

GWILT, JOSEPH, Architect.—TREATISE ON THE EQUILIBRIUM OF ARCHES.

In 8vo, cloth boards, with 8 Plates, 4s. 6d.

HAKEWELL, S. J.—Elizabethan Architecture ;
Illustrated by parallels of Dorton House, Hatfield, Long-
leat, and Wollaton, in England, and the Palazzo Della Cancelleria
at Rome.

8vo, with a Map, 1s.

HAMILTON, P. S., Barrister-at-Law, Halifax
Nova Scotia—Nova Scotia considered as a Field for Emi-
gration.

In Imperial 8vo, Third Edition, with additions, 11 Plates, cloth
boards, 8s.

HART, J., On Oblique Bridges. — A Practical
Treatise on the Construction of Oblique Arches.

In 4to, with Woodcuts, 3s. 6d.

HEALD, GEORGE, C.E.—System of Setting Out
Railway Curves.

Royal 8vo, Plates and Woodcuts, price 12s. 6d.

HEDLEY, JOHN.—Practical Treatise on the
Working and Ventilation of Coal Mines, with Suggestions
for Improvements in Mining.

Two Vols., demy 12mo, In cloth extra boards and lettered, price
12s. 6d.

HOMER.—The Iliad and Odyssey, with the
Hymns of Homer, Edition with an accession of English notes
by the Rev. T. H. L. LEARY, M.A.

In 8vo, with Engravings, cloth boards, Third Edition, 10s. 6d.

HOPKINSON, JOSEPH, C.E.—The Working of
the Steam Engine Explained by the use of the Indicator.

In 8vo, in boards, 18s.

HUNTINGTON, J. B., C.E.—TABLES and
RULES for Facilitating the Calculation of Earthwork, Land,
Curves, Distances, and Gradients, required in the Formation of
Railways, Roads, and Canals.

Separate from the above, price 3s.

HUNTINGTON, J. B., C.E.—THE TABLES
OF GRADIENTS.

10 Plates, 8vo, bound, 5s.

INIGO JONES.—Designs for Chimney Glasses
and Chimney Pieces of the Time of Charles the 1st.

In a sheet, 2s.

IRISH.—Plantation and British Statute Measure
(comparative Table of), so that English Measure can be trans-
ferred into Irish, and vice versa.

In 4to, with 8 Engravings, In a wrapper, 6s.

**IRON.—ACCOUNT OF THE CONSTRU-
TION OF THE IRON ROOF OF THE NEW HOUSES
OF PARLIAMENT, with elaborate Engravings of details.**

In Imperial 4to, with 50 Engravings, and 2 fine Woodcuts, half-
bound in morocco, £1 4s.

IRON.—DESIGNS OF ORNAMENTAL
GATES, LODGES, PALISADING, AND IRON-WORK OF
THE ROYAL PARKS, with some other Designs.

John Weale, 59, High Holborn, London, W.C.

MR. WEALE'S WORKS ON ARCHITECTURE, ENGINEERING, FINE ARTS, &c.

In 4to, with 10 Plates, 12s.

JEBB'S, Colonel, Modern Prisons.—Their Construction and Ventilation.

In 3 vols. 8vo, with 26 elaborate Plates, cloth boards, £2 2s.

JONES, Major-Gen. Sir John, Bart.—Journal of the Sieges carried on by the Army under the Duke of Wellington in Spain, between the years 1811 and 1814, with an Account of the Lines of Torres Vedras. By Major-Gen. Sir JOHN T. JONES, Bart, K.C.B. Third Edition, enlarged and edited by Lieut.-General Sir HARRY D. JONES, Bart.

16mo, cloth boards, 2s. 6d.

KENNEDY AND HACKWOOD'S Tables for Setting out Curves.

In 4to, 37 Plates, half-cloth boards, 9s.

KING, THOMAS.—The Upholsterer's Guide; Rules for Cutting and Forming Draperies, Valances, &c.

Illustrated by large Draughts and Engravings. In 1 volume 4to, text, and a large atlas folio volume of Plates, half-bound, £6 6s.

KNOWLES, JOHN, F.R.S.—The Elements and Practice of Naval Architecture; or, A Treatise on Ship Building, theoretical and practical, on the best principles established in Great Britain; with copious Tables of Dimensions, Scantlings, &c. The Third Edition, with an Appendix, containing the principles of constructing the Royal and Mercantile Navies, by Sir ROBERT SEPPINGS.

41 Plates of a fine and an elaborate description in large atlas folio half-bound, £2 12s. 6d.; with the text half-bound in 4to.

LOCOMOTIVE ENGINES.—The Principles and Practice and Explanation of the Machinery of Locomotive Engines in operation.

In 12mo, sewed, 1s.

MAIN, Rev. ROBERT.—An Account of the Observatories in and about London.

4to, in boards, 15s.

MANUFACTURES AND MACHINERY.—

Progress of, in Great Britain, as exhibited chiefly in Chronological notices of some Letters Patent granted for Inventions and Improvements, from the earliest times to the reign of Queen Anne.

16mo, 2s. 6d.

MAY, R. C., C.E.—Method of setting out Railway Curves.

Imperial 4to, with fine Illustrations, extra cloth boards, £1 5s., or half-bound in morocco, £1 11s. 6d.

METHVEN, CAPTAIN ROBERT.—THE LOG OF A MERCHANT OFFICER, Viewed with Reference to the Education of Young Officers and the Youth of the Merchant Service. By ROBERT METHVEN, Commander in the Peninsular and Oriental Company's Service.

In royal 8vo, 1s. 6d.

METHVEN, CAPTAIN ROBERT.—NARRATIVES WRITTEN BY SEA COMMANDERS. ILLUSTRATIVE OF THE LAW OF STORMS. The "Blenheim" Hurricane of 1851, with Diagrams.

Part 1, large 8vo, 5s. Part 2, in preparation.

MURRAY, JOHN, C.E.—A Treatise on the Stability of Retaining Walls, elucidated by Engravings and Diagrams.

John Weale, 59, High Holborn, London, W.C.

MR. WEALE'S WORKS ON ARCHITECTURE, ENGINEERING, FINE ARTS, &c.

On a large folio sheet, price 2s. 6d.

NEVILLE, JOHN, C.E., M.R.I.A. — OFFICE HYDRAULIC TABLES: for the use of Engineers engaged in Water Works, giving the Discharge and Dimensions of River Channels and Pipes.

In 8vo, Second and much Improved Edition, with an Appendix, cloth boards, price 16s.

NEVILLE, JOHN, C.E., M.R.I.A. — HYDRAULIC TABLES, COEFFICIENTS, AND FORMULÆ; for Finding the Discharge of Water from Orifices, Notches, Weirs, Pipes, and Rivers, with Extensive Additions, New Formulas, Tables, and General Information on Rain-Fall Catchment-Basins, Drainage, Sewerage, Water Supply for Towns and Mill Power.

On 33 folio Plates, 12s.

ORNAMENTS. — Ornaments displayed on a full size for Working, proper for all Carvers, Painters, &c., containing a variety of accurate examples of foliage and friezes.

Plates, 8vo, 2s. 6d.

O'BRIEN'S, W., C.E. — Prize Essay on Canals and Canal Conveyance.

In demy 8vo, cloth, boards, 12s.

PAMBOUR, COUNT DE — STEAM ENGINE; the Theory of the Proportions of Steam Engines, and a series of practical formulæ.

In 8vo, cloth, boards, with Plates, a second edition, 18s.

A PRACTICAL TREATISE ON LOCOMOTIVE ENGINES UPON RAILWAYS. — With practical Tables and an Appendix, showing the expense of conveying Goods by means of Locomotives on Railroads. By COUNT F. M. G. DE PAMBOUR.

4to, 72 finely executed Plates, in cloth, £1 16s.

PARKER, CHARLES, Architect, F.I.B.A. — The Rural and Villa Architecture of Italy, portraying the several very interesting examples in that country, with Estimates and Specifications for the application of the same designs in England; selected from buildings and scenes in the vicinity of Rome and Florence, and arranged for Rural and Domestic Buildings generally.

Price, complete, £2 2s. In 4to.

POLE, WILLIAM, M. Inst., C. E. — CORNISH PUMPING ENGINE; designed and constructed at the Hayle Copper House in Cornwall, under the superintendence of CAPTAIN JENKINS; erected and now on duty at the Coal Mines of Languin, Department of the Loire Inferieur, Nantes. Nine elaborate Drawings, historically and scientifically described.

With Plate. 10s. 6d.

AN ANALYTICAL INVESTIGATION OF THE ACTION OF THE CORNISH PUMPING ENGINE. — This Third Part sold separately from above.

28s. bound in 4to size.

PORTFOLIO OF ENGINEERING ENGRAVINGS. — Useful to Students as a Text Book, or a Drawing Book of Engineering and Mechanics; being a series of Practical Examples in Civil, Hydraulic, and Mechanical Engineering. Fifty Engravings to a scale for drawing.

John Weale, 59, High Holborn, London, W.C.

MR. WEALE'S WORKS ON ARCHITECTURE, ENGINEERING, FINE ARTS, &c.

50 Plates, 28s., boards.

PORTFOLIO OF GREEK ARCHITECTURE.

—Or, Dilettanti Drawing Book; Architectural Engravings, with descriptive Text. Being adapted as studies of the best Classic Models in the Grecian style of Architecture.

50 Plates, £1 8s., bound.

PORTFOLIO OR DRAWING BOOK OF GOTHIC CHURCH ARCHITECTURE.—Of the periods of the 14th, 15th, and 16th centuries. Useful to Architects, Builders, and Students.

25 Plates, folio. 25s.

PORTFOLIO OF ARCHÆOLOGICAL COLLECTIONS.—Of curious, interesting, and ornamental subjects and patterns for stained glass windows, from York.

18 Plates, 10s. 6d. Small folio.

PORTFOLIO OF ANCIENT CAPITAL LETTERS, MONOGRAMS, QUAIN T DESIGNS, &c.—Beautifully Coloured and Ornamented.

153 Plates, folio, half-bound in morocco, very neat, £4 4s.

PUBLIC WORKS OF GREAT BRITAIN.—

Consisting of Railways, Rails, Chairs, Blocks, Cuttings, Embankments, Tunnels, Oblique Arches, Viaducts, Bridges, Stations, Locomotive Engines, &c.; Cast-Iron Bridges, Iron and Gas Works, Canals, Lock-gates, Centering, Masonry and Brickwork for Canal Tunnels; Canal Boats: the London and Liverpool Docks, Plans and Dimensions, Dock gates, Walls, Quays, and their Masonry; Mooring-Chains; Plan of the Harbour and Port of London, and other important Engineering Works, with Descriptions and Specifications.

In two Parts. Imperial folio.

PUBLIC WORKS OF THE UNITED STATES OF AMERICA.

And the text in an 8vo Volume, price together £2 6s.

REPORTS, SPECIFICATIONS, AND ESTIMATES OF PUBLIC WORKS OF THE UNITED STATES OF AMERICA; explanatory of the Atlas Folio of Detailed Engravings, elucidating practically these important Engineering Works. The Plates are Engraved in the best style.

Imperial 8vo, 50 Engravings, £1 5s.

PAPERS AND PRACTICAL ILLUSTRATIONS OF PUBLIC WORKS OF RECENT CONSTRUCTION—BOTH BRITISH AND AMERICAN. Supplementary to previous Publications, and containing all the details of the Niagara Suspension Bridge.

Half-bound in morocco, finely coloured Plates, price £3 8s.

RAWLINSON'S, ROBERT, C.E.—Designs for Factory, Furnace, and other Tall Chimney Shafts. Tall chimneys are necessary for purposes of Trade and Manufactures. They are required for Factories, for Foundries, for Gas Works, for Chemical Works, for Baths and Wash-houses, and for many other purposes.

Third Edition, in royal 8vo, boards, with 13 Charts, &c., 12s.

REID, Major-General Sir W., F.R.S., &c.—AN ATTEMPT TO DEVELOP THE LAW OF STORMS by means of facts arranged according to place and time; and hence to point out a cause for the variable winds, with a view to practical use in navigation.

John Weale, 59, High Holborn, London, W.C.

MR. WEALE'S WORKS ON ARCHITECTURE, ENGINEERING, FINE ARTS, &c.

In royal 8vo, uniform with the preceding, 9s., with Cbarts and Woodcuts. The work together in 2 vols., £1 1s.

REID, Major-General Sir W., F.R.S., &c. — THE PROGRESS OF THE DEVELOPMENT OF THE LAW OF STORMS AND OF THE VARIABLE WINDS, with the practicable application of the subject to navigation.

Illustrated with 17 Plates, Third Edition, 8vo, cloth, 7s. 6d.

RICHARDSON, C. J., Architect. — A Popular Treatise on the Warming and Ventilation of Buildings; showing the advantage of the improved system of Heated Water Circulation. And a method to effect the combination of large and small pipes to the same apparatus, and ventilating buildings.

Bound in 2 vols., very neat, half-morocco, gilt tops, price £18.

RENNIE'S, Sir JOHN, F.R.S., Work on the Theory, Formation, and Construction of British and Foreign Harbours, Docks, and Naval Arsenals. This great work may now be had complete, 20 parts and supplement, price £16.

In 8vo, 2s.

RÉVY, J. L., C.E. — THE PROGRESSIVE SCREW AS A PROPELLER IN NAVIGATION.

12mo, cloth boards, 8s. 6d.

SIMMS, F. W. — Treatise on the principal Mathematical and Drawing Instruments employed by the Engineer, Architect, and Surveyor; with a description of the Theodolite, together with Instructions in Field Works.

4to, with fine Plates, a New Edition, extended, sewed, 5s.

SMITH, C. H., Sculptor. — Report and Investigation into the Qualifications and Fitness of Stone for Building Purposes.

In 1 vol. 8vo, in boards, 7s. 6d.

SMITH'S, Colonel of the Madras Engineers, Observations on the Duties and Responsibilities Involved in the Management of Mines.

8vo, cloth boards, with Index Map, 6s.

SOPWITH, THOMAS, F.R.S. — THE AWARD OF THE DEAN FOREST COMMISSIONERS AS TO THE COAL AND IRON MINES.

16 large folio Plates, £1 4s. Separately, 2s. each.

SOPWITH, THOMAS, F.R.S. — SERIES OF ENGRAVED PLANS OF THE COAL AND IRON MINES.

12 Plates, 4to, 6s. in a wrapper.

STAIRCASES, HANDRAILS, BALUSTRADES, AND NEWELS OF THE ELIZABETHAN AGE, &c. — Consisting of — 1. Staircase at Audley-end Old Manor House, Wilts; 2. Charlton House, Kent; 3. Great Ellingham Hall, Norfolk; 4. Dorfold, Cheshire; 5. Charterhouse; 6. Oak Staircase at Clare Hall, Cambridge; 7. Cromwell Hall, Highgate; 8. Ditto; 9. Catherine Hall, Cambridge; 10. Staircase by Inigo Jones at a house in Chandos Street; 11. Ditto at East Sutton; 12. Ditto, ditto. Useful to those constructing edifices in the early English domestic style.

Large atlas folio Plates, price £2 2s.

STALKARTT, M., N.A. — Naval Architecture; or, The Rudiments and Rules of Ship Building: exemplified in a Series of Draughts and Plans. No text.

John Weale, 59, High Holborn, London, W.C.

MR. WEALE'S WORKS ON ARCHITECTURE, ENGINEERING, FINE ARTS, &c.

With Illustrative Diagrams. In 8vo, 7s. 6d.

STEVENSON'S, THOMAS, C.E., of Edinburgh,
Description of the Different kinds of Lighthouse Apparatus.

8vo, 2s. 6d.

STEVENSON, DAVID, C.E., of Edinburgh. —
Supplement to his Work on Tidal Rivers.

Text in 4to, and large folio Atlas of 75 Plates, half-cloth boards,
£2 12s. 6d.

STEAM NAVIGATION. — Vessels of Iron and
Wood; the Steam Engine; and on Screw Propulsion. By
WM. FAIRBAIRN, F.R.S., of Manchester; Messrs. FORRESTER,
M.I.C.E., of Liverpool; JOHN LAIRD, M.I.C.E., of Birkenhead;
OLIVER LANG, (late) of Woolwich; Messrs. SEAWARD, Lime-
house, &c. &c. &c. Together with Results of Experiments on the
Disturbance of the Compass in Iron-built Ships. By G. B. AIRY,
M.A., Astronomer Royal.

10s.

ST. PAUL'S CATHEDRAL, LONDON, SEC-
TION OF. — The Original Splendid Engraving by J.
GWYN, J. WALE, decorated agreeably to the original intention
of Sir Christopher Wren; a very fine large print, showing distinctly
the construction of that magnificent edifice.

Size of Plate $4\frac{1}{2}$ feet in height, 10s.

ST. PAUL'S CATHEDRAL, LONDON, GREAT
PLAN. — J. WALE and J. GWYN'S GREAT PLAN,
accurately measured from the Building, with all the Dimensions
figured and in detail, description of Compartments by engraved
Writing.

Second Edition, greatly enlarged, royal 8vo, with Plates, cloth
boards, price 16s.

STRENGTH OF MATERIALS. — FAIRBAIRN,
WILLIAM, C.E., F.R.S., and of the Legion of Honour of
France. On the application of Cast and Wrought Iron to Building
Purposes.

With Plates and Diagrams. New Edition. The work complete
in 2 vols., bound in 1 vol., price, in cloth boards, 16s. The
second portion of the work, containing Mr. Hodgkinson's Experi-
mental Researches, may be had separately, price 9s.

STRENGTH OF MATERIALS. — HODGKIN-
SON, EATON, F.R.S., AND THOMAS TREDGOLD,
C.E. A PRACTICAL ESSAY ON THE STRENGTH OF CAST
IRON AND OTHER METALS; intended for the assistance of
engineers, ironmasters, millwrights, architects, founders, smiths
and others engaged in the construction of machines, buildings, &c.
By EATON HODGKINSON, F.R.S.

To be published in 1861, in crown 8vo, bound for use.

STRENGTH OF MATERIALS. — POLE, WIL-
LIAM, C.E., F.R.S. — Tables and popular explanations of
the Strength of Materials, of Wrought and Cast Iron with other
metals, for structural purposes; developing in a systematic form,
the strengths, bearings, weights, and forms of these materials, whe-
ther used as girders or arches, for the construction of bridges and
viaducts, public buildings, domestic mansions, private buildings,
columns or pillars, bressummers for warehouses, shops, working
and manufacturing factories, &c. &c. &c. The whole rendered of
easy reference for architects, builders, civil and mechanical engi-
neers, millwrights, ironfounders, &c. &c. &c., and forming Ready
Reckoner or Calculator.

John Weale, 59, High Holborn, London, W.C.

MR. WEALE'S WORKS ON ARCHITECTURE, ENGINEERING, FINE ARTS, &c.

30 very elaborately drawn Engravings. In large 4to, neatly half-bound and lettered, £1 1s. A few copies on large imperial size, extra half-binding, £1 11s. 6d.

TEMPLE CHURCH.—The Architectural History and Architectural Ornaments, Embellishments, and Painted Glass, of the Temple Church, London.

Part I., with 26 Engravings on Wood and Copper, in cloth boards, 4to, 15s.

THAMES TUNNEL.—A Memoir of the several Operations and the Construction of the Thames Tunnel, from Papers by the late Sir ISAMBARD BRUNEL, F.R.S., Civil Engineer.

Fourth Edition, with a Supplementary Addition, large 8vo, 12s. 6d.

THOMAS (LYNALL), F.R.S.L.—Rifled Ordnance.—A Practical Treatise on the Application of the Principle of the Rifle to Guns and Mortars of every calibre; to which is added a New Theory of the Initial Action and Force of Fixed Gunpowder plates.

In 4to, complete, cloth, Vol. I., with Engravings, £1 10s.; Vol. II., ditto, £1 8s.; Vol. III., ditto, £2 12s. 6d.

TRANSACTIONS OF THE INSTITUTION OF CIVIL ENGINEERS.

8 vols., numerous Engravings of Sections of Coal Mines, &c., large folding Plates, several of which are coloured, in large 8vo, half-bound in calf, price £1 1s. per volume.

TRANSACTIONS OF THE NORTH OF ENGLAND INSTITUTE OF MINING ENGINEERS.—Commencing in 1832, and continued to 1860.

A New Edition revised by the translator, and with additional Plates, in demy 12mo, India proof Plates and Vignettes, half-bound in morocco, gilt tops, price 12s. Only 25 printed on India paper.

VITRUVIUS.—The Architecture of Marcus Vitruvius Pollio in 10 Books. Translated from the Latin by JOSEPH GWILT, F.S.A., F.R.A.S.

In 4to, with Plates, 7s. 6d.

WALKER'S, THOMAS, Architect.—Account of the Church at Stoke Golding.

£1 10s.

WEALE'S QUARTERLY PAPERS ON ENGINEERING.—Vol. VI. (Parts 11 and 12 completing the work.) Comprising, "On the Principles of Water Power." Plates. Experiments on Locomotive Engines. Coloured Plates. On Naval Armaments. On the Mode of Forming Foundations under water and on bad ground. Plates. On the Improvement of the River Medway and of the Fort and Arsenal of Chatham. On the Improvement of Portsmouth Harbour. An Analysis of the Cornish Pumping. Plates. On Water Wheels. Plates.

Text in 8vo, cloth boards, and Plates in atlas folio, in cloth, 16s.

WHITE'S, THOMAS, N.A., Theory and Practice of Ship Building.

In 8vo, with a large Sectional Plate, 1s. 6d.

WHICHORD, JOHN, Architect.—OBSERVATIONS ON KENTISH RAG STONE AS A BUILDING MATERIAL.

John Weale, 59, High Holborn, London, W.C.

MR. WEALE'S WORKS ON ARCHITECTURE, ENGINEERING FINE ARTS, &c.

4to, coloured Plates, in half-morocco, 7s. 6d.

WHICCORD, JOHN, Architect.—HISTORY AND ANTIQUITIES OF THE COLLEGIATE CHURCH OF ALL SAINTS, MAIDSTONE.

In 4to, 6s.

WICKSTEED, THOMAS, C.E.—AN EXPERIMENTAL INQUIRY CONCERNING THE RELATIVE POWER OF, AND USEFUL EFFECT PRODUCED BY, THE CORNISH AND BOULTON & WATT PUMPING ENGINES, and Cylindrical and Waggon-Head Boilers.

In 8vo, 1s.

WICKSTEED, THOMAS, C.E.—FURTHER ELUCIDATION OF THE USEFUL EFFECTS OF CORNISH PUMPING ENGINES; showing the average working for long periods, &c., &c., &c.

£2 2s.

WICKSTEED, THOMAS, C.E.—THE ELABORATELY ENGRAVED ILLUSTRATIONS OF THE CORNISH AND BOULTON & WATT ENGINES erected at the East London Water Works, Old Ford. Eight large atlas folio very fine line engravings by GLADWIN, from elaborate drawings made expressly by Mr. WICKSTEED; folio, together with a 4to explanation of the plates, containing an engraving, by LOWRY, of Harvey and West's patent pump-valve, with specification.

With numerous Woodcuts.

WILLIAMS, C. WYE, Esq., M. Inst. C. E.—THE COMBUSTION OF COAL AND THE PREVENTION OF SMOKE, chemically and practically considered.

Imperial 8vo, with a Portrait, 2s. 6d.

WILLIAMS, C. WYE, Esq., M. Inst. C. E.—PRIZE ESSAY ON THE PREVENTION OF THE SMOKE NUISANCE, with a fine portrait of the Author.

With 3 Plates, containing 51 figures, 4to, 5s.

WILLIS, REV. PROFESSOR, M.A.—A system of Apparatus for the use of Lecturers and Experimenters in Mechanical Philosophy.

In 4to, bound, with 26 large plates and 17 woodcuts, 12s.

WILME'S MANUALS.—A MANUAL OF WRITING AND PRINTING CHARACTERS, both ancient and modern.

Maps and Plans, in 4to, plates coloured, half-bound morocco, £2.

WILME'S MANUALS.—A HANDBOOK FOR MAPPING, ENGINEERING, AND ARCHITECTURAL DRAWING.

Three Vols., large 8vo, £3.

WOOLWICH.—COURSE OF MATHEMATICS. This course is essential to all Students destined for the Royal Military Academy at Woolwich.

8vo, 1s.

YULE, MAJOR-GENERAL.—ON BREAK-WATERS AND BUOYS OF VERTICAL FLOATS.
John Weale, 59, High Holborn, London, W.C.

FOREIGN WORKS, KEPT IN STOCK AS FOLLOWS:—

Large folio, 32 plates, some coloured, and 12 woodcuts, 50 francs.
£2 10s.

ARCHITECTURE SUISSE.—Ou Choix de Maisons Rustiques des Alpes du Canton de Berne, par GRAFFINRIED et STÜRLER, Architectes. Berne, 1844.

Small folio, 52 most interesting and explanatory plates of Public Works, Bridges, Iron Works, &c., &c., &c., very neatly half-bound in morocco, £1 10s.

BAUERNFEIND, CARL MAX.—VORLEGE-BLAETTER ZUR BRUCKENBAU KUNDE. München.

Large folio, 36 plates of Byzantine capitals, 12s.

BYZANTINISCHE CAPITAELE.—München.

Second edition, 126 plates, large folio, best Paris edition, 100 f., printed on fine paper, half-cloth boards, £4 4s.

CALLIAT, VICTOR, ARCT.—Parallèle des Maisons de Paris, construites depuis 1830 jusqu'à nos jours.—1857.

Large folio, 60 francs, 60 plates, and several vignettes, £2 8s.

CANÉTO, F.—Sainte-Marié d'Auch. Atlas Monographique de Cette Cathédrale. The Plates consist principally of outline drawings of the Painted Glass Windows in this Cathedral.

120 plates, elegant in half-morocco extra, interleaved, £5 15s. 6d.

CASTERMAN, A.—PARALLÈLE des MAISONS de BRUXELLES et des PRINCIPALES VILLES de la BELGIQUE, construites depuis 1830 jusqu'à nos jours, représentées en plans, élévations, coupes et détails intérieurs et extérieurs.—Paris.

Small folio, 48 plates of edifices. £1 1s.

DEGEN, L.—LES CONSTRUCTIONS EN BRIQUES, composées et publiées. 8 livraisons.—1858.

Small folio, 48 plates of houses, parts of houses, details of all kinds of singularly beautiful woodwork, coloured plates in imitation of the objects given, £1 1s.

DEGEN, L.—LES CONSTRUCTIONS ORNAMENTALES EN BOIS, 8 livraisons.

In 3 very large folio parts, 35 fine plates, £1 11s. 6d.

GAERTNER, F. V.—The splendid works of M. GAERTNER of Munich, drawn to a very large size, consisting of the library in plans, elevations, interiors, details, and sections, and coloured ornaments. The church, with details, ornaments, &c.—München.

Small folio, 88 fine plates of the Architecture, ornament, and detail of the houses and churches of Germany during the middle age, very neatly half-bound in morocco, £2 12s. 6d.

KALLENBACH, C. C.—Chronologie der Deutsch-Mittelalterlichen Baukunst.—München. Fine Work.

The works of the great master KLENZIE of Munich, in 5 parts very large folio, 50 plates of elevations, plans, sections, details and ornaments of his public and private buildings executed in Munich and St. Petersburg, £2 2s.

KLENZE, LEO VON.—Sammlung Architectonischer Entwürfe, für die Ausführung bestimmt oder wirklich ausgeführt. Published in Munich.

John Weale, 59, High Holborn, London, W.C.

FOREIGN WORKS KEPT IN STOCK AS FOLLOWS:—

Upwards of 100 plates, large 4to, £2 12s. 6d.

PETIT, VICTOR.—CHATEAUX DE FRANCE.
Architecture Pittoresque, ou Monuments des quinzième et seizième siècles. Paris.

Livraisons 1 à 18, very finely executed plates, large Imperial folio,
£5 8s.

**CHATEAUX DE LA VALLÉE DE LA
LOIRE DES XV, XVI, ET COMMENCEMENT DU XVII
SIECLE.**—Paris, 1857—60.

4to, 96 plates, 72f.; £2 10s.

RECUEIL DE SCULPTURES GOTHIQUE.—
Dessinées et gravées à l'eau forte d'après les plus beaux monu-
ments construits en France depuis le onzième jusqu'au quinzième
siècle, par ADAMS, Inspecteur des travaux de la Sainte Chapelle.
Paris, 1856.

4 parts are published, price 14s.

**RAMÉE.—HISTOIRE GÉNÉRALE DE L'AR-
CHITECTURE.** L'histoire générale de l'Architecture, par
DANIEL RAMÉE, forme 2 vol. grande in 8vo, publiés en 8 fas-
cicules.

5 vols., large 8vo, numerous fine woodcuts, half morocco.

**VIOLET-LE-DUC. — DICTIONNAIRE RAI-
SONNE,** de l'Architecture Française du quinzième au seizième
siècle. Paris, 1854-8.

2 vols., extra Imperial folio, price £6 16s. 6d.

BADIA D'ALTACOMBA.—Storia e Descrizione
della Antico Sepolchro del Reali di Savola, fondata da Amedeo
III. rinnovata da Carlo Felice e Maria Christina.

79 livraisons in large 4to, 200 engravings, £8 18s. 6d.

BELLE ARTI.—Il Palazzo Ducale di Venezia,
illustrato da Francesco Zanotto. Venezia, 1846—1858.

2 vols. large 4to, 62 very neatly engraved outline Plates, £1 5s.

CANOVA.—Le Tombe ed i Monumenti Illustri
d'Italia. Milano.

2 vols. 4to, 67 elaborate Plates, £1 16s.

**CAVALIERI SAN-BERTOLO (NICOLA).—
ISTITUZIONI DI ARCHITETTURA STATICA E IDRAU-
LICA.** Mantova.

2 vols. Imperial folio, in parts of eight divisions, &c., New and much
Improved Edition, comprising 259 Plates of the Public Buildings
of Venice, plans, elevations, sections, and details, £8 18s. 6d.

CICOGNARA (COUNT).—Le Fabbriche e i Monu-
menti Cospicui di Venezia, illustrati da L. Cicognara, da A.
Diedo, e da G. A. Selva, edizione con copiose note ed aggiunte di
Francesco Zanotto, arricchita di nuove tavole e della Versione
Francesca. Venezia nullo stab. naz. di G. Antonelli a spese degli
edit. G. Antonelli e Lucleno Basadonna, 1858. The elaborately de-
scriptive text is in French and Italian, beautifully printed.

Copies elegantly half-bound in morocco, extra gilt, library copy
and interleaved, £12 12s. Venezia, 1858.

Folio, Portrait, and 147 Plates, consisting of subjects of public build-
ings, executed at Verona, plans, elevations, sections, details, and
ornaments, with some executed works at Venice. &c., £4 4s.

**FABBRICHE.—CIVILI ECCLESIASTICHE
E MILITARI** DI MICHELE SAN MICHELE disegnate
ed incise da RONZANI FRANCESCO e L.
GIROLAMO.

John Weale, 59, High Holborn, London, W.C.

FOREIGN WORKS KEPT IN STOCK AS FOLLOWS.

Large folio, containing a profusion of Plates of the palaces, theatres, hôtel de villes, and other public buildings in several parts of Italy. Elegantly half-bound in red morocco, extra gilt and interleaved, £6 6s.

FABBRICHE.—E DISEGNI D'ANTONIO DIEDO, NOBILE VENETO. Venezia.

36 livraisons, price £12 12s.

GALLERIA DI TORINO (LA REALE).—

Illustrata da R. D'AZEGLIO, Memb. dell' Accad., &c. &c.

Copies, Indian proofs, £18 18s.

* Bound copies in elegant half-morocco binding, India proof, £23 2s.

2 vols. folio, complete, 177 Plates of outline elevations, plans, interiors, details, &c., first impression, 150 francs, half-bound, £6 6s.

GAUTHIER, M.P., Architecte.—Les PLUS BEAUX ÉDIFICES de la VILLE de GENES et des ses ENVIRONS. Paris, 1830-2.

Folio, 109 Plates of plans, elevations, sections, and details, £2 8s.

GRANDJEAN de MONTIGNY et A. FAMIN.

—ARCHITECTURE TOSCANE, ou palais, maisons, et autres édifices, de la Toscane. Paris, 1815.

Oblong folio, containing a profusion of picturesque views of palaces and public buildings and scenes of Venice, executed in tinted lithography, with full descriptions attached to each. Elegant in half extra morocco, interleaved, £4 14s. 6d.

KIER, G.—VENEZIA MONUMENTALE PITTORESCA. Venezia.

Large folio, 61 livraisons or 3 vols., with 3 vols. of text in 4to, £18 18s.

LETAROUILLY, P.—Édifices de Rome Moderne. Paris, 1825-55.

Fine Plates of the New Palace of Justice, Senate House, &c., plans, elevations, sections, doors, &c., details of the several parts, &c., £1 1s.

MICHELA, IGNAZIO.—DESCRIZIONE e DISEGNI del PALAZZO dei MAGISTRATI SUPREMI di TORINO. Torino.

Large folio, 94 Plates, bound in extra half-morocco, gilt and interleaved, price £6 10s.

REYNAUD, J.—Trattato di Architettura, contenente nozioni generali sui Principii della Construzione e sulla storia dell' Arti, con annot. per cura di Lorenzo Urbani. Venezia, 1857.

4 Imperial bulky 8vo volumes, printed and published under authority, and treats of the early foundation of Venice and establishment as a kingdom, its wealth and commerce, and its once great political position, with Plates, £3 3s.

VENEZIA.—E le sue Lagune. Venezia, 1847.

VENEZIA.—Copies elegantly bound and gilt, £4 14s. 6d. Venezia, 1847.

In 2 large folio volumes, numerous and elaborately drawn Plates, very well executed in outline, altogether a very fine work. Very elegantly half-bound in morocco, extra gilt and interleaved, £12 12s.

ACCADEMIA DI BELLI ARTI.—Opere dei Grandi Concorsi Premiate dall' I. R. Accademia delle Belle Arti, in Milano, e pubblicate, per cura dell' Architetto, G. ALUISETTI—per la Classe di Ornato—per le Classi di Architettura, figura ed Ornato. Milano, 1825-29.

John Weale, 59, High Holborn, London, W.C.

FOREIGN WORKS, KEPT IN STOCK AS FOLLOWS:—

Atlas folio, very fine impressions, complete in 3 parts, Columbier folio, £3 13s. 6d. Elegantly half-bound in extra morocco and interleaved, £5 15s. 6d.

ALBERTOLLI, G.—*Alcune Decorazioni di Nobili Sale ed Altri Ornamenti.* Milano, 1787, 1824, 1838.

To be had separately, £1 8s.

ALBERTOLLI, G.—Part III., very frequently required to make up sets.

2 vols., folio, 80 Plates of the most exquisite kind in colours, far superior to any existing work of the present day, £7 10s.

HOFFMAN, ET KELLERHOVEN.—*Recueil de Dessins relatifs à l'Art de la Décoration chez tous les peuples et aux plus belles époques de leur civilisation, &c., destinés à servir de motifs et de matériaux aux peintres, décorateurs, peintres sur verre, et aux dessinateurs de fabriques.*

Price £1 1s.

HOPE, ALEXANDER J. BERESFORD, Esq.—*Abbildungen der Glasgemälde in der Salvator-Kirche zu Kilndown in der Grafschaft Kent. Copies of paintings on glass in Christ Church, Kilndown, in the county of Kent, executed in the Royal Establishment for Painting on Glass, Munich, by order of ALEXANDER J. BERESFORD HOPE, Esq., published by F. Eggert, Painter on Glass, München. The work contains one sheet with the dedication to A. J. B. HOPE, Esq., and fourteen windows; in the whole fifteen, beautifully engraved and carefully coloured.*

In large folio, 80 Plates, containing a profusion of rich Italian and other ornaments. Elegant in half-morocco, gilt, and interleaved, £6 8s.

JULIENNE, E.—*Industria Artistica o Raccolto di Composizioni e Decorazioni Ornamentali, come suppellettili, tappezzerie, armature, cristalli, soffitti, cornici, lampade, bronzi, &c.* Venezia, 1851—1858.

Prix 50f., in folio, £3.

LE PAUTRE.—*Collection des plus belles Compositions, gravées par DE CLOUX, Archte. L'Ouvrage contient cent planches.* Paris.

This unique collection is in 2 Vols. 4to, had its commencement in 1812, and contains upwards of 500 rich Designs. Price £5 5s.

METIVIER, MONS., Architecte.—The original Sketches, Drawings, and Tracings, in pencil and pen and ink, of executed Works and Proposals, displaying the genius of Mons. Metivier, as an architect of high attainments, whose recent death was much regretted in Bavaria. He was a native of France, and was induced to settle in Munich by the late Duke of Leuchtenberg, under whose patronage he was much employed in the construction of private edifices for the Bavarian nobility and gentry; and for decoration and fittings of them; his interiors are still much in admiration. He built a mansion for Prince Charles, in a most simple and elegant style (in Brienner Street), which is still now considered one of the purest buildings of Munich. The above Sketches are his professional life and practice.

Twelve Parts, in small oblong 4to, 60 coloured Plates of 90 elaborately coloured and gilt ornaments. £1 1s.

ORNAMENTENBUCH.—*Farbige Verzierungen für Fahrkanten, Zimmermalerei und andere Baugewerke.* München.

John Weale, 59, High Holborn, London, W.C.

FOREIGN WORKS, KEPT IN STOCK AS FOLLOWS:—

410 Plates, in two thick large 4to. Vols., designed and engraved by MM. Reister Arget, d'Hautel, de Wailly, Wagner, L. Feuchère et Regnier, &c. £5 5s.

ORNEMENTS.—Tirés ou imités des Quatre Écoles. Paris.

Six Parts, large folio, Plates beautifully coloured, in fac-similes of the Interiors, Ornaments, Compartments, Ceilings, &c. £2 12s. 6d. Also, elegantly half-bound in morocco gilt, £4 4s.


ROTTMANN, L.—Ornamente aus den vorzüg- lichsten Bauwerken Münchens. München.

Very elegant, in half red morocco, gilt, and interleaved, £7 17s. 6d.

**ZANETTI, G.—STUDII ARCHITETTONICO
ORNAMENTALI**, dedicati all' J. R. Accademia Veneta delle Belle Arti, seconda edizione con aggiunte del Prof. L. URBANI. 56 livraisons, in Imperial folio, about 200 of most elaborately designed subjects of Architecture and Interior Fittings, Designs for Chimney Pieces, Iron Work for Interiors and Exteriors, Gates and Wooden Gates, Garden Decorations, &c., &c., including the Appendices. Venezia.

A Catalogue, of 40 pages, to be had gratis; printed in demy 8vo.

Export Orders executed either for Principals abroad, or Merchants at home.



In Atlas of Plates and Text, 12mo, price 25s. together,

IRON SHIP BUILDING.

WITH

PRACTICAL ILLUSTRATIONS.

BY

JOHN GRANTHAM, N.A.

DESCRIPTION OF PLATES.

1. Hollow and Bar Keels, Stem and Stern Posts.
2. Side Frames, Floorings, and Bilge Pieces.
3. Floorings continued — Keelsons, Deck Beams, Gunwales, and Stringers.
4. Gunwales continued — Lower Decks, and Orlop Beams.
5. Angle-Iron, T Iron, Z Iron, Bulb Iron, as rolled for Iron Ship-Building.
6. Rivets, shown in section, natural size, Flush and Lapped Joints, with Single and Double Riveting.
7. Plating, three plans, Bulkheads, and modes of securing them.
8. Iron Masts, with Longitudinal and Transverse Sections.
9. Sliding Keel, Water Ballast, Moulding the Frames in Iron Ship-building, Levelling Plates.
10. Longitudinal Section, and Half-breadth Deck Plans of large Vessels, on a reduced scale.
11. Midship Sections of Three Vessels of different sizes.
12. *Large Vessel*, showing details.— *Fore End* in Section, and End View, with Stern Post, Crutches, Deck Beams, &c.
13. *Large Vessel*, showing details.— *After End* in section, with End View, Stern Frame for Screw, and Rudder.
14. *Large Vessel*, showing details.— *Midship Section*, Half breadth.
15. *Machines* for Punching and Shearing Plates and Angle-Iron, and for Bending Plates; Rivet Hearth.
16. *Machines*.— Garforth's Riveting Machine, Drilling and Counter Sinking Machine.
17. *Air Furnace* for Heating Plates and Angle-Iron; various Tools used in Riveting and Plating.
18. *Gunwale*, Keel, and Flooring; Plan for Sheathing Iron Ships with Copper.
19. Illustrations of the Magnetic Condition of various Iron Ships.
20. Gray's Floating Compass and Binnacle, with Adjusting Magnets.
21. Corroded Iron Bolt in Frame of Wooden Ship; Caulking Joints of Plates.
22. *Great Eastern*—Longitudinal Sections and Half-breadth Plans.
23. *Great Eastern*—Midship Section, with details.
24. *Great Eastern*—Section in Engine Room, and Paddle Boxes.

This Work may be had of Messrs. LOCKWOOD & Co., No. 7, Stationers' Hall Court, and also of Mr. WEALE; either the Atlas separately for 1*l.* 2*s.* 6*d.*, or together with the Text price as above stated.

Bradbury and Evans, Printers, Whitechapel.

